

DRAINAGE STRUCTURE SCHEDULE

LABEL	ROADWAY	STATION	OFFSET	54260311	54261327	54262315	54262318	60801008	60801018	60236200	60221100	X6020294
				TRAVERSABLE PIPE GRATE (FOOT)	CONC END SECTION, STD 542001, 27", 1:3 (EACH)	CONC END SECTION, STD 542006, 15", 1:3 (EACH)	CONC END SECTION, STD 542006, 18", 1:3 (EACH)	FLAP GATE 8" (EACH)	FLAP GATE 18" (EACH)	INLETS, TY A, TY 8 GR (EACH)	MH, TY A, 5', TY 1 FR, CLSD LID (EACH)	MH, TY A, 7', TY 1 FR, CLSD LID, REST. PLATE (EACH)
A1	2ND ST	12+57.9	84.8' RT	19.3	1							
A3	2ND ST	12+65.0	62.0' RT									1
A5	2ND ST	12+65.0	32.2' LT								1	
B2	2ND ST	12+11.8	53.1' RT				3		3			
B4	2ND ST	12+11.8	53.0' RT			1		1				
F2	2ND ST	10+55.0	35.0' RT							1		
-	I-64/55	123+85.0	17.8' RT									1
-	I-64/55	124+25.0	17.8' RT									1
TOTAL:				19	1	1	3	1	3	1	1	1

STORM SEWER /FORCE MAIN SCHEDULE

LABEL	STATION TO STATION			20800150	550A0340	550A0420			X0326934			Z0068300
				TRENCH BACKFILL (CU YD)	SS, CL A, TY 2 12" (FOOT)	SS, CL A, TY 2 27" (FOOT)	SS, DI, TY 2 8" (FOOT)	SS, DI, TY 2 18" (FOOT)	SS, DI, TY 2 24" (FOOT)	HDPE 12" (FOOT)	HDPE 18" (FOOT)	HDPE 24" (FOOT)
A2	0+76.1	TO	1+00.0	8.6		20.4						
A4	1+00.0	TO	1+94.2	71.0		88.2						
B1	5+00.0	TO	6+65.5	116.6				498.7				
B3	5+00.0	TO	6+67.3				149.1					
C4	-								48.0			
C5	-								61.0			
C7	-								137.0			
F1	10+32.2	TO	10+55.0	8.0	25.0							
-	10+03.5	TO	15+00.0	119.0				128.3		92.2	330.0	62.0
-	15+00.0	TO	21+00.0								600.0	136.0
-	21+00.0	TO	27+00.0								600.0	
-	27+00.0	TO	33+00.0								600.0	
-	33+00.0	TO	39+00.0								600.0	
	39+00.0	TO	45+00.0								600.0	
	45+00.0	TO	51+00.0								600.0	24.0
	51+00.0	TO	57+00.0								600.0	
-	57+00.0	TO	61+17.4					223.1			194.3	
TOTAL:				323	25	109	149	627	223	246	92	4724

FORCE MAIN LOCATING SCHEDULE

LABEL	STATION	X0327021
		LOCATING DEEP WELL FORCE MAIN (EACH)
C4	-	1
C5	-	1
C6	-	2
C7	-	1
-	14+56	1
-	16+90	1
TOTAL		7

PIPE DRAIN SCHEDULE

LABEL	LOCATION	60100060	60100905	60100925	X0323859
		CONCRETE HEADWALLS FOR PIPE DRAINS (EACH)	PIPE DRAINS 4" (FOOT)	PIPE DRAINS 8" (FOOT)	DOWNSPOUT CONNECTION (EACH)
G1	WEST WALL (N) WELL HOUSE				1
G2	NORTH SIDE WELL HOUSE			58	
G1	WEST WALL (S) WELL HOUSE			38	1
G3	11+89.8 78.9' RT (2ND STREET)	1			
G4	WELL HOUSE OVERFLOWS & SUMPS		93	94	
G5	11+90.2 68.9' RT (2ND STREET)	1			
TOTAL:		2	93	190	2

CURB AND GUTTER SCHEDULE

LOCATION	60600605	60605000
	CONCRETE CURB, TYPE B (FOOT)	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24 (FOOT)
10+27.5 TO 10+33.5 LT (2ND STREET)		6.5
10+32.5 TO 10+38.5 RT (2ND STREET)		7.5
10+70.0 TO 11+40.0 RT (2ND STREET)		70.0
10+86.0 TO 10+92.0 LT (2ND STREET)		7.1
11+70.0 TO 12+30.0 RT (2ND STREET)		60.0
11+70.0 TO 12+30.0 LT (2ND STREET)		60.0
12+62.0 TO 12+68.0 RT (2ND STREET)		6.0
12+62.0 TO 12+68.0 LT (2ND STREET)		6.0
WELL HOUSE PARKING LOT - EAST	146.1	
WELL HOUSE PARKING LOT - SOUTH	25.2	
123+67 TO 124+81 RT (ROADWAY B)		
TOTAL	171	223

SANITARY SEWER SCHEDULE

LABEL	STATION	OFFSET	Z0056700	X0326713	X6022820
			SANITARY SEWER 4" (FOOT)	SANITARY SEWER CONNECTION (EACH)	MH, SANITARY, 5', TY 1 FR, CLOSED LID (EACH)
D1	11+85.0	6.4' LT		1	
D2			108		
D3	11+83.0	102.0' LT			1
TOTAL			108	1	1

WATER MAIN SCHEDULE

LABEL	LOCATION	56104800	56200500	56201120	56500500
		WATER VALVES 4" (EACH)	WATER SERVICE LINE 1 1/2" (FOOT)	WATER SERVICE LINE 4" (FOOT)	DOMESTIC METER VAULTS (EACH)
E2	10+75.1 32.9' RT (2ND STREET)				1
E3	WATER MAIN TO WELL HOUSE			150	
E4	WELL HOUSE TO EX. PUMP STA.		170		
E5	10+75.1 45.0' RT (2ND STREET)	1			
TOTAL:		1	170	150	1

FILE NAME = G:\11\110223\Work_Drain_3_M0_Ave_Riz2\CAD\Drawings\DR76699-ant-tch\dwg\locdrn



USER NAME = seb	DESIGNED - SEB	REVISED - 8/27/2014 - SEB
PLOT SCALE = 48.0000' / in.	DRAWN - SEB	REVISED -
PLOT DATE = 9/23/2014	CHECKED -	REVISED -
	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**SCHEDULE OF QUANTITIES
MISSOURI AVENUE DEEP WELL FACILITY**

SCALE: NONE SHEET 3 OF 6 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
64	82-4T-1	ST. CLAIR	185	18
CONTRACT NO. 76C99			ILLINOIS FED. AID PROJECT	