

LOCATION	HORIZONTAL WELL (FOOT)
LATERAL 1	250
LATERAL 2	250
LATERAL 3	180
LATERAL 4	170
LATERAL 5	190
LATERAL 6	250
LATERAL 7	250
<b>TOTAL</b>	<b>1540</b>

**RECORDER WELL SCHEDULE**

		X0326931
STATION	OFFSET	RECORDER WELL (EACH)
121+93.0	26.4' RT	1
<b>TOTAL</b>		<b>1</b>

**PROTECTIVE COAT SCHEDULE**

		50300300
PAY ITEM	PROTECTIVE COAT (SQ YD)	
PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	123.0	
PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	32.1	
SLOPE WALL 6 INCH	4125.0	
CONCRETE CURB, TYPE B	15.3	
COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	76.4	
PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH, SPECIAL	75.9	
CONCRETE GUTTER, TYPE B (SPECIAL)	27.0	
<b>TOTAL:</b>	<b>4475</b>	

**FORCE MAIN VAULT SCHEDULE**

CALL-OUT	STATION	OFFSET	50300225	50800105	50200100	X6040205
			CONCRETE STRUCTURES (CU YD)	REINFORCEMENT BARS (POUND)	STRUCTURE EXCAVATION (CU YD)	FRAMES AND LIDS, SPECIAL (EACH)
C1	11+36.7	-	29.6	6790	58	1
C2	11+60.9	-	37.5	8200	61	1
C3	13+65.3	-	75.9	32220	247	2
C4	13+76.0	41.8' RT	37.1	8190	79	1
C5	13+84.0	47.2' RT	37.1	8190	79	1
C6	14+12.2	30.2' RT	26.8	5520	51	1
C7	14+64.4	11.8' RT	33.1	7520	68	1
C8	17+91.1	-	22.7	5020	43	1
C9	21+22.9	-	18.7	4390	31	1
C10	25+20.0	-	20.7	4770	37	1
C11	29+29.2	-	28.5	5890	61	1
C12	33+37.8	-	28.7	5900	62	1
C13	37+17.0	-	18.4	4370	30	1
C14	41+91.5	-	18.7	4390	31	1
C15	45+68.7	-	18.7	4390	31	1
C16	49+34.2	-	18.4	4370	30	1
C17	52+88.0	-	19.6	4570	34	1
C18	57+44.4	-	20.4	4620	36	1
<b>TOTAL:</b>			<b>511</b>	<b>129310</b>	<b>1069</b>	<b>19</b>

**STRUCTURAL STEEL SCHEDULE**

		50500405
LOCATION		FURNISHING AND ERECTING STRUCTURAL STEEL (POUND)
PIPE BRIDGE OVER ST. CLAIR AVE.		2960
<b>TOTAL:</b>		<b>2960</b>

ALL STRUCTURAL STEEL FOR THE NEW WELL HOUSE BUILDING AND THE EXISTING PUMP STATION BUILDING SHALL BE INCLUDED IN THE UNIT PRICE FOR "PUMP STATION GENERAL WORK"

FILE NAME = G:\115\110223\Work - D:\dr - 3 MO Ave Proj\2\AC00 Sheets\0876699-ant-tch\sheet4.dwg



USER NAME = seb
PLOT SCALE = 40.0000' / in.
PLOT DATE = 9/23/2014

DESIGNED - SEB	REVISED - SEB - 9/22/2014
DRAWN - SEB	REVISED -
CHECKED -	REVISED -
DATE -	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES  
MISSOURI AVENUE DEEP WELL FACILITY

SCALE: NONE SHEET 4 OF 6 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
64	82-4T-1	ST. CLAIR	185	19
CONTRACT NO. 76C99				
ILLINOIS FED. AID PROJECT				