

TRAFFIC CONTROL SCHEDULE

LOCATION			70100205	70100420	70103815	70400100	70600260	78200410	78200520	X7010410
WESTBOUND F.A.I. 64			TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	TRAFFIC CONTROL SURVEILLANCE	TEMPORARY CONCRETE BARRIER	IMPACT ATTENUATORS, TEMP (FULLY REDIRECTIVE, NARROW), TEST LVL 3	GUARDRAIL MARKERS, TYPE A	BARRIER WALL MARKERS, TYPE B	SPEED DISPLAY TRAILER
STATION	STATION	OFFSET	(EACH)	(EACH)	(CAL DA)	(FOOT)	(EACH)	(EACH)	(EACH)	(CAL MO)
118+00	142+00	N/A	1		120					
121+67	124+67	6.9' LT				300.1			13	
121+87	136+00	LT						17		
124+67	127+20	6.9' RT				253.4				
127+20	N/A	12' RT					1			
130+25	N/A	RT								4
131+87	132+47	RT		1						
TOTAL:			1	1	120	554	1	17	13	4

PAVEMENT MARKING SCHEDULE

LOCATION			WORK ZONE PAVEMENT MARKING REMOVAL	MODIFIED URETHANE PAVEMENT MARKING - LINE 4"	MODIFIED URETHANE PAVEMENT MARKING - LINE 6"	RAISED REFLECTIVE PAVEMENT MARKER	PAVEMENT MARKING REMOVAL	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	WET REFLECTIVE TEMPORARY TAPE TYPE III, 4 INCH
STATION	STATION	O/S	SQ.FT	FOOT	FOOT	EACH	SQ.FT	EACH	FOOT
WESTBOUND FAI 55/64/70			70301000	78009004	78009006	78100100	78300100	78300200	X7030030
119+55	129+30	24' LT	325				321.8		975
119+55	131+87	CL	410.67						1232
119+55	128+00	24' LT		845	243.8				
119+55	129+30	12' LT	325		243.8	26	487.5	26	975
119+55	128+00	CL							
121+67	124+67	LT							
121+87	126+00	LT							
123+67	124+42	13.3' RT		74.5					
123+85	N/A	N/A							
124+25	N/A	N/A							
128+00	129+30	24' LT		130.3					
129+30	142+00	CL					158.8		
131+50	131+87	RT							44.5
131+87	N/A	N/A	14.84						
131+88	142+00	RT							1020.7
131+89	142+00	RT	340.25						
TOTAL			1416	1050	488	26	968	26	4247

CONCRETE GUTTER SCHEDULE

LOCATION			CONCRETE GUTTER, TYPE B (SPECIAL)	PROTECTIVE COAT	GUTTER REMOVAL (SPECIAL)
STATION	STATION	O/S	FOOT	SQ YD	FOOT
WESTBOUND FAI 55/64/70			X6063000	50300300	X4402720
123+68	123+99.75	21' RT	31.4	13.6	31
124+12.42	124+42	21' RT	29.3	12.7	29
TOTAL			61.0	27	61

FILE NAME = G:\111\1110023\Work_Drwn_3_M0_Ave_R12\ACADD_Sheets\01\B76699-ant-t-technical.dwg



USER NAME = seb	DESIGNED - RP	REVISED - 8/27/2014 - SEB
	DRAWN - RP	REVISED -
PLOT SCALE = 48.0000' / in.	CHECKED - SGL	REVISED -
PLOT DATE = 9/23/2014	DATE - 7/30/2014	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULE OF QUANTITIES	
MISSOURI AVENUE DEEP WELL FACILITY	
SCALE: NONE	SHEET 5 OF 6 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
64	82-4T-1	ST. CLAIR	185	20
CONTRACT NO. 76C99				
ILLINOIS FED. AID PROJECT				