

Revised 7-1-94

Designer Note: Use on small urban projects with small quantities of excavation [less than 1000 cubic meters (1300 cu. yds.)] and very minor grading. Revised Article and D.N. (metric) 7-1-94.

EARTH EXCAVATION - INCIDENTAL TO CURB, GUTTER & DRIVEWAY

Earth excavation and backfill for proposed curb and gutters and driveway pavements shall be included in the unit cost of the various items.