

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

Schedule of Quantities

FAI Routes 57 & 70
D5-7 OVD SIN STR REPL 2009-5
Various Counties
Sheet 4 of 35
Contract Number 46006

PAY ITEM	UNIT	Y002 - 1C 100% STATE TOTAL QUANTITY	DISTRICT 5	DISTRICT 7	PAY ITEM	UNIT	Y002 - 1C 100% STATE TOTAL QUANTITY	DISTRICT 5	DISTRICT 7
REMOVE & REINSTALL WALKWAY	FOOT	130.00	79.00	51.00	MOBILIZATION	L SUM	1.00	0.25	0.75
OVERHEAD SIGN STRUCTURE WALKWAY	FOOT	458.00		458.00	TRAFFIC CONTROL & PROTECTION	L SUM	1.00	0.25	0.75
REPLACE/TIGHTEN CLIP PER SIGN	EACH	5.00		5.00	OVERHEAD SIGN STRUCTURE - SPAN, TYPE I-A (4' - 0"X4' - 6")	FOOT	184.00	88.00	96.00
REMOVE & REINSTALL SIGN PANEL	SQ FT	1,132.50	862.00	270.50	OVERHEAD SIGN STRUCTURE - SPAN, TYPE II-A (4' - 6"X 5' - 3")	FOOT	81.00	81.00	
TIGHTEN U-BOLT	EACH	2.00		2.00	DRILLED SHAFT CONCRETE FOUNDATIONS	CU YD	68.30	47.80	20.50
FURNISH & INSTALL SADDLE SHIM BLOCK	EACH	20.00		20.00	REMOVE OVERHEAD SIGN STRUCTURE - SPAN	EACH	3.00	2.00	1.00
FURNISH & INSTALL INTERNAL TRUSS DAMPER	EACH	5.00		5.00	REMOVE CONCRETE FOUNDATION - OVERHEAD	EACH	6.00	4.00	2.00
FURNISH & INSTALL SAFETY CHAIN	EACH	14.00	4.00	10.00	STRUCTURAL STEEL SUPPORT FOR OVERHEAD SIGN STRUCTURE - SPAN	EACH	16.00	4.00	12.00
REPAIR HANDRAIL LOCKING PIN CONNECTION	EACH	64.00	9.00	55.00	REMOVE & RE-ERECT OVERHEAD SIGN STRUCTURE - SPAN	EACH	5.00		5.00
DISCONNECT/RECONNECT ELECTRIC SERVICE	EACH	8.00	2.00	6.00					
RELOCATE ELECTRIC SERVICE	EACH	3.00	2.00	1.00					
CHANGEABLE MESSAGE SIGN	CAL DAY	70.00	70.00						
ATTENUATOR BASE	SQ YD	102.00	102.00						
IMPACT ATTENUATOR REMOVAL	EACH	2.00	2.00						
IMPACT ATTENUATOR (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2.00	2.00						
PAVED DITCH REMOVAL & REPLACEMENT	FOOT	40.00	40.00						
GUARD POSTS	EACH	35.00	35.00						
GUARD POST REMOVAL	EACH	23.00	23.00						

Rev.