

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE			SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		MARSHALL COUNTY (1000) 80% FEDERAL 20% STATE	MARSHALL COUNTY (1000) 50% STATE 50% CITY	-----	CODE NO	ITEM	UNIT		MARSHALL COUNTY (1000) 80% FEDERAL 20% STATE	MARSHALL COUNTY (1000) 50% STATE 50% CITY	-----
40600215	POLYMERIZED BITUMINOUS MATERIAL (PRIME COAT)	TON	58.4	54.8	3.6	*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	509	509			
40600300	AGGREGATE (PRIME COAT)	TON	329	310.7	18.3	78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	509	509			
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	31	31		*88600100	DETECTOR LOOP, TYPE I	FOOT	160	160			
40600895	CONSTRUCTING TEST STRIP	EACH	1	1		X0322729	MATERIAL TRANSFER DEVICE	TON	10938	10938			
40600982	HOT - MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	527	527		*X2503100	MOWING	UNIT	406	406			
40600990	TEMPORARY RAMP	SO YD	730	730		X4067107	POLYMERIZED LEVELING BINDER (MACHINE MET HOD), IL-4.75, N50	TON	3669	3669			
40603080	HOT - MIX ASPHALT BINDER COURSE, IL - 19 .0, N50	TON	364	364		X0326245	WEATHER SENSOR UPGRADE AND REPLACE	L SUM	1	1			
40603335	HOT MIX - ASPHALT SURFACE COURSE, MIX "D", N50	TON	10938	9915	1023								
44000152	HOT - MIX ASPHALT SURFACE REMOVAL, 3/4"	SO YD	85064	85064									
44000157	HOT - MIX ASPHALT SURFACE REMOVAL, 2 "	SO YD	31377	22294.6	9082.4								
44000165	HOT - MIX ASPHALT SURFACE REMOVAL, 4"	SO YD	2000	2000									
48101200	AGGREGATE SHOULDERS, TYPE B	TON	928	928									
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3									
67100100	MOBILIZATION	L SUM	1	1									
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1									
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1									
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	11387	11387									
70300210	TEMPORARY PAVEMENT MARKING-LETTERS AND SYMBOLS	SO FT	13.8	13.8									
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	92654	92654									
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	168	168									
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	216	216									
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	44	44									
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	1354	1354									
*78005100	EPOXY PAVEMENT MARKING-LETTERS AND SYMBOLS	SO FT	13.8	13.8									
*78005110	EPOXY PAVEMENT MARKING - LINE 4"	FOOT	92654	92654									
*78005130	EPOXY PAVEMENT MARKING - LINE 6"	FOOT	168	168									
*78005150	EPOXY PAVEMENT MARKING - LINE 12"	FOOT	216	216									
*78005180	EPOXY PAVEMENT MARKING - LINE 24"	FOOT	44	44									

■ NON-PARTICIPATING

FILE NAME S:\GEN\DRIFT\STD&PLNS\sqeet1\68560 IL2	USER NAME = jongsr N Lacon\plans.dgn	DESIGNED - --- DRAWN - ---	REVISED - --- REVISED - ---
PLOT SCALE = 206.0223' / IN.	CHECKED - --- DATE - -----	REVISED - --- REVISED - ---	
PLOT DATE = 10/10/2008			

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
649	11G.18CSRS-1J3RS-2RS&2ZRS-2	MARSHALL	15	3
CONTRACT NO. 68560				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				