

EPOXY PAVEMENT MARKING LINE - 4"
 TEMPORARY PAVEMENT MARKING LINE - 4"

LOCATION	White feet	Yellow Skip feet
IL 17		
Sta. 6+23 to 22+50	704	407
Sta. 27+15 to 46+44		482
Sta. 46+44 to 65+59	3830	
IL 26		
Sta. 7+08 to 174+31	33446	3433
Sta. 176+21 to 333+10 bk	29938	3922
Sta. 68+45 to 85+20 (S. of IL 17)		419
90+00 to 100+75 bk		269
Sub-Total	67918	8932

LOCATION	Yellow NPZ feet
IL 17	
Lt. Sta. 6+23 to 10+37	414
Rt. Sta. 39+00 to 46+44	744
Lt. & Rt. Sta. 46+44 to 65+59	3830
IL 26	
Lt. & Rt. Sta. 7+08 to 14+08	1400
Lt. Sta. 14+08 to 24+00	992
Rt. Sta. 80+40 to 88+10	770
Lt. & Rt. Sta. 88+10 to 111+00	4580
Lt. Sta. 111+00 to 121+20	1020
Rt. Sta. 181+00 to 190+80	980
Lt. Sta. 190+80 to 201+54	1074
Sub-Total	15804
Total	92654

EPOXY PAVEMENT MARKING LINE - LETTERS AND SYMBOLS
 TEMPORARY PAVEMENT MARKING LINE - LETTERS AND SYMBOLS

LOCATION	sq. ft.
IL 17	
Handicap Symbol @ parking lanes (3@ 4.6 s.f. each)	13.8
Total	13.8

EPOXY PAVEMENT MARKING LINE - 6"
 TEMPORARY PAVEMENT MARKING LINE - 6"

LOCATION	feet
IL 17	
Crosswalk Sta. 32+75	84
Crosswalk Sta. 33+17	84
Total	168

EPOXY PAVEMENT MARKING LINE - 12"
 TEMPORARY PAVEMENT MARKING LINE - 12"

LOCATION	feet
IL 17	
Crosswalk Sta. 32+75	108
Crosswalk Sta. 33+17	108
Total	216

EPOXY PAVEMENT MARKING LINE - 24"
 TEMPORARY PAVEMENT MARKING LINE - 24"

LOCATION	feet
IL 17	
Stop Bar Sta. 32+68	22
Stop Bar Sta. 33+24	22
Total	44

MIXTURE FOR CRACKS JOINTS AND FLANGWAYS

LOCATION	ton
IL 17	5
IL 26	26
Total	31