

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

SECTION	COUNTY	TOTAL SHEETS	SHEET NO
05-00016-03-BR	MADISON	129	3

STA. TO STA.

CONTRACT NO.: 97351
 ADDENDUM #1 01-02-2009

CODE NO	ITEM	UNIT	STRUCTURES		5000 ROAD WAY	TOTAL QUANTITIES
			SN: 060 -6851	SN: 060 -6853		
20100500	TREE REMOVAL, ACRE	ACRES			5.53	5.53
20200100	EARTH EXCAVATION	CU YD			58,901	58,901
20400800	FURNISHED EXCAVATION	CU YD			47,049	47,049
20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	465			465
20800150	TRENCH BACKFILL	CU YD			475.6	475.6
25000200	SEEDING, CLASS 2	ACRE			8.2	8.2
25000400	NITROGEN FERTILIZER NUTRIENT	POUND			738	738
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND			738	738
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND			738	738
25100115	MULCH, METHOD 2	ACRE			8.2	8.2
25100630	EROSION CONTROL BLANKET	SQ YD			2,250	2,250
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND			820	820
28000300	TEMPORARY DITCH CHECKS	EACH			27	27
28000400	PERIMETER EROSION BARRIER	FOOT			1,159	1,159
28000500	INLET AND PIPE PROTECTION	EACH			20	20
28100109	STONE RIPRAP, CLASS A5	SQ YD		221		221
28100705	STONE DUMPED RIPRAP, CLASS A3	SQ YD			6	6
28100707	STONE DUMPED RIPRAP, CLASS A4	SQ YD			103	103
28200200	FILTER FABRIC	SQ YD		251		354
30200650	PROCESSING MODIFIED SOIL, 12"	SQ YD			4,007	4,007
30201500	LIME	TON			77.2	77.2
31100300	SUB-BASE GRANULAR MATERIAL, TYPE A 4"	SQ YD			4,007	4,007
*42000311	PORTLAND CEMENT CONCRETE PAVEMENT 8 1/2"(JOINTED)	SQ YD			3,053	3,053
42001165	BRIDGE APPROACH PAVEMENT	SQ YD			200	200
42001300	PROTECTIVE COAT	SQ YD			3,953	3,953
42400100	PORTLAND CEMENT CONCRETE SIDEWALK, 4"	SQ FT			4,896	4,896
44000300	CURB REMOVAL	FOOT			4	4
50200100	STRUCTURE EXCAVATION	CU YD	1,057			1,057
50300225	CONCRETE STRUCTURES	CU YD	350.2			350.2
50300255	CONCRETE SUPERSTRUCTURE	CU YD	350.6			350.6
50300260	BRIDGE DECK GROOVING	SQ YD	959			959
50300280	CONCRETE ENCASEMENT	CU YD	5			5
50300285	FORM LINER TEXTURED SURFACE	SQ FT	2,656			2,656
50300300	PROTECTIVE COAT	SQ YD	2,628			2,628
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1			1
50500505	STUD SHEAR CONNECTORS	EACH	2,232			2,232
50800105	REINFORCEMENT BARS	POUND		204,384		204,384
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	94,446	320		94,766
*50900805	PEDESTRIAN RAILING	FOOT	229			229
51100100	SLOPE WALL, 4"	SQ YD	66			66
X007764	BRICK SLOPE WALL	SQ YD	192			192
51201600	FURNISHING STEEL PILES HP12X53	FOOT	646			646
51201700	FURNISHING STEEL PILES HP12X74	FOOT	1,938			1,938
51201710	FURNISHING STEEL PILES HP12X84	FOOT	768			768
51202305	DRIVING PILES	FOOT	3,333			3,333
51203600	TEST PILE STEEL HP12X53	EACH	1			1
51203700	TEST PILE STEEL HP12X74	EACH	2			2
51203710	TEST PILE STEEL HP12X84	EACH	2			2
51500100	NAME PLATES	EACH	1	1		2
52000110	PREFORMED JOINT STRIP SEAL	FOOT	77			77
52100010	ELASTOMETRIC BEARING ASSEMBLY, TYPE 1	EACH	12			12

CODE NO	ITEM	UNIT	STRUCTURES		5000 ROAD WAY	TOTAL QUANTITIES
			SN: 060 -6851	SN: 060 -6853		
52100520	ANCHOR BOLTS, 1"	EACH	24			24
52100540	ANCHOR BOLTS, 1/2"	EACH	12			12
54001001	BOX CULVERT END SECTION, CULVERT NO.1	EACH			2	2
54003000	CONCRETE BOX CULVERTS	CU YD		935		935
54201279	PIPE CULVERTS, TYPE 2 RCCP 24"	FOOT			60	60
54201291	PIPE CULVERTS, TYPE 2 RCCP 36"	FOOT			41	41
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH			1	1
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH			1	1
54213675	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 30"	EACH			1	1
54213681	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 36"	EACH			1	1
54248510	CONCRETE COLLAR	CU YD			0.5	0.5
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT			650	650
550A0380	STORM SEWERS, CLASS A, TYPE 2 18"	FOOT			174	174
550A0430	STORM SEWERS, CLASS A, TYPE 2 30"	FOOT			347	347
58700300	CONCRETE SEALER	SQ FT	173			173
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	111			111
*60109582	PIPE UNDERDRAINS FOR STRUCTURES 6"	FOOT	76			76
60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH			2	2
60219000	MANHOLES, TYPE A, 4'-DIAMETER, TYPE B GRATE	EACH			1	1
60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH			1	1
*60228110	MANHOLES, SANITARY, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH			3	3
60240220	INLETS, TYPE B, TYPE 3 FRAME AND GRATE	EACH			2	2
60602500	CONCRETE GUTTER, TYPE A	FOOT			198	198
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B6.24	FOOT			2,111	2,111
*63000000	STEEL PLATE BEAM GUARDRAIL, TYPE A	FOOT			262.5	262.5
*63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH			2	2
*63100087	TRAFFIC BARRIER TERMINAL, TYPE 6A	EACH			2	2
*66500105	WOVEN WIRE FENCE, 4'	FOOT			706	706
*66502400	WOVEN WIRE FENCE TO BE REMOVED & RE-ERECTED	FOOT			360	360
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO			12	12
67100100	MOBILIZATION	L SUM			1	1
70103700	TRAFFIC CONTROL COMPLETE	L SUM			1	1
*78200410	GUARDRAIL MARKERS, TYPE A	EACH			2	2
X0300266	WOODEN FENCE REMOVAL	FOOT			514	514
*X0320591	SANITARY MANHOLES TO BE REMOVED	EACH			1	1
*X0322791	FILL EXISTING SANITARY SEWERS	CU YD			9	9
X0323265	REMOVE EXISTING RIPRAP	SQ YD			70	70
XX007765	WETLAND MITIGATION PLANT/SEED MIX	ACRE			1.60	1.60
X6020074	INLETS, TYPE A, TYPE 3V FRAME AND GRATE	EACH			2	2
X6020075	INLETS, TYPE B, TYPE 3V FRAME AND GRATE	EACH			6	6
XX001875	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 3V FRAME AND GRATE	EACH			2	2
Z0030150	IMPACT ATTENUATORS (NON-REDIRECTIVE), TEST LEVEL 3	EACH			2	2
Z0054517	ROCK FILL - FOUNDATION	TON		344		344
*Z0057200	SANITARY SEWER 15"	FOOT			383	383

REVISED 1-6-09

CODE NO	ITEM	UNIT	STRUCTURES		5000 ROAD WAY	TOTAL QUANTITIES
			SN: 060 -6851	SN: 060 -6853		

NOTE: * INDICATES SPECIALTY ITEM