

SUMMARY OF QUANTITIES			
CODE NO.	ITEM	CONSTRUCTION TYPE CODE 0011	
		UNIT	097-0079 FUNDING NHS 80% FEDERAL 20% STATE
20200100	EARTH EXCAVATION	CU YD	125
20300100	CHANNEL EXCAVATION	CU YD	320
20700220	POROUS GRANULAR EMBANKMENT	CU YD	45
25000210	SEEDNG, CLASS 2A	ACRE	0.25
25000350	SEEDING, CLASS 7	ACRE	0.25
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	11
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	7
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	7
25000700	AGRICULTURAL GROUND LIMESTONE	TON	0.2
25100115	MULCH, METHOD 2	ACRE	0.5
25100630	EROSION CONTROL BLANKET	SQ YD	272
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	35
28000305	TEMPORARY DITCH CHECKS	FOOT	12
28000400	PERIMETER EROSION BARRIER	FOOT	735

^ SEE SPECIAL PROVISIONS

FILE NAME = c:\pwwork\pwwork\1\awander\1\BRES38046.D978266\1\16201.dgn	DESIGNED - L.F.S.	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES ILLINOIS ROUTE 1/14</b>		P.A.P.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
HAMPTON, LENZINI AND RENWICK, INC. 2000 STEVENSON DRIVE, SUITE 301 SPRINGFIELD, ILLINOIS 62761	DRAWN - L.G.C.	REVISED -		332	58-1	WHITE	51	3		
FLDT SCALE = 2.8988' / 1" =	CHECKED - J.W.F.	REVISED -		SCALE:		SHEET NO. 1 OF 6 SHEETS		STA.	TO STA.	CONTRACT NO. 78266
FLDT DATE = 9/23/2013	DATE - 08/15/13	REVISED -		ILLINOIS FED. AID PROJECT						
ILLINOIS PROFESSIONAL DESIGN FIRM L.L./P.E./S.E. CORP. 14-00009										