

SUMMARY OF QUANTITIES			
CODE NO.	ITEM	CONSTRUCTION TYPE CODE 0011	
		UNIT	097-0079 FUNDING NHS 80% FEDERAL 20% STATE
28100107	STONE RIPRAP, CLASS A4	SQ YD	14
28100109	STONE RIPRAP, CLASS A5	SQ YD	538
28200200	FILTER FABRIC	SQ YD	552
35501324	HOT-MIX ASPHALT BASE COURSE, 10"	SQ YD	727
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	82
40600300	AGGREGATE (PRIME COAT)	TON	2
40600847	LEVELING BINDER (MACHINE METHOD), IL-9.5FG, N90	TON	27
40600882	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	266
40600990	TEMPORARY RAMP	SQ YD	136
40603345	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	85
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	56
44000100	PAVEMENT REMOVAL	SQ YD	397
44004250	PAVED SHOULDER REMOVAL	SQ YD	416
48203006	HOT-MIX ASPHALT SHOULDERS, 2 1/4"	SQ YD	370

111 ^SEE SPECIAL PROVISIONS

FILE NAME * D:\970266\sh1-5002.dgn	USER NAME * #USER#	DESIGNED - L.F.S.	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES ILLINOIS ROUTE 1/14	F.A.P.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
HAMPTON, LENZINI AND RENWICK, INC. 2045 STEVENSON DRIVE, SUITE 201 SPRINGFIELD, ILLINOIS 62703	PLOT SCALE * #SCALE#	DRAWN - L.G.C.	REVISED -			332	5B-1	WHITE	51	4	
ILLINOIS PROFESSIONAL DESIGN FIRM L8 / PR / SE COMP. 184.002954	PLOT DATE * 9/17/2013	CHECKED - J.W.F.	REVISED -			CONTRACT NO. 78266					
	DATE - 08/15/13	REVISED -				SCALE:	SHEET NO. 2 OF 6 SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT	