
GENERAL NOTES

Reinforcement bars designated (E) shall be epoxy coated. Layout of the slope protection system may be varied to suit ground conditions in the field as directed by the Engineer.

in the field as directed by the Engineer. Seal coat thickness design is based on the Estimated Water Surface Elevation (EWSE). Cofferdam design details and proposed changes in seal coat thickness shall be submitted to the Engineer for approval with the cofferdam design. The Contractor shall make allowance for the deflection of forms, shrinkage and settlement of falsework, in addition to allowance for dead load deflection. Forms for deck slab shall be removed prior to placement of bridge approach slab. Excavation behind existing abutment walls shall be performed to balance front and back soil pressure before removing the existing superstructure. The Contractor shall sawcut the upper portion of the existing abutment at the stage removal line before Stage I removal to ensure the remaining portion will not be prematurely damaged.

prematurely damaged. Slip-Forming of the parapets is not allowed.




STATION 336+25.25 BUILT 201_ BY STATE OF ILLINOIS F.A.P. RTE. 332 SEC. 5B-1 LOADING HL-93 STR. NO. 097-0079

> NAME PLATE See Std. 515001

Stone Riprap, C
Filter Fabric Removal of Exis
Structure Excav
Cofferdam Exca
Cofferdam (Type
Cofferdam (Type
Concrete Struct
Concrete Supers
Bridge Deck Gro
Seal Coat Concr
Protective Coat
Reinforcement E
Bar Splicers
Furnishing Metal
Driving Piles
Test Pile Metal
Name Plates
Geocomposite Wo
Asbestos Bearir
Pipe Underdrain.
Temporary Soil
Granular Backfil

FILE	NAME = \$FILE\$	USER NAME =	DESIGNED - T.J.A.	REVISED -		GENERAL DETAILS		SECTION	COUNTY	TOTAL	SHEET NO.
	HAMPTON, LENZINI AND RENWICK, INC.		CHECKED - S.M.S.	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	STRUCTURE NO. 097-0079	332	5B-1	WHITE	51	26
Ъ	SPRINGFIELD, ILLINOIS 62703	PLOT SCALE =	DRAWN - D.A.B.	REVISED -			IL RTE	1/14 OVER CROOKED CR.	CONTRACT	T NO. 7	8266
	LS / PE / SE CORP. 184.000959	PLOT DATE = 9/17/2013	CHECKED - M.D.C.	REVISED -		SHEET NO. 2 OF 15 SHEETS		ILLINOIS FED. AI	D PROJECT		



TOTAL BILL OF MATERIAL

ITEM	UNIT	SUPER	SUB	TOTAL
lass A5	Sq. Yd.	00/2/1		538
	Sq. Yd.			538
sting Structures	Éach			1
ration	Cu. Yd.			176
vation	Cu. Yd.			268
e 2) (Location - 1)	Each			1
e 2) (Location - 2)	Each			1
ures	Cu. Yd.		166.4	166.4
structure	Cu. Yd.	267.7		267.7
poving	Sq. Yd.	521		521
rete	Cu. Yd.			118
	Sq. Yd.	632	0	632
Bars, Epoxy Coated	Pound	67,910	17,260	85,170
	Each	257	188	445
Shell Piles 14''x0.312''	Foot		1,879	1,879
	Foot		1,879	1,879
Shells	Each		1	1
	Each			1
all Drain	Sq. Yd.			46
ng Pad Removal	Each			36
s for Structures, 4"	Foot			136
Retention System	Sq. Ft.			416
I for Structures	Cu. Yd.			71