

STONE RIPRAP & FILTER FABRIC							
LOCATION			LT/RT	28100107	28100125	28100127	28200200
				STONE RIPRAP CLASS A4	STONE RIPRAP CLASS B3	STONE RIPRAP CLASS B4	FILTER FABRIC
				SQ YD	SQ YD	SQ YD	SQ YD
Main Line (IL-91)							
STA. 099+24.93	TO	STA. 099+40.05	RT		13.54		
STA. 099+33.19	TO	STA. 099+53.00	LT		22.31		
STA. 103+60.50	TO	STA. 103+69.52	LT		11.26		
STA. 145+75.00	TO	STA. 146+25.00	LT	63.92			63.92
STA. 145+75.00	TO	STA. 146+23.00	RT	52.88			52.88
STA. 148+60.39	TO	STA. 149+25.35	LT		88.62		88.62
Legion Hall Rd							
STA. 002+62.82	TO	STA. 002+75.63	LT		9.85		
STA. 017+31.82	TO	STA. 017+50.71	LT	29.10			29.10
STA. 017+82.00	TO	STA. 018+03.86	RT	34.72			34.72
STA. 017+95.52	TO	STA. 018+19.68	RT	13.01			13.01
W. Ash St.							
STA. 001+91.37	TO	STA. 003+08.61	RT			274.48	274.48
TOTALS				194	146	274	557

AGGREGATE SUBGRADE IMPROVEMENT, 4"						
LOCATION			LT/RT	WIDTH	30300104	
				FT	SQ FT	SQYD
GRAZE STREET						
STA. 009+67.96	TO	STA. 009+48.97	LT & RT	VAR.	2823.85	313.76
N. CASTLE DRIVE						
STA. 010+52.05	TO	STA. 010+97.78	LT & RT	VAR.	1511.04	167.89
WILEY ROAD						
STA. 010+52.35	TO	STA. 010+85.77	LT & RT	VAR.	1274.37	141.60
W. ASH STREET						
STA. 009+21.63	TO	STA. 009+49.09	LT & RT	VAR.	666.80	74.09
E. ASH STREET						
STA. 010+51.69	TO	STA. 011+02.23	LT & RT	VAR.	1266.65	140.74
W. BIRCH STREET						
STA. 009+00.00	TO	STA. 009+49.19	LT & RT	VAR.	1098.03	122.00
W. PINE STREET						
STA. 008+90.11	TO	STA. 009+49.46	LT & RT	VAR.	1460.08	162.23
ELM STREET						
STA. 010+55.01	TO	STA. 011+00.00	LT & RT	VAR.	1203.89	133.77
TOTAL					5,880	

AGGREGATE SUBGRADE IMPROVEMENT, 12"						
LOCATION			LT/RT	WIDTH	30300112	
				FT	SQFT	SQYD
Main Line (IL 91)						
STA. 100+58.00	TO	STA. 102+83.72	LT	10.24	1619.44	179.94
STA. 100+75.41	TO	STA. 102+78.59	RT	10.88	2214.22	246.02
STA. 102+83.72	TO	STA. 104+33.00	LT	13.14	1969.64	218.85
STA. 102+78.59	TO	STA. 104+33.00	RT	19.05	2956.01	328.45
STA. 104+33.00	TO	STA. 105+08.62	LT	12.52	957.18	106.35
STA. 105+08.63	TO	STA. 106+37.52	LT	9.51	1225.11	136.12
STA. 107+09.48	TO	STA. 108+56.57	LT	16.58	2406.57	267.40
STA. 104+33.00	TO	STA. 105+75.14	RT	23.58	3361.01	373.45
STA. 105+74.14	TO	STA. 107+55.94	RT	20.5	3707.86	411.98
STA. 107+55.94	TO	STA. 108+56.57	RT	20.05	1844.83	204.98
STA. 108+56.57	TO	STA. 109+46.52	LT	16.99	1492.34	165.82
STA. 108+56.57	TO	STA. 109+46.52	RT	16.58	1491.86	165.76
STA. 109+46.52	TO	STA. 145+10.00	LT	15.58	55523.09	6169.23
STA. 109+46.52	TO	STA. 145+10.00	RT	15.58	55515.89	6168.43
STA. 145+10.00	TO	STA. 146+90.00	LT	13.33	2399.57	266.62
STA. 145+10.00	TO	STA. 146+90.00	RT	13.33	2399.57	266.62
STA. 146+90.00	TO	STA. 147+50.00	LT	11.08	664.83	73.87
STA. 146+90.00	TO	STA. 147+25.00	RT	8	280.00	31.11
SUB-TOTAL 1					142,029	15,781
SIDERROADS						
W. LEGION HALL ROAD			LT	Var.	5956.99	661.89
E. LEGION HALL ROAD.			RT	Var.	5424.7	602.74
S. CASTLE DRIVE			RT	26.79	1225.26	136.14
GRAZE STREET			LT	25.77	1188.65	132.07
N. CASTLE DRIVE			RT	27.43	1268.18	140.91
WILEY ROAD			RT	33.46	1448.75	160.97
E. ASH STREET			RT	21.58	1090.63	121.18
W. ASH STREET			LT	18.58	987.85	109.76
E. BIRCH STREET			RT	19.93	1270.63	141.18
W. BIRCH STREET			LT	19.37	1007.41	111.93
E. PINE STREET			RT	26.48	1506.00	167.33
W. PINE STREET			LT	20.5	1029.43	114.38
WALNUT STREET			RT	20.93	1296.03	144.00
ELM STREET			RT	21.67	1187.09	131.90
HICKORY STREET			RT	21.58	1161.83	129.09
SUB-TOTAL 2					27,049	1,741
TOTAL						17,522

AGGREGATE SUBGRADE IMPROVEMENT, 4"						
LOCATION			LT/RT	WIDTH	30300104	
				FT	SQ FT	SQYD
Main Line (IL 91)						
STA. 147+50.00	TO	STA. 148+45.55	LT	7.29	708.34	78.70
STA. 148+45.55	TO	STA. 149+57.82	LT	5.23	571.34	63.48
STA. 147+25.00	TO	STA. 149+57.82	RT	3.55	872.42	96.94
W. Legion Hall Road						
STA. 002+85.22	TO	STA. 004+98.62	RT	VAR.	1234.42	137.16
STA. 005+27.03	TO	STA. 008+03.57	RT	VAR.	3898.42	433.16
STA. 002+77.04	TO	STA. 008+03.57	LT	VAR.	3985.93	442.88
STA. 008+03.57	TO	STA. 009+15.11	LT&RT	VAR.	5472.58	608.06
E. LEGION HALL ROAD.						
STA. 010+89.11	TO	STA. 014+31.94	LT & RT	VAR.	16377.77	1819.75
STA. 014+31.94	TO	STA. 017+85.62	RT	VAR.	2900.44	322.27
STA. 014+31.91	TO	STA. 020+31.95	LT	VAR.	4032.87	448.10
S. CASTLE DRIVE						
STA. 010+51.35	TO	STA. 011+00.00	LT & RT	VAR.	1557.87	173.10
GRAZE STREET						
STA. 009+67.96	TO	STA. 009+48.97	LT & RT	VAR.	2823.85	313.76
N. CASTLE DRIVE						
STA. 010+52.05	TO	STA. 010+97.78	LT & RT	VAR.	1511.04	167.89

HOT-MIX ASPHALT BASE COURSE 7 1/2"						
LOCATION			LT/RT	WIDTH	35501314	
				FT	SQFT	SQYD
W. Legion Hall Road						
STA. 002+85.22	TO	STA. 004+98.62	RT	VAR.	587.76	65
STA. 005+27.03	TO	STA. 008+03.57	RT	VAR.	2992.27	332
STA. 002+77.04	TO	STA. 008+03.57	LT	VAR.	2425.13	269
STA. 008+03.57	TO	STA. 009+15.11		VAR.	4779.16	531
E. LEGION HALL ROAD.						
STA. 010+89.11	TO	STA. 014+31.56		VAR.	14260.20	1,584
STA. 014+31.56	TO	STA. 017+85.62	RT	VAR.	2105.66	234
STA. 014+31.56	TO	STA. 020+31.95	LT	VAR.	2182.61	243
SUB-TOTAL 1					3,259	
TOTAL						3,259