

TABULATION OF RESURFACING QUANTITIES

LOCATION	TOTAL ROADWAY WIDTH	LENGTH	AREA	H.M. A. SURFACE REMOVAL (BUTT JOINT)	TEMPORARY RAMP	H.M.A SURFACE REMOVAL	POLY. BIT. MATERIALS PRIME COAT	AGGREGATE PRIME COAT	POLY. LEV. BINDER IL4.75, N 50 0.75 IN	POLY. H.M.A. SURF. COURSE MIX. E. N 50
						0.75 IN				
						SQ YD				
IL 91 MAIN LINE										
STA. 99 + 21.00 TO 99 + 51.00	26.00	30.00	86.67	86.67	14.44		0.06	0.35	3.65	9.77
STA. 99 + 51.00 TO 100 + 75.41	26.08	124.41	360.55			360.55	0.23	1.44	15.18	40.64
STA. 100 + 75.41 TO 102 + 78.59	31.16	203.18	703.45			361.21	0.45	2.81	29.60	79.21
STA. 102 + 78.59 TO 104 + 33.00	42.08	154.41	722.54			274.51	0.46	2.89	30.39	81.24
STA. 104 + 33.00 TO 105 + 63.77	48.00	130.77	704.23			261.54	0.45	2.82	29.62	79.14
STA. 105 + 63.77 TO 107 + 55.94	52.00	192.17	1110.32			384.34	0.71	4.44	46.69	124.75
STA. 107 + 55.94 TO 108 + 56.51	48.50	100.57	521.75			201.14	0.33	2.09	21.94	58.64
STA. 108 + 56.51 TO 109 + 46.50	43.00	89.99	429.95			179.98	0.28	1.72	18.08	48.34
STA. 109 + 46.50 TO 145 + 10.06	41.00	3563.56	16234.00			7127.12	10.39	64.94	682.87	1825.60
STA. 145 + 10.06 TO 146 + 90.00	36.50	179.94	729.76			359.88	0.47	2.92	30.70	82.11
STA. 146 + 90.00 TO 149 + 57.82	32.00	267.82	952.25			773.70	0.61	3.81	40.07	107.21
STA. 149 + 57.82 TO 149 + 87.82	26.00	30.00	86.67	86.67	14.44		0.06	0.35	3.65	9.77
WEST LEGION HALL ROAD										
STA. 2 + 47.00 TO 2 + 77.00	24.00	30.00	80.00	80.00	14.44		0.05	0.32	3.37	9.02
STA. 2 + 77.00 TO 8 + 03.57	34.75	526.57	1895.44			1404.19	1.21	7.58	79.76	213.38
STA. 8 + 03.57 TO 8 + 36.00	41.00	32.43	147.74			86.48	0.09	0.59	6.21	16.61
STA. 8 + 36.00 TO 9 + 77.50	0.00	141.50	933.73				0.60	3.73	39.26	104.87
EAST LEGION HALL ROAD										
STA. 10 + 29.50 TO 11 + 89.33		159.83	1036.64				0.66	4.15	43.59	116.44
STA. 11 + 89.33 TO 13 + 45.36	41.00	156.03	710.80				0.45	2.84	29.90	79.93
STA. 13 + 45.36 TO 14 + 31.56	39.19	86.20	375.35				0.24	1.50	15.79	42.22
STA. 14 + 31.56 TO 18 + 00.00	30.94	368.44	1266.61			982.51	0.81	5.07	53.31	142.63
STA. 18 + 00.00 TO 18 + 30.00	24.50	30.00	81.67	81.67	14.44		0.05	0.33	3.44	9.21
STA. 18 + 30.00 TO 20 + 31.95	2.00	201.95	44.88				0.03	0.18	1.94	5.45
S. CASTLE DRIVE										
STA. 10 + 20.50 TO 10 + 51.31	VAR	30.81	134.47				0.09	0.54	5.66	15.12
STA. 10 + 51.31 TO 11 + 00.00	27.17	48.69	146.99				0.09	0.59	6.19	16.56
GRAZE STREET										
STA. 8 + 67.95 TO 9 + 02.22	34.13	34.27	129.96				0.08	0.52	5.47	14.63
STA. 9 + 02.22 TO 9 + 50.00	25.83	47.78	137.13				0.09	0.55	5.77	15.46
STA. 9 + 50.00 TO 9 + 79.50	VAR	29.50	126.82				0.08	0.51	5.34	14.27
N. CASTLE DRIVE										
STA. 10 + 20.50 TO 10 + 52.09	VAR	31.59	139.30				0.09	0.56	5.86	15.67
STA. 10 + 52.09 TO 10 + 97.78	27.50	45.69	139.61				0.09	0.56	5.88	15.73