

TABULATION OF RESURFACING QUANTITIES

LOCATION	TOTAL ROADWAY WIDTH	LENGTH	AREA	H.M. A. SURFACE REMOVAL (BUTT JOINT)	TEMPORARY RAMP	H.M.A SURFACE REMOVAL	POLY. BIT. MATERIALS PRIME COAT	AGGREGATE PRIME COAT	POLY. LEV. BINDER IL4.75, N 50 0.75 IN	POLY. H.M.A. SURF. COURSE MIX. E. N 50
						0.75 IN				
	FT	FT	SQ YD	SQ YD	SQ YD	SQ YD	TON	TON	TON	TON
WILEY ROAD										
STA. 10 + 20.50 TO 10 + 52.23	VAR	31.73	160.73				0.10	0.64	6.76	18.07
STA. 10 + 52.23 TO 10 + 85.77	33.50	33.54	124.84				0.08	0.50	5.25	14.05
W. ASH STREET										
STA. 9 + 21.67 TO 9 + 49.35	18.25	27.68	56.13				0.04	0.22	2.37	6.34
STA. 9 + 49.35 TO 9 + 79.50	VAR	30.15	103.37				0.07	0.41	4.35	11.64
E. ASH STREET										
STA. 10 + 20.50 TO 10 + 51.53	VAR	31.03	117.30				0.08	0.47	4.94	13.20
STA. 10 + 51.53 TO 11 + 02.33	22.00	50.80	124.18				0.08	0.50	5.23	14.01
W. BIRCH STREET										
STA. 9 + 00.00 TO 9 + 49.19	19.33	49.19	105.65				0.07	0.42	4.45	11.93
STA. 9 + 49.19 TO 9 + 79.50	VAR	30.31	106.41				0.07	0.43	4.48	11.98
E. BIRCH STREET										
STA. 10 + 20.50 TO 10 + 60.00	VAR	39.50	129.69				0.08	0.52	5.46	14.61
W. PINE STREET										
STA. 8 + 90.11 TO 9 + 49.46	20.50	59.35	135.19				0.09	0.54	5.70	15.26
STA. 9 + 49.46 TO 9 + 79.50	VAR	30.04	110.43				0.07	0.44	4.65	12.43
SUB-TOTAL 1				335	58	12,757	20.1	125.8	1,323	3,537
E. PINE STREET										
STA. 10 + 20.50 TO 10 + 60.00	VAR	39.50	157.85				0.10	0.63	6.64	17.76
WALNUT STREET										
STA. 10 + 20.50 TO 10 + 59.88	VAR	39.38	132.27				0.08	0.53	5.57	14.90
ELM STREET										
STA. 10 + 20.50 TO 10 + 55.00	VAR	34.50	126.05				0.08	0.50	5.30	14.19
STA. 10 + 55.00 TO 11 + 00.00	21.50	45.00	107.50				0.07	0.43	4.53	12.13
HICKORY STREET										
STA. 10 + 20.50 TO 10 + 54.21	VAR	33.71	121.99				0.08	0.49	5.13	13.73
BRECKENRIDGE										
STA. 0 + 16.53 TO 0 + 49.37	VAR	32.84	161.45			161.45	0.10	0.65	6.79	18.15
STA. 0 + 49.37 TO 0 + 79.37	28.00	30.00	93.33	93.33	14.44		0.06	0.37	3.93	10.52
SUB-TOTAL 2				93.33	14.44	161.45	0.58	3.60	37.89	101.38
SUB-TOTAL 1				335.00	57.78	12,757.15	20.12	125.77	1,322.80	3,537.15
GRAND-TOTAL				428	72	12,919	21	129	1,361	3,639