

COMBINATION CURB & GUTTER REMOVAL				
LOCATION			LT/RT	44000500 FOOT
Breckenridge St				
STA. 000+28.66	TO	STA. 000+59.26	LT	35.00
STA. 000+28.98	TO	STA. 000+79.23	RT	53.00
S. Castle Dr				
STA. 010+19.49	TO	STA. 011+00.00	RT	83.00
STA. 010+18.73	TO	STA. 011+09.39	LT	93.00
Graze St				
STA. 008+68.31	TO	STA. 009+21.00	LT	53.00
N. Castle Dr				
STA. 010+19.00	TO	STA. 010+97.80	LT	79.00
STA. 010+23.00	TO	STA. 010+97.80	RT	76.00
Wiley St				
STA. 010+32.51	TO	STA. 010+82.66	LT	50.00
STA. 010+34.22	TO	STA. 010+86.81	RT	53.00
<b>TOTAL</b>				<b>575</b>

PAVED SHOULDER REMOVAL					
LOCATION			LT/RT	AREA SQFT	44004250 SQYD
Main Line (IL-91)					
STA. 099+51.00	TO	STA. 101+23.82	LT	460.71	51.19
STA. 102+12.83	TO	STA. 104+03.00	LT	543.15	60.35
STA. 104+84.38	TO	STA. 106+62.43	LT	1174.98	130.55
STA. 108+01.00	TO	STA. 108+50.00	RT	146.02	16.22
STA. 131+37.86	TO	STA. 132+12.63	RT	199.44	22.16
<b>TOTAL</b>				<b>280</b>	

STRIP REFLECTIVE CRACK CONTROL TREATMENT				
LOCATION			LT/RT	44300200 FT
Main Line (IL-91)				
STA. 100+75.41	TO	STA. 147+25.00	RT	4649.59
STA. 100+63.79	TO	STA. 147+50.00	LT	4686.21
<b>TOTAL</b>				<b>9,336</b>

REMOVAL OF EXISTING STRUCTURES		
LOCATION	TYPE	50100100 EACH
STA. 114+00.00	3' Box Culvert	1
<b>TOTAL</b>		<b>1</b>

SIDEWALK REMOVAL				
LOCATION			LT/RT	44000600 SQFT
Main Line (IL-91)				
STA. 107+48.89	TO	STA. 110+12.50	RT	1065.72
STA. 110+46.00	TO	STA. 113+41.54	RT	1161.80
STA. 113+76.30	TO	STA. 116+72.80	RT	969.05
STA. 116+94.25	TO	STA. 118+30.50	LT	458.10
STA. 117+06.00	TO	STA. 120+23.70	RT	1250.11
STA. 118+49.45	TO	STA. 120+24.15	LT	631.77
STA. 120+45.43	TO	STA. 123+38.25	RT	1056.00
STA. 120+48.89	TO	STA. 124+41.00	LT	1294.47
STA. 124+64.42	TO	STA. 128+39.03	LT	1458.57
STA. 124+84.39	TO	STA. 128+39.74	RT	1244.65
STA. 130+04.48	TO	STA. 132+35.22	RT	922.19
E. Legion Hall Rd.				
STA. 010+28.58	TO	STA. 015+72.44	LT	2260.72
STA. 015+92.63	TO	STA. 016+76.74	LT	317.11
S. Castle Dr.				
STA. 010+34.67	TO	STA. 010+82.65	RT	195.40
STA. 010+34.77	TO	STA. 011+09.29	LT	280.16
Graze St.				
STA. 008+66.12	TO	STA. 009+25.10	LT	228.84
N. Castle Dr.				
STA. 010+32.83	TO	STA. 010+50.18	LT	66.98
STA. 010+34.51	TO	STA. 010+97.81	RT	243.95
E. Ash St.				
STA. 010+32.00	TO	STA. 011+10.00		311.82
W. Birch St.				
STA. 009+04.10	TO	STA. 009+67.56	LT	223.28
STA. 009+35.50	TO	STA. 009+68.50	RT	120.92
E. Birch St.				
STA. 010+26.59	TO	STA. 010+41.96	LT	53.83
E. Pine St.				
STA. 010+19.62	TO	STA. 011+03.30	RT	392.70
<b>TOTAL</b>				<b>16,208</b>

HOT-MIX ASPHALT SHOULDERS 8"					
LOCATION			LT/RT	AREA SQFT	48203029 SQYD
Main Line (IL-91)					
STA. 147+50.00	TO	STA. 149+57.82	LT	460.71	103.21
STA. 147+25.00	TO	STA. 149+57.82	RT	798.4695	88.72
<b>TOTAL</b>				<b>192</b>	

CLASS C PATCHES							
LOCATION	WIDTH		LENGTH	AREA			
	LT	RT		LT	TYPE	RT	TYPE
STA.	FT		FT	SQ YD			
PRE-STAGE 1A (IL 91)							
STA. 143+91.65	10.7		7	6.92	II		
STA. 146+00.00	9.8		10	10.89	II		
PRE-STAGE 1B (IL 91)							
STA. 143+85.34		20	7			14.17	II
STA. 164+00.00		15	10			16.67	III
Stage 1 (Legin Hall )							
STA. 012+56.00	11	11.00	6	7.33	II	7.33	II
STA. 013+91.00	11	9	6	7.33	II	5.98	II
STA. 016+41.72	10	10	6	6.67	II	6.60	II
STA. 017+63.71	11	14.00	11	13.44	II	17.11	III
Stage 2 (IL 91)							
STA. 102+00.59	13	13.25	6	8.67	II	8.83	II
STA. 103+50.00	12.5	13.25	6	8.33	II	8.83	II
STA. 105+02.00	12	12.25	6	8.00	II	8.17	II
STA. 107+75.00	12.25	12.57	6	8.17	II	8.38	II
STA. 109+79.10	12.1	13.10	6	8.07	II	8.73	II
STA. 110+95.12	11.87	13.03	6	7.91	II	8.69	II
STA. 112+79.38	11.93	12.13	6	7.95	II	8.09	II
STA. 113+84.46	11.98	15.42	6	7.99	II	10.28	II
STA. 116+00.00	12	12.79	6	8.00	II	8.53	II
STA. 118+75.00	11.3	12.93	6	7.53	II	8.62	II
STA. 119+88.98	11.49	12.75	6	7.66	II	8.50	II
STA. 121+14.54	11.09	13.31	6	7.39	II	8.87	II
STA. 124+90.95	11.98	12.80	6	7.99	II	8.53	II
STA. 128+20.31	9.44	12.53	6	6.29	II	8.35	II
STA. 129+95.42	11.52	13.00	6	7.68	II	8.67	II
STA. 132+22.82	11.33	13.08	6	7.55	II	8.72	II
STA. 134+99.00	11.69	12.61	6	7.79	II	8.41	II
STA. 136+50.00	11.3	12.71	6	7.53	II	8.47	II
STA. 138+49.91	11.53	12.87	6	7.69	II	8.58	II
STA. 140+02.00	11.46	13.03	6	7.64	II	8.69	II
STA. 142+00.00	11.61	12.48	6	7.74	II	8.32	II
E. BIRCH STREET							
		25.50	6			17.00	III
<b>SUB-TOTAL TYPE II</b>				<b>216.17</b>		<b>215.34</b>	
<b>TOTAL TYPE II (44201377)</b>						<b>432</b>	
<b>TOTAL TYPE III (44201381)</b>						<b>51</b>	