

PIPE CULVERT REMOVAL					
LOCATION		LT/RT	SIZE	TYPE	50105220
			INCH		FT
Main Line (IL-91)					
	STA. 100 + 70.00	LT	12	CMP	18.00
C.E.	STA. 101 + 61.78	LT	18	CMP	60.63
C.E.	STA. 104 + 44.66	LT	18	CMP	80.70
S. Castle	STA. 110 + 29.80	RT	18	CMP	60.26
C.E.	STA. 110 + 46.38	LT	15	CMP	20.45
C.E.	STA. 110 + 81.08	LT	15	CMP	20.45
C.E.	STA. 111 + 47.34	LT	15	CMP	30.21
C.E.	STA. 111 + 88.84	LT	15	CMP	24.11
Graze st.	STA. 113 + 30.09	LT	18	CMP	39.20
N. Castle	STA. 113 + 60.56	RT	18	CMP	68.56
C.E.	STA. 113 + 88.60	LT	15	CMP	13.60
C.E.	STA. 114 + 55.85	LT	15	CMP	57.16
P.E.	STA. 118 + 40.25	LT	15	CMP	21.16
P.E.	STA. 118 + 41.87	RT	15	CMP	28.29
P.E.	STA. 119 + 11.85	LT	15	CMP	24.83
P.E.	STA. 119 + 27.00	RT	15	CMP	24.49
P.E.	STA. 119 + 65.71	LT	12	CMP	18.57
Crossing IL-91 STA. 120 + 15.60			24	CMP	69.20
E. Ash st.	STA. 120 + 35.26	RT	18	CMP	59.34
W. Ash st.	STA. 120 + 35.75	LT	18	CMP	57.41
Crossing IL-91 STA. 120 + 56.00			30	CMP	72.00
P.E.	STA. 121 + 91.39	LT	15	CMP	24.02
P.E.	STA. 122 + 28.76	LT	15	CMP	20.42
	STA. 122 + 47.17	RT	15	CMP	39.40
P.E.	STA. 123 + 29.09	LT	15	CMP	20.02
C.E.	STA. 123 + 55.12	RT	18	CMP	160.30
Pine st.	STA. 128 + 70.47	RT	18	CMP	64.70
Pine st.	STA. 128 + 74.65	LT	12	CLAY	46.64
C.E.	STA. 129 + 67.10	LT	12	CMP	45.36
C.E.	STA. 130 + 11.90	LT	12	CMP	16.15
C.E.	STA. 130 + 24.85	RT	15	CMP	47.56
P.E.	STA. 130 + 58.62	LT	12	CMP	19.72
P.E.	STA. 130 + 97.82	RT	12	CMP	17.37
P.E.	STA. 131 + 70.01	RT	15	CMP	25.86
P.E.	STA. 132 + 43.50	LT	15	CMP	22.29
Walnut st.	STA. 132 + 85.57	RT	12	CMP	33.20
C.E.	STA. 133 + 80.58	RT	12	CMP	69.50
C.E.	STA. 134 + 53.51	RT	10	CMP	48.33
P.E.	STA. 137 + 00.00	LT	15	CMP	28.64
P.E.	STA. 137 + 95.30	LT	15	CMP	23.63
P.E.	STA. 139 + 53.77	RT	12	CMP	17.55
P.E.	STA. 139 + 81.46	RT	12	CMP	18.43
C.E.	STA. 140 + 55.59	RT	15	CMP	113.90

PIPE CULVERT REMOVAL					
LOCATION		LT/RT	SIZE	TYPE	50105220
			INCH		FT
Main Line (IL-91)					
P.E.	STA. 142 + 66.38	RT	15	CMP	38.83
P.E.	STA. 144 + 10.27	RT	15	CLAY	61.35
Temporary	STA. 146 + 46.15	LT	30	CMP	40.00
W. Legion Hall Rd.					
P.E.	STA. 003 + 23.66	LT	15	CMP	18.48
P.E.	STA. 003 + 65.34	RT	15	CMP	20.00
P.E.	STA. 004 + 42.89	LT	12	CMP	19.63
P.E.	STA. 004 + 98.92	LT	12	CMP	25.15
P.E.	STA. 006 + 08.00	RT	12	CMP	20.00
C.E.	STA. 008 + 49.11	LT	15	CMP	50.59
C.E.	STA. 008 + 74.60	RT	18	CMP	70.56
E. Legion Hall Rd.					
P.E.	STA. 011 + 61.92	RT	12	STEEL	19.10
P.E.	STA. 012 + 32.37	RT	12	CMP	20.67
P.E.	STA. 012 + 74.51	LT	15	CMP	31.80
P.E.	STA. 013 + 43.08	RT	15	CMP	29.84
P.E.	STA. 014 + 12.84	LT	15	CMP	23.50
P.E.	STA. 014 + 60.90	RT	18	CMP	34.24
P.E.	STA. 015 + 83.78	LT	15	CMP	48.03
P.E.	STA. 016 + 49.86	RT	15	CMP	21.00
P.E.	STA. 016 + 83.18	LT	15	CMP	65.40
C.E.	STA. 017 + 22.09	RT	42	CMP	58.19
P.E.	STA. 017 + 79.35	LT	15	CMP	30.57
P.E.	STA. 020 + 11.77	LT	15	CMP	21.00
Crossing Legion Hall STA 17 + 63.00			48	CMP	71.09
Graze St.					
C.E.	STA. 009 + 51.88	RT	18	CMP	42.69
W. Pine St					
C.E.	STA. 009 + 21.88	LT	15	CMP	71.70
	STA. 009 + 69.65	RT	15	CMP	8.62
TOTAL					2,754

STRUCTURE EXCAVATION			
LOCATION		50200100	
		STRUCTURE EXCAVATION	
		CU YD	
IL91 (MSC WALL) RIGHT			
STA. 099 + 35.00	TO	STA. 104 + 50.00	394.0
TOTAL			394

PIPE CULVERT CL D, TYPE 2, 30" (TEMPORARY)		
LOCATION		5422D030
		FEET
PRE-STAGE 1A		
IL91	LT STA. 146 + 46.15	40.00
TOTAL		40.00

CONCRETE COLLAR			
LOCATION		50800105	54248510
		REINFORCEMENT BARS	CLASS SI CONCRETE
		POUNDS	CU YD
PRE-STAGE 1A			
IL 91	LT STA. 146 + 46.15	26.00	0.36
TOTAL		26.00	0.36