Structure #	LOCATION		LT/RT	OFFSET	INLETS								INLET–MANHOLE							MANHOLE TYPE A								RIM ELEV	FLOW LINE ELEV	INVERT ELEVATION				REMARKS
					TYPE G–1 SPECIAL	TYPE G–1	TYPE A, TYPE 1 FRAME, OPEN LID	TYPE A, TYPE 8 GRATE	TYPE A, W/ SPECIAL FRAME AND GRATE	TYPE B, TYPE 1 FRAME, OPEN LID	INLET SPECIAL	TYPE G–1 DOUBLE	TYPE G–1, SPECIAL, 4' DIA	TYPE G–1, SPECIAL, 5' DIA	TYPE G–1, SPECIAL, 6' DIA	TYPE G–1, SPECIAL, 8' DIA	TYPE G–1, SPECIAL, 4' DIA, DOUBLE	TYPE G–1, 4' DIA	TYPE G–1, 5' DIA	4' DIA. TYPE 1 FRAME, OPEN LID	4' DIA, W/ SPC. FRAME & GRATE	5' DIA. TYPE 1 FRAME, CLOSED LID	7' DIA. TYPE 1 FRAME, CLOSED LID	8' DIA. TYPE 1 FRAME, CLOSED LID	5' DIA, W/ SPC. FRAME & GRATE	6' DIA, W/ SPC. FRAME & GRATE	5' DIA, T1 FRAME CL. LID. SPECI			N	E	S	W	
				FOOT	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH							
62	IL–91	STA. 110+95.12	RT	20.50										1														728.00	715.35	715.45		715.35	724.08	
64	IL–91	STA. 113+14.49	LT	38.35														1										725.97	721.85			721.85	722.06	
65	IL–91	STA. 112+79.45	LT	20.50									1															726.46	721.58	721.68	721.58			
66	IL–91	STA. 112+79.45	RT	20.50										1														726.46	716.17	716.37	720.14	716.17	721.16	
67	IL–91	STA. 113+27.64	RT						1																			723.17	720.67			720.67		
68	GRAZE ST	STA. 008+88.65	LT	19.82								1																727.13	724.13		724.13			
69	GRAZE ST	STA. 008+95.69	LT	19.82																								727.14	723.71		723.71		723.81	
70	IL–91	STA. 113+45.21	LT	39.79														1										725.46	721.84	721.84			721.94	
71	IL–91	STA. 113+84.46	LT	20.50	SEE SCHEDULE																							725.88	721.43	721.86	721.43	721.63		
72	IL–91	STA. 113+91.53	LT	20.50	SEE SCHEDULE																							725.88	722.08	722.92		722.08	722.28	
73	IL–91	STA. 114+11.21	LT	34.00				1																				725.50	722.5			722.5		
74	IL–91	STA. 114+92.38	LT	20.50	1																							726.49	723.31			723.31		
75	IL–91	STA. 114+09.28	RT	45.91					1																			723.50	719.5				719.5	
76	IL–91	STA. 114+09.28	RT	20.50										1														725.98	717.2	717.4	719.31	717.2		
77	IL–91	STA. 113+84.46	RT	22.78																	1							725.84	716.72	717.12		716.72	720.52	
78	IL–91	STA. 116+00.00	RT	20.50										1														727.54	718.15	718.25		718.15	723.66	
79	IL–91	STA. 116+00.00	LT	20.50	1																							727.54	724.04		724.04			
80	IL–91	STA. 118+27.29	RT	39.96					1																			726.90	723.87	723.87				
81	IL–91	STA. 118+57.31	RT	39.38					1																			726.48	723.48	723.48		723.58		
82	IL–91	STA. 118+75.00	RT	20.50										1														727.75	719.33	719.43	723.27	719.33	723.24	
83	IL–91	STA. 118+75.00	LT	20.50	1																							727.75	724.09		724.09			
84	IL–91	STA. 119+91.16	LT	20.50										1														726.88	721.27	721.48	721.27			
85	IL–91	STA. 120+26.12	LT	37.68															1									726.12	721.79	722.34		721.79	722.4	
86	W. ASH ST.	STA. 009+44.92	RT	18.80					1																			725.90	723.65		723.65		723.75	
88	IL–91	STA. 120+49.83	LT	38.76														1										726.08	722.57			722.57	722.67	
90	IL–91	STA. 119+95.94	RT	45.00					1																			724.65	721.4				721.4	
91	IL–91	STA. 119+86.83	RT	20.50										1														726.91	719.86	720.34	721.2	719.86	720.06	
92	IL–91	STA. 121+14.73	RT	20.50													1											726.26	720.86	721.43		720.86	721.03	
93	IL–91	STA. 121+21.79	RT	20.50																								726.26	721.71	721.81		721.71		
94	IL–91	STA. 121+14.73	LT	20.50													1											726.26	721.24	721.49	721.24			
95	IL–91	STA. 121+21.79	LT	20.50																								726.26	721.81	721.93		721.81		
96	IL–91	STA. 121+71.22	LT	25.60						1																		725.75	722.16	722.26		722.16		
97	IL–91	STA. 122+00.00	LT	25.60						1																		725.55	722.42	722.52		722.42		
98	IL–91	STA. 122+44.57	LT	25.60						1																		726.07	722.94	723.14		722.94		
99	IL–91	STA. 122+60.00	LT	20.50	1																							726.69	723.36	723.82		723.36		
100	IL–91	STA. 123+43.31	LT	25.00			1																					726.72	724.22			724.22		
101	IL–91	STA. 122+44.57	RT	33.24			1																					724.64	722.64				722.64	
SUB–TOTAL 2					4	0	2	1	6	3	0	1	1	7	0	0	2	3	1	0	0	1	0	0	0	0	0							

FILE NAME =	USER NAME = crespole	DESIGNED -	REVISED -
c:\pw_work\pwidot\crespole\d0330150\D488792-sht-schedule of quantities.dgn		DRAWN -	REVISED -
	PLOT SCALE = 200.0000 ' / in.	CHECKED -	REVISED -
Default	PLOT DATE = 8/15/2013	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SECHEDULE OF QUANTITIES

SCALE: SHEET OF SHEETS STA. TO STA.

F.A.S RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1380	7W-1,RS-3	Peoria	617	50

CONTRACT NO. 88792

ILLINOIS FED. AID PROJECT