GENERAL NOTES

- 1. Reinforcement bars shall conform to the requirements of ASTM A 706 Gr 60.
- 2. Reinforcement bars designated (E) shall be epoxy coated.
- 3. All construction joints shall be bonded..

1. General Plan & Elevation
2. General Notes
3. Wall Facing Section Panel 1 - 7
4. Wall Detail Panel 1-4
5. Wall Detail Panel 5-7
6. A.D.A. Ramps Detail

TOTAL BILL OF MATERIAL

Item	Unit	Total
Reinforcement Bars, Epoxy Coated	Pound	4,912
Concrete Structure	Cu. Yd.	63
Porous Granular Embankment	Cu. Yd.	36
Pipe Handrail	Foot	153.30

FILE NAME =	USER NAME = crespole	DESIGNED -	REVISED -	STATE OF ILLINOIS		GENERAL NOTES AND DETAILS		A.S.	SECTION	COUNTY TOT	TAL SHEET
c:\pw_work\pwidot\crespole\d0330150\D48	792-sht-details.dgn	DRAWN -	REVISED -					380	7W-1,RS-3	Peoria 61	517 322
	PLOT SCALE = 40.0000 ' / in.	CHECKED -	REVISED -	DEPARTMENT OF TRANSPORTATION	CONCRETE STRUCTURE NO. 2				· · · ·	CONTRACT NO.	
Default	PLOT DATE = 8/15/2013	DATE -	REVISED -		SCALE: SHEET 2 OF 9 SHEETS STA. TO STA.				ILLINOIS FED. AID PROJECT		

INDEX OF SHEETS