

| CODE NO. | ITEM | UNIT | TOTAL QUANTITY | PATH 0028 | RETAINING WALL 0044 | TRAFFIC SIGNALS 0021 | TRAINEES 0042 |
|------------|---|-------|----------------|-------------------|---------------------|----------------------|-------------------|
| | | | | 75% FED 25% LOCAL | 75% FED 25% LOCAL | 75% FED 25% LOCAL | 75% FED 25% LOCAL |
| | | | | URBAN | URBAN | URBAN | URBAN |
| 50200100 | STRUCTURE EXCAVATION | CU YD | 1,161 | | 1,161 | | |
| 50300225 | CONCRETE STRUCTURES | CU YD | 196 | | 196 | | |
| 50300300 | PROTECTIVE COAT | SQ YD | 248 | | 248 | | |
| 50800205 | REINFORCEMENT BARS, EPOXY COATED | POUND | 33,230 | | 33,230 | | |
| + 50901760 | PIPE HANDRAIL | FOOT | 971 | | 971 | | |
| 52200700 | PRECAST MODULAR RETAINING WALL | SQ FT | 798 | | 798 | | |
| 54213657 | PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12" | EACH | 1 | 1 | | | |
| 54213663 | PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18" | EACH | 1 | 1 | | | |
| 550A2320 | STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 1 12" | FOOT | 38 | 38 | | | |
| 550A2340 | STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 1 18" | FOOT | 8 | 8 | | | |
| 550A2520 | STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 2 12" | FOOT | 12 | 12 | | | |
| 59100100 | GEOCOMPOSITE WALL DRAIN | SQ YD | 217 | | 217 | | |
| 60220200 | MANHOLES, TYPE A, 4'-DIAMETER | EACH | 2 | 2 | | | |
| 60238800 | INLETS, TYPE A | EACH | 3 | 3 | | | |
| 60250500 | CATCH BASINS TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID | EACH | 1 | 1 | | | |

+ INDICATES SPECIALTY ITEM

MODEL: D:\p\h\1
FILE NAME: S:\0113800-3893\3852\07\Drawings\CADD\Microst\CADD_Sheets\007-500.dgn



| | | |
|----------------------------|--------------------|--------------------|
| USER NAME = StevenB | DESIGNED - MAG | REVISED - 1/3/2020 |
| PLOT SCALE = 2.0000' / in. | DRAWN - DJW | REVISIONS - |
| PLOT DATE = 1/3/2020 | CHECKED - SJG | REVISIONS - |
| | DATE - \$PLANDATES | REVISIONS - |

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET OF SHEETS STA. TO STA.

| F.A.U. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
|--------------------|----------------|--------|---------------------------|-----------|
| 2561 | 11-00237-11-BT | DUPAGE | 193 | 6 |
| CONTRACT NO. 61F74 | | | ILLINOIS FED. AID PROJECT | |