

January 2, 2008

SUBJECT: FAP Route 351 Section 2007-025I Will County Contract No. 60C93 Item No. 17, January 18, 2008 Letting Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

- 1. Revised page 1 of the Schedule of Prices.
- 2. Revised page i of the Table of Contents to the Special Provisions.
- 3. Revised pages 36 & 37 of the Special Provisions.
- 4. Revised sheet 3 of the Plans.

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

Eric E. Harm Interim Bureau Chief Bureau of Design and Environment

Tester abschleger A.E.

By: Ted B. Walschleger, P. E. Engineer of Project Management

cc: Diane O'Keefe, Region 1, District 1; Roger Driskell; Estimates

TBW:MS:jc

ILLINOIS DEPARTMENT OF TRANSPORTATION SCHEDULE OF PRICES CONTRACT 60C93 NUMBER -

Project Number

C-91-278-07 State Job # -PPS NBR -1-70212-0100 County Name -WILL--Code -197 - -District -1 - -

Section Number - 2007-0251

ltem Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
X0322256	TEMP INFO SIGNING	SQ FT	125.000				
X0323077	SILICONE JT SEAL 2.75	FOOT	46.000				
X0325305	STR REP CON DP = < 5	SQ FT	1,155.000				
* DELETED							
X7011005	TR CONT-PROT TEMP DET	L SUM	1.000				
Z0001800	APPROACH SL REP (PD)	SQ YD	11.000				
Z0006100	BR DK LATEX CON OVLAY	SQ YD	14,990.000				
* DELETED							
* Z0006229	BR DECK HY-SCAR 3	SQ YD	14,990.000				
Z0016002	DECK SLAB REP (FD-T2)	SQ YD	168.000				
Z0048665	RR PROT LIABILITY INS	L SUM	1.000				
50157300	PROTECTIVE SHIELD	SQ YD	3,702.000				
50300260	BR DECK GROOVING	SQ YD	14,285.000				
67000400	ENGR FIELD OFFICE A	CAL MO	5.000				
67100100	MOBILIZATION	L SUM	1.000				
70106800	CHANGEABLE MESSAGE SN	CAL MO	2.000				
		* REVIS	ED : DECEMBER 31, 2007				

Page 1 1/3/2008

Route FAP 351

TABLE OF CONTENTS

LOCATION OF PROJECT	1
DESCRIPTION OF PROJECT	1
COMPLETION DATE PLUS WORKING DAYS	1
TRAFFIC CONTROL AND PROTECTION FOR TEMPORARY DETOUR	2
TRAFFIC CONTROL PLAN	2
TEMPORARY INFORMATION SIGNING	3
EPOXY COATING ON REINFORCEMENT (DISTRICT ONE)	
DECK SLAB REPAIR	4
BRIDGE DECK LATEX CONCRETE OVERLAY	9
SILICONE BRIDGE JOINT SEALER	20
STRUCTURAL REPAIR OF CONCRETE	23
APPROACH SLAB REPAIR	31
RAILROAD PROTECTIVE LIABILITY INSURANCE (5 AND 10)(BDE)	
EXHIBIT A	
ALKALI-SILICA REACTION FOR CAST-IN-PLACE CONCRETE (BDE)	45
CEMENT (BDE)	47
DISADVANTAGED BUSINESS ENTERPRISE PARTICIPATION (BDE)	50
ENGINEER'S FIELD OFFICE TYPE A (BDE)	57
EPOXY PAVEMENT MARKINGS (BDE)	58
EQUIPMENT RENTAL RATES (BDE)	60
PAYMENTS TO SUBCONTRACTORS (BDE)	61
PORTLAND CEMENT CONCRETE PLANTS (BDE)	62
REFLECTIVE SHEETING ON CHANNELIZING DEVICES (BDE)	
REINFORCEMENT BARS (BDE)	64
SELF-CONSOLIDATING CONCRETE FOR CAST-IN-PLACE CONSTRUCTION (BI	DE)65
SUBCONTRACTOR MOBILIZATION PAYMENTS (BDE)	69
WATER BLASTER WITH VACUUM RECOVERY (BDE)	69
STEEL COST ADJUSTMENT (BDE) (RETURN FORM WITH BID)	70
	Revised 01/02/2008

Construction equipment will be permitted on a patch during the cure period if the concrete has obtained the minimum required strength. In this instance, the strength specimens shall be cured with the patch.

Method of Measurement.

When specified, hot-mix asphalt surface removal and full or partial depth repairs will be measured for payment and computed in square yards (square meters).

Basis of Payment.

The hot-mix asphalt surface removal will be paid for at the contract unit price per square yard (square meter) for HOT-MIX ASPHALT SURFACE REMOVAL (DECK). Areas removed and replaced up to and including a depth of 5 1/2 inches (140 mm) or as specified will be paid for at the contract unit price per square yard (square meter) for APPROACH SLAB REPAIR (PARTIAL DEPTH). Areas requiring removal greater than a depth of 5 1/2 inches (140 mm) shall be removed and replaced full depth and will be paid for at the contract unit price per square yard (square meter) for APPROACH SLAB REPAIR (PARTIAL DEPTH).

When corroded reinforcement bars are encountered in the performance of this work and replacement is required, the Contractor will be paid according to Article 109.04 of the Standard Specifications.

No payment will be allowed for removal and replacement of reinforcement bars damaged by the Contractor in the performance of his/her work or for any increases in dimensions needed to provide splices for these replacement bars.

Removal and disposal of asbestos waterproofing and/or asbestos hot-mix asphalt will be paid for as specified in the Special Provision for "Asbestos Waterproofing Membrane or Asbestos Bituminous Concrete Surface Removal".

Revised 01/02/2008

RAILROAD PROTECTIVE LIABILITY INSURANCE (5 AND 10)(BDE)

Effective: December 1, 1986

Revised: January 1, 2006

<u>Description</u>. Railroad Protective Liability and Property Damage Liability Insurance shall be carried according to Article 107.11 of the Standard Specifications, expect the limits shall be a minimum of \$5,000,000 combined single limit occurrence for bodily injury liability and property damage liability with an aggregate limit of \$10,000,000 over the life of the policy. A separate policy is required for each railroad unless otherwise noted.

NAMED INSURED & ADDRESS	NUMBER & SPEED OF PASSENGER TRAINS	NUMBER & SPEED OF FREIGHT TRAINS
BNSF Railway Company 547 West Jackson Blvd Suite 1509. Chicago, IL 60661	0	52 Trains / day at 55 MPH
DOT/AAR No.: 0043314B	RR Mile Post:	12.35
RR Division: Chicago	RR Sub-Division:	Chillicothe
For Freight/Passenger Information Cont	Phone: 312-850-5680	
For Insurance Information Contact: Jan	Phone: 817-352-3485	

<u>Approval of Insurance</u>. The original and one certified copy of each required policy shall be submitted to the following address for approval:

Illinois Department of Transportation Bureau of Design and Environment 2300 South Dirksen Parkway, Room 326 Springfield, Illinois 62764

The Contractor will be advised when the Department has received approval of the insurance from the railroad(s). Before any work begins on railroad right-of-way, the Contractor shall submit to the Engineer evidence that the required insurance has been approved by the railroad(s). The Contractor shall also provide the Engineer with the expiration date of each required policy.

<u>Basis of Payment</u>. Providing Railroad Protective Liability and Property Damage Liability Insurance will be paid for at the contract unit price per Lump Sum for RAILROAD PROTECTIVE LIABILITY INSURANCE.

Revised 01/02/2008