


CODE NO.	DESCRIPTION	UNIT	TOTAL QUANTITY	901 FED. AID STATE ROADWAY 1000-2A
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	0.3	0.3
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	12	12
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	175	175
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	180	180
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	1240	1240
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	785	785
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	125	125
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	1380	1380
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	34	34
63300115	REMOVAL AND REINSTALLATION OF EXISTING STEEL PLATE BEAM GUARDRAIL, SINGLE RAIL	FOOT	125	125
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	1	1
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1	1
70102550	TRAFFIC CONTROL AND PROTECTION FOR TEMPORARY DETOUR	EACH	1	1
70300200	TEMPORARY PAVEMENT MARKING	FOOT	1400	1400
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	960	960
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	414	414
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	70	70
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	26	26

* SPECIALTY ITEM

FILE NAME = N:\PROJECTS\3329\3329_02\Design\Misc\Sheet\3329-02-500.dgn

 Ciorba Group, Inc. CONSULTING ENGINEERS 5507 North Cumberland Avenue, Suite 402 Chicago, Illinois 60656 Tel. 773.775.4009 Fax 773.775.4014	USER NAME = dmorris DESIGNED - WBL DRAWN - MLB CHECKED - MJL DATE - 9/19/2007	REVISED - REVISED - REVISED - REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	FAP ROUTE 347 ILLINOIS ROUTE 38 SUMMARY OF QUANTITIES	F.A.P. RTE. 347 SECTION (C&J) R-RS-2 COUNTY TOTAL SHEETS 18 SHEET NO. 3	DU PAGE 18 CONTRACT NO. 60D42	SCALE: NO SCALE SHEET NO. 1 OF 1 SHEETS STA. TO STA.	FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT
	PLOT SCALE = 1/8" = 1.0000' / IN. PLOT DATE = 10/29/2007	DATE - 9/19/2007			REVISED -			