

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEET SHEETS	NO.
10B	116T-1	STEPHENSON	78	8
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

48101500	AGGREGATE SHOULDERS, TYPE B 6"			
<u>SO YD</u>	<u>LOCATION</u>			
21	STA. 1042+58.9	TO	STA. 1043+33.9	LT
354	STA. 1043+90.1	TO	STA. 1052+50	LT
169	STA. 1048+69.9	TO	STA. 1052+50	LT

544 TOTAL

48203021	HOT-MIX ASPHALT SHOULDERS, 6"			
<u>SO YD</u>	<u>LOCATION</u>			
898	STA. 962+05	TO	STA. 969+88	RT
476	STA. 964+45	TO	STA. 968+91	LT
46	STA. 1038+85	TO	STA. 1040+42	RT
569	STA. 1041+48	TO	STA. 1048+70	RT

1989 TOTAL

50105200 REMOVE EXISTING CULVERTS

<u>EACH</u>	<u>LOCATION</u>
1	STA. 1043+61.4 LT
1	STA. 964+25.7 RT

2 TOTAL

54002020 EXPANSION BOLTS 3/4 INCH

<u>EACH</u>	<u>LOCATION</u>
12	STA. 1044+62 LT
12	TOTAL

542A1105 PIPE CULVERTS, CLASS A, TYPE 2 60"

<u>FOOT</u>	<u>LOCATION</u>
78	STA. 1044+62 (CULVERT)
78	TOTAL

542D0220 PIPE CULVERTS, CLASS D, TYPE 1 15"

<u>FOOT</u>	<u>LOCATION</u>
50	STA. 1046+65.9 RT
50	TOTAL

542D0223 PIPE CULVERTS, CLASS D, TYPE 1 18"

<u>FOOT</u>	<u>LOCATION</u>
60	STA. 1043+61.4 LT
60	TOTAL

542D0241 PIPE CULVERTS, CLASS D, TYPE 1 36"

<u>FOOT</u>	<u>LOCATION</u>
62	STA. 964+25.7 RT
62	TOTAL

5421D048 PIPE CULVERTS, CLASS D, TYPE 1 48" (TEMPORARY)

<u>FOOT</u>	<u>LOCATION</u>
24	STA. 1044+62 LT
24	TOTAL

54213450 END SECTIONS 15"

<u>EACH</u>	<u>LOCATION</u>
2	STA. 1046+65.9 RT
2	TOTAL

54213453 END SECTIONS 18"

<u>EACH</u>	<u>LOCATION</u>
2	STA. 1043+61.4 LT
2	TOTAL

54213471 END SECTIONS 36"

<u>EACH</u>	<u>LOCATION</u>
2	STA. 964+25.7 RT
2	TOTAL

54213495 END SECTIONS 60"

<u>EACH</u>	<u>LOCATION</u>
1	STA. 1044+62 RT (CULVERT)
1	TOTAL

54248510 CONCRETE COLLAR

<u>CU YD</u>	<u>LOCATION</u>
0.6	STA. 1044+62 LT
0.6	TOTAL

63000000 STEEL PLATE BEAM GUARD RAIL, TYPE A

<u>FOOT</u>	<u>LOCATION</u>
237.5	STA. 965+30.3 TO STA. 968+65.9 RT
50	STA. 965+27.0 TO STA. 967+52.8 LT
287.5	TOTAL

63100169 TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (FLARED)

<u>EACH</u>	<u>LOCATION</u>
1	STA. 965+27.0 LT
1	STA. 967+52.8 LT
1	STA. 965+30.3 RT
1	STA. 968+65.9 RT
4	TOTAL

63200310 GUARDRAIL REMOVAL

<u>FOOT</u>	<u>LOCATION</u>
128	STA. 965+44.9 TO STA. 967+48.8 LT
191	STA. 965+70.9 TO STA. 967+61.6 RT
319	TOTAL

63301210 REMOVE AND RE-ERECT STEEL PLATE BEAM GUARD RAIL, TYPE A

<u>FOOT</u>	<u>LOCATION</u>
75	STA. 965+44.9 TO STA. 967+48.8 LT
75	TOTAL

63500105 DELINEATORS

<u>EACH</u>	<u>LOCATION</u>
4	STA. 966+60 LT & RT (CULVERT)
4	STA. 1044+62 LT & RT (CULVERT)
1	STA. 965+27.0 LT
1	STA. 967+52.8 LT
1	STA. 965+30.3 RT
1	STA. 968+65.9 RT
12	TOTAL

66600105 FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS

<u>EACH</u>	<u>LOCATION</u>
1	STA. 963+50 RT
1	STA. 964+00 RT
1	STA. 965+50 RT
1	STA. 966+50 RT
1	STA. 968+00 RT
1	STA. 969+00 RT
1	STA. 970+00 RT
1	STA. 964+53.71 LT
1	STA. 966+50 LT
1	STA. 967+00 LT
1	STA. 968+50 LT
1	STA. 969+00 LT
1	STA. 1040+50 RT
1	STA. 1040+85 RT
1	STA. 1043+00 RT
1	STA. 1043+20 RT
1	STA. 1043+80 RT
1	STA. 1044+65 RT
1	STA. 1046+50 RT
1	STA. 1048+00 RT
1	STA. 1049+00 RT
1	STA. 1052+00 RT
1	STA. 1052+75 RT
1	STA. 1043+00 LT
1	STA. 1043+35 LT
1	STA. 1046+00 LT
1	STA. 1047+50 LT
1	STA. 1051+50 LT
1	STA. 1052+75 LT

29 TOTAL

66700305 PERMANENT SURVEY MARKERS, TYPE II

<u>EACH</u>	<u>LOCATION</u>
1	STA. 966+60 (CULVERT)
1	STA. 1044+62 (CULVERT)
2	TOTAL

70106500 TEMPORARY BRIDGE TRAFFIC SIGNALS

<u>EACH</u>	<u>LOCATION</u>
1	STA. 966+60 (CULVERT)
1	STA. 1044+62 (CULVERT)
2	TOTAL

70106700 TEMPORARY RUMBLE STRIP

<u>EACH</u>	<u>LOCATION</u>
1	STA. 945+15.4 RT
1	STA. 950+15.4 RT
1	STA. 955+15.4 RT
1	STA. 977+99.8 LT
1	STA. 982+99.8 LT
1	STA. 987+99.8 LT
1	STA. 1032+90.0 RT
1	STA. 1027+90.0 RT
1	STA. 1022+90.0 RT
1	STA. 1055+66.9 LT
1	STA. 1060+66.9 LT
1	STA. 1065+66.9 LT

12 TOTAL

70300100 SHORT-TERM PAVEMENT MARKING

<u>FOOT</u>	<u>LOCATION</u>	4 FOOT @ 40 FEET
8	STA. 966+05.0 TO STA. 967+05.0	YELLOW CENTERLINE
4	STA. 1044+42.0 TO STA. 1044+83.0	YELLOW CENTERLINE
12	TOTAL	

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF QUANTITIES
 IL RTE 73 CULVERT REPLACEMENTS

SCALE: VERT.: N.A.
 HORIZ.: 1:20
 DATE: OCTOBER 1, 2007
 DRAWN BY: DLZ
 CHECKED BY: GB