

ROUTE NO.	SECTION	COUNTY	DIST.	SHEET
FAP 313	(7BY)BR	HENDERSON	68	3
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

IDOT HIGHWAY STANDARDS

- 000001-05 STANDARD SYMBOLS, ABBREVIATIONS, AND PATTERNS
- 001001-01 AREAS OF REINFORCEMENT BARS
- 280001-04 TEMPORARY EROSION CONTROL SYSTEMS
- 406201-c1 MAILBOX TURNOUTS
- 420001-07 PAVEMENT JOINTS
- 420401-06 BRIDGE APPROACH PAVEMENT
- 421001-02 BAR REINFORCEMENT FOR CRC PAVEMENT
- 482001-02 HMA SHOULDERS ADJACENT TO FLEXIBLE PAVEMENT
- 482011-03 HMA SHOULDER STRIPS/SHOULDER WITH RESURFACING OR WIDENING AND RESURFACING PROJECTS
- 515001-02 NAME PLATE FOR BRIDGES
- 542401 METAL END SECTION FOR PIPE CULVERTS
- 601001-07 CONCRETE HEADWALL FOR PIPE DRAIN
- 630001-07 STEEL PLATE BEAM GUARDRAIL
- 630301-04 SHOULDER WIDENING FOR TYPE 1, (SPECIAL) GUARDRAIL TERMINALS
- 631031-06 TRAFFIC BARRIER TERMINAL, TYPE 6
- 635006-02 REFLECTOR AND TERMINAL MARKER PLACEMENT
- 635011-01 REFLECTOR MARKER AND MOUNTING DETAILS
- 666001 RIGHT -OF-WAY MARKERS
- 701006-02 OFF-ROAD OPERATIONS 2L, 2W, 4.5M (15') TO 600 MM (24") FROM PAVEMENT EDGE
- 701011-01 OFF-ROAD MOVING OPERATIONS 2L, 2W, DAY ONLY
- 701301-02 LANE CLOSURE, 2L, 2W, SHORT TIME OPERATIONS
- 701306-01 LANE CLOSURE, 2L, 2W, SLOW MOVING OPERATIONS - DAY ONLY FOR SPEEDS > 45 MPH
- 701311-02 LANE CLOSURE, 2L, 2W, MOVING OPERATIONS, DAY ONLY
- 701326-02 LANE CLOSURE, 2L, 2W, PAVEMENT WIDENING FOR SPEEDS > 45 MPH
- 701331-02 LANE CLOSURE, 2L, 2W, WITH RUN-AROUND, FOR SPEEDS > 45 MPH
- 701901 TRAFFIC CONTROL DEVICES
- 780001-01 TYPICAL PAVEMENT MARKINGS
- 781001-02 TYPICAL APPLICATIONS RAISED REFLECTIVE PAVEMENT MARKERS

DISTRICT 4 CADD STANDARDS

- 205001-D4 SLOPE STEPS DETAIL
- 280001-D4 TYPICAL APPLICATION OF SILT FILTER FENCE
- 280101-D4 EROSION CONTROL AGGREGATE DITCH CHECK
- 406101-D4 BUTT JOINTS
- 440001-D4 HOT-MIX ASPHALT SURFACE REMOVAL (COLD MILLING)
- 630101-D4 GUARDRAIL EROSION CONTROL TREATMENTS
- 635101-D4 GUARDRAIL AND BARRIER WALL DELINEATION
- 667101-D4 PERMANENT SURVEY TIE & PERMANENT SURVEY MARKERS TY.I - TY.II
- 701331-D4 LANE CLOSURE, 2L, 2W, WITH RUNAROUND ADJACENT TO EXISTING PAVEMENT FOR SPEEDS ≥ 45MPH (STANDARD 701331, SPECIAL)
- 780001-D4 TYPICAL PAVEMENT MARKINGS

STATUS OF UTILITIES TO BE ADJUSTED DURING CONSTRUCTION

NAME AND ADDRESS OF UTILITY
FRONTIER

ROUTE: FAP 313
SECTION: (7BY)BR
COUNTY: HENDERSON
CONTRACT NO.: 68149
CATALOG NO.: 031941-000

OFFSET	LOCATION	TYPE OF UTILITY	TYPE OF CONFLICT	DISPOSITION
60' RT. TO 60' RT.	294+00 TO 306+00	BURIED COPPER CABLE	NEW RUN AROUND	CAUTION
40' LT. TO 40' LT.	300+80 TO 302+25	AERIAL COPPER CABLE	STRUCTURE REPLACEMENT EXCAVATION	RELOCATE
40' LT. TO 50' LT.	302+25 TO 306+00	BURIED COPPER CABLE	FILL	CAUTION
70' RT. TO 60' RT.	294+20 TO 306+00	BURIED TELEPHONE CABLE	NEW RUN AROUND	CAUTION
70' RT.	294+50	TELEPHONE SPLICE BOX	NEW RUN AROUND	RELOCATE
70' RT.	297+00	TELEPHONE SPLICE BOX	NEW RUN AROUND	RELOCATE
70' RT.	303+05	TELEPHONE SPLICE BOX	NEW RUN AROUND	RELOCATE
70' RT.	305+80	TELEPHONE SPLICE BOX	NEW RUN AROUND	RELOCATE

NAME AND ADDRESS OF UTILITY
NICOR

OFFSET	LOCATION	TYPE OF UTILITY	TYPE OF CONFLICT	DISPOSITION
65' RT. TO 65' RT.	296+00 TO 305+50	10" GAS LINE	UNDER TEMPORARY RUN AROUND	CAUTION
83' RT.	303+50	GAS LINE	UNDER TEMPORARY RUN AROUND DITCH	CAUTION

NAME AND ADDRESS OF UTILITY
LIGHT CORP.

OFFSET	LOCATION	TYPE OF UTILITY	TYPE OF CONFLICT	DISPOSITION
65' RT. TO 65' RT.	294+20 TO 307+00	BURIED FIBER OPTIC	RUN AROUND	CAUTION

NAME AND ADDRESS OF UTILITY
MEDIACOM COMMUNICATIONS

OFFSET	LOCATION	TYPE OF UTILITY	TYPE OF CONFLICT	DISPOSITION
70' RT. TO 70' RT.	296+00 TO 306+00	TV CABLE	NEW RUN AROUND	CAUTION

NAME AND ADDRESS OF UTILITY
ILLINOIS POWER

OFFSET	LOCATION	TYPE OF UTILITY	TYPE OF CONFLICT	DISPOSITION
70' RT.	295+90	POWER POLE	BEGINNING NEW RUN AROUND	CAUTION
70' RT.	300+03	POWER POLE	NEW RUN AROUND	RELOCATE
70' RT.	304+23	POWER POLE	NEW RUN AROUND	RELOCATE
70' RT. TO 70' RT.	295+90 TO 307+00	POWER POLE	NEW RUN AROUND	RELOCATE

THE ABOVE REPRESENTS THE BEST INFORMATION OF THE DEPARTMENT AND IS ONLY INCLUDED FOR THE CONVENIENCE OF THE BIDDER. THE APPLICABLE PROVISION OF ARTICLES 102.05, 105.07, 107.20, AND 107.31 OF THE STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION SHALL APPLY.

HAMPTON, LENZINI & RENWICK, INC.
CIVIL & STRUCTURAL ENGINEERS

3085 STEVENSON DRIVE, SUITE 201
SPRINGFIELD, ILLINOIS 62703
(217) 548-3400

ELGIN • SPRINGFIELD

PROJECT NUMBER: 12-44-0001-X DATE: 08/07/07
DESIGNED: W.D.G. CHECKED: L.F.S. DRAWN: W.J.S.

STANDARDS & UTILITY STATUS

U.S. 34 OVER P.D. CREEK
F.A.P. 313 / SECTION (7BY)BR
HENDERSON COUNTY
STRUCTURE NO. 036-0052 / STATION 301+23