

SUMMARY OF QUANTITIES			100% STATE SFTY-2A TOTAL QUANTITIES	CONSTRUCTION TYPE CODE STRUCTURE NUMBER 026-0049
CODE NO	ITEM	UNIT		
35400300	PORTLAND CEMENT CONCRETE BASE COURSE WIDENING 8"	SQ YD	233	233
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	27	27
40600300	AGGREGATE (PRIME COAT)	TON	1	1
40603545	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	97	97
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	269	269
44000156	HOT-MIX ASPHALT SURFACE REMOVAL, 1 3/4"	SQ YD	890	890
48101200	AGGREGATE SHOULDERS, TYPE B	TON	15	15
50102400	CONCRETE REMOVAL	CU YD	11.4	11.4
50157300	PROTECTIVE SHIELD	SQ YD	249	249
50300255	CONCRETE SUPERSTRUCTURE	CU YD	13.2	13.2
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	1270	1270
50500715	JACK AND REMOVE EXISTING BEARINGS	EACH	12	12
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	1630	1630
50800515	BAR SPLICERS	EACH	30	30
52000110	PREFORMED JOINT STRIP SEAL	FOOT	75	75
52100020	ELASTOMERIC BEARING ASSEMBLY, TYPE II	EACH	12	12
52100520	ANCHOR BOLTS, 1"	EACH	24	24
58100200	WATERPROOFING MEMBRANE SYSTEM	SQ YD	890	890
67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL MO	5	5
67100100	MOBILIZATION	L SUM	1	1
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1	1
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1	1
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	4	4
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1	1
70106700	TEMPORARY RUMBLE STRIP	EACH	6	6
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	94	94
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	3160	3160
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	347	347
70400100	TEMPORARY CONCRETE BARRIER	FOOT	675	675

SUMMARY OF QUANTITIES			100% STATE SFTY-2A TOTAL QUANTITIES	CONSTRUCTION TYPE CODE STRUCTURE NUMBER 026-0049
CODE NO	ITEM	UNIT		
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	675	675
* 78000812	45 MIL HOT SPRAY THERMOPLASTIC PAVEMENT MARKING LINE - 4 INCH	FOOT	3028	3028
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	2	2
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	2	2
* 78100300	REPLACEMENT REFLECTOR	EACH	8	8
78300100	PAVEMENT MARKING REMOVAL	SQ FT	781	781
X0322050	RAISED REFLECTIVE PAVEMENT MARKER, REFLECTOR REMOVAL	EACH	8	8
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	30	30
Z0030240	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 2	EACH	2	2
Z0016001	DECK SLAB REPAIR (FULL DEPTH, TYPE I)	SQ YD	3	3
Z0016002	DECK SLAB REPAIR (FULL DEPTH, TYPE II)	SQ YD	25	25
Z0016200	DECK SLAB REPAIR (PARTIAL)	SQ YD	78	78
Z0030340	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE) TEST LEVEL 2	EACH	2	2

*SPECIALTY ITEMS

Rev.

FILE NAME =	USER NAME = #USER#	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
#FILE#		DRAWN -	REVISED -			752		FAYETTE		3	
	PLOT SCALE = #SCALE#	CHECKED -	REVISED -			CONTRACT NO. 74276					
	PLOT DATE = #DATE#	DATE -	REVISED -			SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.