

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1362	06-0047-00-LS	COOK	59	4
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SUMMARY OF QUANTITIES

IDOT PAY ITEM	DESCRIPTION	UNIT	1000-2A	7000-2A	Y003	Y030-IE	Y003 NON-PARTICIPATING	TOTAL QUANTITY
20100110	TREE REMOVAL (8 TO 15 UNITS DIAMETER)	UNIT	0	0	118	0	0	118
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	0	0	38	0	0	38
20101100	TREE TRUNK PROTECTION	EACH	0	0	5	0	0	5
20101200	TREE ROOT PRUNING	EACH	0	0	10	0	0	10
20203100	EARTH EXCAVATION	CY	0	2190	0	0	0	2190
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CY	0	337	0	0	0	337
20700420	POROUS GRANULAR EMBANKMENT, SUBGRADE	CY	0	337	0	0	0	337
20800250	TRENCH BACKFILL, SPECIAL	CY	530	0	0	0	0	530
21101515	TOPSOIL FURNISH AND PLACE 4"	SY	0	0	898	0	0	898
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	0	0	12	0	0	12
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	0	0	12	0	0	12
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	0	0	12	0	0	12
25100105	MULCH METHOD	ACRE	0	0	0.1	0	0	0.1
25200110	SODDING, SALT TOLERANT	SY	0	0	828	0	0	828
25200200	SUPPLEMENTAL WATERING	UNIT	0	0	5	0	0	5
28000510	INLET FILTERS	EACH	55	0	0	0	0	55
31101200	SUB-BASE GRANULAR MATERIAL, TYPE B 4"	SY	0	1061	0	0	0	1061
35101400	AGGREGATE BASE COURSE, TYPE B	TON	114	0	0	0	0	114
35300400	PORTLAND CEMENT CONCRETE BASE COURSE 6"	SY	0	1773	0	0	0	1773
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	500	0	0	0	0	500
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GAL	0	1289	0	0	0	1289
40600300	AGGREGATE (PRIME COAT)	TON	114	0	0	0	0	114
40603050	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	0	28	0	0	0	28
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	0	229	0	0	0	229
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	20	0	0	0	0	20
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	112	0	0	0	0	112
42300500	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT 6"	SY	534	0	0	0	0	534
42400430	PORTLAND CEMENT CONCRETE SIDEWALK 3" INCH, SPECIAL	SF	0	0	24270	0	0	24270
44000100	PAVEMENT REMOVAL	SY	0	790	0	0	0	790
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SY	10363	0	0	0	0	10363
44000200	DRIVEWAY PAVEMENT REMOVAL	SF	2045	0	0	0	0	2045
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	0	3839	0	0	0	3839
44000600	SIDEWALK REMOVAL	SF	0	0	9315	0	0	9315
44002122	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3"	SY	318	0	0	0	0	318
44200348	CLASS B PATCHES, TYPE I, 9 INCH	SY	23	0	0	0	0	23
44200956	CLASS B PATCHES, TYPE II, 9 INCH	SY	66	0	0	0	0	66
44200962	CLASS B PATCHES, TYPE III, 9 INCH	SY	79	0	0	0	0	79
44200964	CLASS B PATCHES, TYPE IV, 9 INCH	SY	151	0	0	0	0	151
55019500	STORM SEWERS, TYPE I, R.C.C. STORM DRAIN, AND SEWER PIPE, CLASS IV 12"	FOOT	826	0	0	0	0	826
55019600	STORM SEWERS, TYPE I, R.C.C. STORM DRAIN, AND SEWER PIPE, CLASS IV 18"	FOOT	15	0	0	0	0	15
55019700	STORM SEWERS, TYPE I, R.C.C. STORM DRAIN, AND SEWER PIPE, CLASS IV 18"	FOOT	86	0	0	0	0	86
55019800	STORM SEWERS, TYPE I, R.C.C. STORM DRAIN, AND SEWER PIPE, CLASS IV 24"	FOOT	81	0	0	0	0	81
55020300	STORM SEWERS, TYPE I, R.C.C. STORM DRAIN, AND SEWER PIPE, CLASS III 36"	FOOT	187	0	0	0	0	187
55100400	STORM SEWER REMOVAL 10"	FOOT	135	0	0	0	0	135
55100600	STORM SEWER REMOVAL 12"	FOOT	6	0	0	0	0	6
60107600	PIPE UNDERDRAINS 4"	FOOT	200	0	0	0	0	200
60200105	CATCH BASINS, TYPE A, 4" DIAMETER, TYPE I FRAME, OPEN LID	EACH	2	0	0	0	0	2
60201105	CATCH BASINS, TYPE A, 4" DIAMETER, TYPE II FRAME AND GRATE	EACH	18	0	0	0	0	18
60201110	CATCH BASINS, TYPE A, 4" DIAMETER, TYPE III FRAME AND GRATE	EACH	5	0	0	0	0	5
60204805	CATCH BASINS, TYPE A, 6" DIAMETER, TYPE II FRAME AND GRATE	EACH	6	0	0	0	0	6
60207905	CATCH BASINS, TYPE C, TYPE II FRAME AND GRATE	EACH	15	0	0	0	0	15
60207915	CATCH BASINS, TYPE C, TYPE III FRAME AND GRATE	EACH	2	0	0	0	0	2
60218400	MANHOLES, TYPE A, 4" DIAMETER, TYPE I FRAME, CLOSED LID	EACH	6	0	0	0	0	6
60221100	MANHOLES, TYPE A, 6" DIAMETER, TYPE I FRAME, CLOSED LID	EACH	11	0	0	0	0	11
60223800	MANHOLES, TYPE A, 6" DIAMETER, TYPE I FRAME, CLOSED LID	EACH	1	0	0	0	0	1
60250200	CATCH BASINS TO BE ADJUSTED	EACH	3	0	0	0	0	3
60255500	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE I FRAME, CLOSED LID	EACH	1	0	0	0	0	1
60255600	MANHOLES TO BE ADJUSTED	EACH	19	0	0	0	0	19
60255800	MANHOLES TO BE ADJUSTED WITH NEW TYPE I FRAME, CLOSED LID	EACH	5	0	0	0	0	5
60290100	INLETS TO BE ADJUSTED	EACH	3	0	0	0	0	3
60295700	VALVE VAULTS TO BE ADJUSTED	EACH	10	0	0	0	0	10
60500040	REMOVING MANHOLES	EACH	4	0	0	0	0	4
60500050	REMOVING CATCH BASINS	EACH	4	0	0	0	0	4
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-8-12	FOOT	0	3818	0	0	0	3818
68800200	NON-SPECIAL WASTE DISPOSAL	CY	50	0	0	0	0	50
68800400	SPECIAL WASTE GROUND WATER DISPOSAL	GAL	275	0	0	0	0	275
68800450	SPECIAL WASTE PLANS AND REPORT	L.SUM	1	0	0	0	0	1
68800530	SOIL DISPOSAL ANALYSIS	EACH	3	0	0	0	0	3
69901000	BACKFILL PLUGS	CY	30	0	0	0	0	30
67000400	ENGINEER'S FIELD OFFICE, TYPE A	GAL. MO.	7	0	0	0	0	7
67100100	MOBILIZATION	L.SUM	0	0	1	0	0	1

* SPECIALTY ITEM

IDOT PAY ITEM	DESCRIPTION	UNIT	1000-2A	7000-2A	Y003	Y030-IE	Y003 NON-PARTICIPATING	TOTAL QUANTITY
70102800	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L.SUM	1	0	0	0	0	1
70102802	TRAFFIC CONTROL AND PROTECTION, STANDARD 701502	L.SUM	1	0	0	0	0	1
70102825	TRAFFIC CONTROL AND PROTECTION, STANDARD 701605	L.SUM	1	0	0	0	0	1
70102832	TRAFFIC CONTROL AND PROTECTION, STANDARD 701602	L.SUM	1	0	0	0	0	1
70102835	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L.SUM	1	0	0	0	0	1
70102840	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L.SUM	1	0	0	0	0	1
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	13091	0	0	0	0	13091
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SF	4364	0	0	0	0	4364
72000100	SIGN PANEL - TYPE 1	SF	58	0	0	0	0	58
72600100	METAL POST - TYPE A	FOOT	86	0	0	0	0	86
78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SF	285	0	0	0	0	285
78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	10798	0	0	0	0	10798
78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	2263	0	0	0	0	2263
78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	84	0	0	0	0	84
78000800	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	176	0	0	0	0	176
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	120	0	0	0	0	120
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	120	0	0	0	0	120
80400100	ELECTRIC SERVICE INSTALLATION	EACH	0	0	0	1	0	1
81017510	CONDUIT IN TRENCH, 1" DIA, COILABLE NONMETALLIC CONDUIT	FOOT	0	0	0	110	0	110
81017520	CONDUIT IN TRENCH, 1 1/2" DIA, COILABLE NONMETALLIC CONDUIT	FOOT	0	0	0	2935	0	2935
81017525	CONDUIT IN TRENCH, 2" DIA, COILABLE NONMETALLIC CONDUIT	FOOT	0	0	0	309	0	309
81017545	CONDUIT IN TRENCH, 4" DIA, COILABLE NONMETALLIC CONDUIT	FOOT	0	0	0	1390	0	1390
81017555	CONDUIT IN TRENCH, 6" DIA, COILABLE NONMETALLIC CONDUIT	FOOT	0	0	0	1740	0	1740
81019800	CONDUIT PUSHED, 2 1/2" DIA, GALV. STEEL	FOOT	0	0	0	455	0	455
81019800	CONDUIT PUSHED, 4" DIA, GALV. STEEL	FOOT	0	0	0	100	0	100
81022400	CONDUIT ENCASED IN CONCRETE, 3" DIA, PVC	FOOT	0	0	0	309	0	309
81030800	CONDUIT BORED AND PULLED, COILABLE NONMETALLIC CONDUIT, 1 1/2"	FOOT	0	0	0	1100	0	1100
81030800	CONDUIT BORED AND PULLED, COILABLE NONMETALLIC CONDUIT, 2"	FOOT	0	0	0	100	0	100
81400730	HANDHOLE, COMPOSITE CONCRETE	EACH	0	0	0	8	0	8
81400200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	0	0	0	10605	0	10605
82502600	LIGHTING CONTROLLER TYPE 05-RCS 200AMP - 480 VOLT	EACH	0	0	0	1	0	1
83600200	LIGHT POLE FOUNDATION, 24" DIAMETER	FOOT	0	0	0	360	0	360
84200600	REMOVAL OF EXISTING LIGHTING UNIT NO SALVAGE	EACH	0	0	0	6	0	6
84200700	LIGHTING FOUNDATION REMOVAL	EACH	0	0	0	6	0	6
84500110	REMOVAL OF LIGHTING CONTROLLER	EACH	0	0	0	1	0	1
84500100	REMOVAL OF ELECTRIC SERVICE INSTALLATION	EACH	0	0	0	1	0	1
86600600	DETECTOR LOOP REPLACEMENT	FOOT	400	0	0	0	0	400
88800100	PEDESTRIAN PUSH-BUTTON	EACH	0	0	1	0	0	1
82000786	TREE AMELANCHIER X GRANDIFLORA AUTUMN BRILLIANCE (AUTUMN BRILLIANCE SERVICE BERRY), 6" HEIGHT, SHRUBFORM, BALLED AND BURLAPPED	EACH	0	0	11	0	0	11
82001286	TREE CORNUS ALTERNIFOLIA PACODA DOG WOOD, 8" HEIGHT, CLUMP FORM, BALLED AND BURLAPPED	EACH	0	0	8	0	0	8
82007916	SHRUB ROSA MEIPITAC (CAREFREE WONDER ROSE), 18" HEIGHT, CONTAINER	EACH	0	0	32	0	0	32
82012772	SHRUB VIBURNUM PRUNIFOLIUM (BLACKHAW VIBURNUM), 6" HEIGHT, BALLED AND BURLAPPED	EACH	0	0	4	0	0	4
82020918	SHRUB SPIREA X BUMAL DA GOLD FLAME (GOLD FLAME SPIREA), 18" HEIGHT, CONTAINER	EACH	0	0	88	0	0	88
D2001854	EVERGREEN, JUNIPERUS HORIZONTALIS WILTONII (BLUE RUG JUNIPER), 18" SPREAD BALLED AND BURLAPPED	EACH	0	0	7	0	0	7
D2001215	EVERGREEN, JUNIPERUS SABINA BROADMOOR (BROADMOOR JUNIPER), 18" WIDTH, BALLED AND BURLAPPED	EACH	0	0	2	0	0	2
D2003424	EVERGREEN, TAXUS X MEDIA BROWNII (BROWN ANGLAJAPANESE YEW), 2" WIDTH, BALLED AND BURLAPPED	EACH	0	0	20	0	0	20
X0300535	PLANTER	EACH	0	0	0	0	33	33
X0301467	PERENNIAL PLANTS, GALLON POT	UNIT	0	0	15	0	0	15
X0301787	WATER CONTROL STRUCTURE, TYPE A	EACH	1	0	0	0	0	1
X0320189	EXPOSED AGGREGATE SURFACE (SPECIAL)	SF	0	0	0	6103	0	6103
X0323426	SEDIMENT CONTROL, DRAINAGE STRUCTURE INLET FILTER CLEANING	EACH	55	0	0	0	0	55
X0444150	BENCHES	EACH	0	0	0	0	33	33
X0640000	BRICK PAVERS	SF	0	0	0	0	11471	11471
X4087107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	480	0	0	0	0	480
X6028300	INLETS TO BE REMOVED, SPECIAL	EACH	10	0	0	0	0	10
X8950200	REBUILD EXISTING HANDHOLE	EACH	4	0	0	0	0	4
X0003959	TRASH RECEPTACLES	EACH	0	0	0	0	7	7
X0001011	BICYCLE RACKS	EACH	0	0	0	0	19	19
X0003711	BUS SHELTER REMOVAL	EACH	0	0	1	0	0	1
X0004144	DRINKING FOUNTAIN	EACH	0	0	0	0	1	1
X0004145	CONCRETE PLANTER WALL	CU YD	0	0	1252	0	0	1252
X0004146	LIGHTING UNIT COMPLETE, TYPE F1	EACH	0	0	0	45	0	45
X0005293	BRICK PAVEMENT CROSSWALK	SF	0	0	0	0	6154	6154
X0005762	TREE CARPINUS CAROLINIANA (AMERICAN HORNBEAM), 1-3/4" CALIPER, BALLED AND BURLAPPED	EACH	0	0	25	0	0	25
X0005892	CLASS D PATCHES, 6" (SPECIAL)	SY	60	0	0	0	0	60
X0005471	STORM SEWERS, TYPE I, WATER MAIN QUALITY PIPE, SDR-21 12"	FOOT	236	0	0	0	0	236
20013758	CONSTRUCTION LAYOUT	L.SUM	1	0	0	0	0	1
20076600	TRAINERS	HOURLY	0	0	0	0	1000	1000
X0001200	BUS SHELTER PLATFORM	EACH	0	0	10	0	0	10
X0001200	LIGHT POLE COMPLETE IN PLACE, TYPE F1	EACH	0	0	45	0	0	45
X0001200	SKATEBOARD DETERRENT	FOOT	0	0	0	0	565	565
X0001200	TREE, TILIA CORDATA GLENLEVEN (GLENLEVEN LITTLE LEAF LINDEN) 2" CALIPER, BALLED AND BURLAPPED	EACH	0	0	7	0	0	7
X0001200	UNIT DUCT, 1" SCH							