

F.A.U. SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1512 05-00093-00-WR	DUPAGE	72	4
STA. TO STA.		FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT	
PROJECT NO.: M-8003 (699)			

SUMMARY OF QUANTITIES

SP	CODED PAY ITEM NUMBER	DESCRIPTION	UNIT OF MEASURE	TOTAL QUANTITY	ROADWAY 1000-2A		HIGHWAY LIGHTING Y030-1E	
					PARTICIPATING	NON-PARTICIPATING	PARTICIPATING	NON-PARTICIPATING
	20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	198	198	-	-	-
	20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	118	118	-	-	-
	20101000	TEMPORARY FENCE	FOOT	1,000	1,000	-	-	-
*	20101100	TREE TRUNK PROTECTION	EACH	59	59	-	-	-
*	20101300	TREE PRUNING (1 TO 10 INCH DIAMETER)	EACH	15	15	-	-	-
	20200100	EARTH EXCAVATION	CU YD	545	545	-	-	-
	20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	1,876	1,876	-	-	-
	20400800	FURNISHED EXCAVATION	CU YD	437	437	-	-	-
△	20700420	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	252	252	-	-	-
	20800150	TRENCH BACKFILL	CU YD	1,060	1,060	-	-	-
	21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	4,583	4,583	-	-	-
*	21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	4,013	4,013	-	-	-
*	25000400	NITROGEN FERTILIZER NUTRIENT	POUND	50	50	-	-	-
*	25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	50	50	-	-	-
*	25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	50	50	-	-	-
*	25100630	EROSION CONTROL BLANKET	SQ YD	4,013	4,013	-	-	-
*	25200110	SODDING, SALT TOLERANT	SQ YD	4,013	4,013	-	-	-
*	25200200	SUPPLEMENTAL WATERING	UNIT	37	37	-	-	-
*	28000400	PERIMETER EROSION BARRIER	FOOT	3,107	3,107	-	-	-
	28000510	INLET FILTERS	EACH	15	15	-	-	-
	40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	115	115	-	-	-
	40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	854	854	-	-	-
	40600300	AGGREGATE (PRIME COAT)	TON	10	10	-	-	-
	40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	131	131	-	-	-
	40701801	HOT-MIX ASPHALT PAVEMENT (FULL DEPTH), 6"	SQ YD	3,856	3,856	-	-	-
	42001300	PROTECTIVE COAT	SQ YD	2,444	2,444	-	-	-
	42400200	PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH	SQ FT	17,807	17,807	-	-	-
	42400800	DETECTABLE WARNINGS	SQ FT	56	56	-	-	-
	44000100	PAVEMENT REMOVAL	SQ YD	2,304	2,304	-	-	-
	44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	1,246	1,246	-	-	-
	44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	426	426	-	-	-
	44000600	SIDEWALK REMOVAL	SQ FT	523	523	-	-	-
△	50105210	REMOVE EXISTING CULVERTS	FOOT	266	266	-	-	-
	55019500	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 12"	FOOT	383	383	-	-	-
	55019700	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 18"	FOOT	299	299	-	-	-
	55019900	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 24"	FOOT	140	140	-	-	-
	55022100	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 27"	FOOT	229	229	-	-	-
	56300300	ADJUSTING WATER SERVICE LINES	FOOT	210	210	-	-	-
△	56500600	DOMESTIC WATER SERVICE BOXES TO BE ADJUSTED	EACH	9	9	-	-	-
	60200305	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 3 FRAME AND GRATE	EACH	9	9	-	-	-
	60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	2	2	-	-	-
	60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	3	3	-	-	-
	60223800	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1	-	-	-
△	60224090	MANHOLES, TYPE A, 6'-DIAMETER, WITH SPECIAL FRAME AND GRATE	EACH	1	1	-	-	-
	60255500	MANHOLES TO BE ADJUSTED	EACH	1	1	-	-	-
	60260100	INLETS TO BE ADJUSTED	EACH	2	2	-	-	-
	60500040	REMOVING MANHOLES	EACH	1	1	-	-	-

* INDICATES SPECIALTY ITEM
 △ INDICATES SPECIAL PROVISION

PLAN	SURVEYED	DATE
NOTE BOOK	ALIGNED	
NO.	RT. OF WAY CHECKED	
	DATE	
	BY	
	DATE	
	BY	
	DATE	

PROFILE	SURVEYED	DATE
NOTE BOOK	ALIGNED	
NO.	RT. OF WAY CHECKED	
	DATE	
	BY	
	DATE	
	BY	
	DATE	

PLOT DATE = #DATE#
 FILE NAME = #FILE#
 PLOT SCALE = #SCALE#
 USER NAME = #USER#

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		VILLAGE OF WESTMONT 59TH STREET RECONSTRUCTION SUMMARY OF QUANTITIES SHEET 1 OF 2 SCALE: N.T.S. DATE: 09/21/07
DRAWN BY: JMT		CHECKED BY: AJB
DATE: 09/21/07		