CONTRACT NO. 83985

F.A.U RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1512	05-00093-00-WR	DUPAGE	72	7
STA.		TO STA.		
FED. ROAD DIST. NO. 1	ILLINOIS FED. AID PROJECT			

PROJECT NO.: M-8003 (699)

TREE REMOVAL SCHEDULE 6 TO 15 UNITS DIAMETER

STA.	OFFSET	UNITS
101+04.77	20.04' LT	10
101+19.03	20.10' LT	10
101+37.46	20.08' LT	10
101+43.23	4.10' LT	12
101+61.10	4.14' LT	8
101+85.70	16.96' LT	10
102+14.08	0.89' RT	12
102+41.25	0.35' LT	12
102+47.09	0.66' LT	12
102+49.94	0.86' LT	15
103+96.36	2.19' RT	12
103+90.74	19.32' LT	15
103+91.37	35.38' LT	10
104+40.17	2.67' LT	15
104+80.93	6.06' LT	8
106+21.08	2.33' RT	12
108+94.77	36.89' LT	15

TREE REMOVAL SCHEDULE OVER 15 UNITS DIAMETER

STA.	OFFSET	UNITS
103+96.69	37.63' LT	18
104+15.65	7.21' LT	18
104+59.73	8.09' LT	20
106+48.52	8.68' LT	24
108+83.13	12.09' LT	38

PROPOSED TREE SCHEDULE

STATION	OFFSET	SPECIES*
102+21.39	27.16' LT	A
102+73.50	27.16' LT	B
103+32.08	27.29' LT	C
106+95.23	27.80' LT	D
107+94.13	29.07' LT	A
108+44.32	29.07' LT	B
109+39.77	29.02' LT	C
110+00.58	24.32' LT	D
100+70.41	26.15' RT	A
101+20.41	26.15' RT	B
101+70.41	26.15' RT	C
102+79.10	24.97' RT	D
103+29.10	26.48' RT	A
103+79.10	26.48' RT	B
104+37.94	26.62' RT	C
105+86.61	34.75' RT	D
106+45.79	27.77' RT	A
106+94.95	27.51' RT	B
107+45.82	27.51' RT	C
108+32.82	26.62' RT	D
108+83.00	26.62' RT	A
109+43.00	26.62' RT	B

*THE FOLLOWING TREE SPECIES SHALL BE USED:

A: TREE, CERCIS CANADENSIS (EASTERN REDBUD), 3" CALIPER, TREE FORM, BALLED AND BURLAPPED

B: TREE, MALUS PRAIRIFIRE (PRAIRIFIRE CRABAPPLE), 2-1/2" CALIPER, TREE FORM, BALLED AND BURLAPPED

C: TREE, SYRINGA RETICULATA (JAPANESE TREE LILAC), 2-1/2" CALIPER, TREE FORM, BALLED AND BURLAPPED

D: TREE, AMELANCHIER CANADENSIS (SHADBLOW SERVICEBERRY), 2" CALIPER, TREE FORM, BALLED AND BURLAPPED

PLAN
SURVEYED
PLOTTED
ALIGNMENT CHECKED
R.O.W. MARKED
FIELD BOOK
NOTE BOOK NO.
PLAN FILE NAME
BY
DATE

PROFILE
SURVEYED
PLOTTED
GRADES CHECKED
S.W.L. NOTED
STRUCTURE NOTATIONS CHKD
NOTE BOOK NO.
BY
DATE

PLOT DATE = $DATE$
FILE NAME = $FILEL$
PLOT SCALE = $SCALE$
USER NAME = $USER$

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

VILLAGE OF WESTMONT
59TH STREET RECONSTRUCTION

TREE SCHEDULE

SCALE: N.T.S.
DRAWN BY: JAL
DATE: 09/21/07
CHECKED BY: AJB