

PAVEMENT SCHEDULE

LOCATION	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70 1.5"	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	HOT-MIX ASPHALT BASE COURSE	AGGREGATE BASE COURSE TYPE B 12"	AGGREGATE BASE COURSE TYPE B 14"	AGGREGATE BASE COURSE TYPE B 18"	HOT-MIX ASPHALT BASE COURSE WIDENING 6.5"	BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)	TEMPORARY PAVEMENT	TEMPORARY RAMP	COMBINATION CONCRETE CURB AND GUTTER TYPE B6.24		CONCRETE MEDIAN TYPE SB-6.12	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	PAVEMENT REMOVAL	HOT-MIX ASPHALT SURFACE REMOVAL, 3/4"	TEMPORARY PAVEMENT REMOVAL	TEMPORARY REMP REMOVAL	COMBINATION CURB AND GUTTER REMOVAL		CONCRETE MEDIAN REMOVAL	PAVEMENT PATCHING, CLASS D, TYPE II, 6"	PAVEMENT PATCHING CLASS D, TYPE III, 6"	PAVEMENT PATCHING CLASS D, TYPE IV, 6"
	(TON)	(TON)	(TON)	(TON)	(TON)	(TON)	(SQ YD)	(GALLON)	(TON)	(SQ YD)	(SQ YD)	LEFT	RIGHT	(SQ FT)	(SQ YD)	(SQ YD)	(SQ YD)	(SQ YD)	(SQ YD)	(SQ YD)	LEFT	RIGHT	(SQ FT)	(SQ YD)	(SQ YD)
DOUGLAS ROAD																									
19+45.00 - 23+07.21	200										19						373								75
23+07.21 - 33+52.58	239										15	999.4	912.3				2676							17	162
33+52.58 - 43+02.59	532	887	2662	11086	3675		2884	6	348			857.0	930.9		6469			348				10		145	
43+02.59 - 46+72.90	231	385	1154	3486	2994		1250	3	197			308.2	288.5		1893			197						135	
46+72.90 - 54+24.03	422	704	2112	1250			2289	5	460			685.9	678.1		2522			460						156	
54+24.03 - 66+37.47	682	1136	3408	2018			3692	8	1209			1092.7	1139.2		3865			1209					14	164	
66+37.47 - 74+98.81	525	875	2624	9239		6927	2842	6	106			803.0	735.2		4074			106			295	13		161	
74+98.22 - 80+04.51/80+28.14	297	495	1486	930			1610	4	604			461.7	315.3	2572	2580			604			418	14		189	
80+04.51/80+28.14 - 83+34.53	226	377	1132	699			1227	3	179			230.9	182.5	2119	2580			179			233	194	20	163	
83+34.53 - 87+61.16	255	425	1275	801			1381	3	575			354.3	365.5	2135	2949			575			444	347	435		118
<b>SUBTOTAL - DOUGLAS ROAD</b>	<b>3609</b>	<b>5284</b>	<b>15853</b>	<b>29510</b>	<b>6669</b>	<b>6927</b>	<b>17174</b>	<b>38</b>	<b>3677</b>	<b>34</b>	<b>5793.0</b>	<b>5548.0</b>	<b>6827</b>	<b>373</b>	<b>26932</b>	<b>7540</b>	<b>3677</b>	<b>34</b>	<b>676</b>	<b>1255</b>	<b>435</b>	<b>51</b>	<b>71</b>	<b>1467</b>	
SIDE STREETS																									
OLD POST ROAD 498+62.36 - 500+61.47				34								92	162.7	71.3			290				174	70			42
MASON SQUARE ENTRANCE	13	22	65	43			70					59.5	46.9		163					59	57				
BARNABY DRIVE 100+90.00	26	44	131	82			142	0				75.2	75.5		261					68	71				
FARMINGTON LAKES DRIVE 200+30.86	37	62	187	128			202	0				87.9	77.0		491					90	199				
SAUGATUCK ROAD 301+19.74	24	40	121	77			131	0				75.0	75.1		297					28	31				
LONG BEACH ROAD 400+66.25 - 403+00.00	64	107	322	208			349	1				262.8	226.2		626					157	156				
WIESBROOK ROAD	21	35	105	68			114	0				74.8	69.0		245					73	64				
ENTRANCE 1	14	23	70	45			76	0				35.8	53.4		159					48	60	112			
FERNWOOD ROAD 503+62.78 - 601+19.62	76	126	379	240			410	1				219.3	273.3		948					252	155			38	
TOWNE'S CROSSING 700+95.43	36	61	182	114			197	0				83.5	73.3		502					132	117				
NORTH MERCHANTS DRIVE	15	24	73	47			79	0				45.8	44.0		132					30	43				
<b>SUBTOTAL - SIDE STREETS</b>		<b>545</b>	<b>1634</b>	<b>1087</b>			<b>92</b>	<b>1770</b>	<b>4</b>			<b>1182.0</b>	<b>1085.0</b>		<b>3824</b>	<b>612</b>				<b>1111</b>	<b>1022</b>	<b>112</b>	<b>38</b>	<b>42</b>	
<b>TOTAL</b>	<b>3609</b>	<b>5829</b>	<b>17487</b>	<b>30596</b>	<b>6669</b>	<b>6927</b>	<b>18944</b>	<b>41</b>	<b>3677</b>	<b>34</b>	<b>13608.0</b>			<b>662</b>	<b>30756</b>	<b>8152</b>	<b>3677</b>	<b>34</b>	<b>4064</b>	<b>547</b>	<b>51</b>	<b>109</b>	<b>1509</b>		

NOTE: SIDESTREET PAVEMENT REMOVAL IS INCLUDED WITH DRIVE-LANE PAVEMENT REMOVAL

PLAN  
NO. \_\_\_\_\_  
DATE \_\_\_\_\_  
BY \_\_\_\_\_  
SURVEYED \_\_\_\_\_  
GRADES CHECKED \_\_\_\_\_  
STRUCTURE NOTATIONS CHECKED \_\_\_\_\_  
NOTE BOOK NO. \_\_\_\_\_  
FILE NAME \_\_\_\_\_

PROFILE  
NO. \_\_\_\_\_  
DATE \_\_\_\_\_  
BY \_\_\_\_\_  
SURVEYED \_\_\_\_\_  
GRADES CHECKED \_\_\_\_\_  
STRUCTURE NOTATIONS CHECKED \_\_\_\_\_  
NOTE BOOK NO. \_\_\_\_\_  
FILE NAME \_\_\_\_\_

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**F.A.U. 2508 - DOUGLAS ROAD**  
**(U.S. RTE 34 TO U.S. RTE 30)**

**PAVEMENT SCHEDULE**

SCALE: VERT. \_\_\_\_\_  
HORIZ. \_\_\_\_\_  
DATE \_\_\_\_\_

DRAWN BY BAH  
CHECKED BY CRF