

DATE _____
 BY _____
 SURVEYED _____
 PLAN CHECKED _____
 NOTE BOOK _____
 NO. _____

CODE NO.	PAY ITEM	UNIT	QUANTITY	ROADWAY#		LIGHTING#		TRAFFIC SIGNALS			NON-PARTICIPATING
				70% FED 30% LA	70% FED 30% LA	70% FED 30% LA	70% FED 30% LA	BUTTERFIELD RD &# COMMONWEALTH LN	INTERCONNECT#	EMERGENCY VEHICLE PREEMPTION	
				0004	0021	0021	0021	100% ELMHURST	100% ELMHURST	0043	
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	176	176							
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	235	235							
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	84	84							
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	38	38							
40600990	TEMPORARY RAMP	SQ YD	142	142							
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	1,068	1,068							
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	566	566							
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	355	355							
42001300	PROTECTIVE COAT	SQ YD	2,986	2,986							
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	710	710							
42400800	DETECTABLE WARNINGS	SQ FT	96	96							
44000100	PAVEMENT REMOVAL	SQ YD	331	331							
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	4,275	4,275							
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	244	244							
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	2,060	2,060							
44000600	SIDEWALK REMOVAL	SQ FT	691	691							
44003100	MEDIAN REMOVAL	SQ FT	332	332							
44004250	PAVED SHOULDER REMOVAL	SQ YD	1,902	1,902							
44201737	CLASS D PATCHES, TYPE I, 8 INCH	SQ YD	200	200							
44201741	CLASS D PATCHES, TYPE II, 8 INCH	SQ YD	500	500							
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	12,020	12,020							
48101600	AGGREGATE SHOULDERS, TYPE B 8"	SQ YD	23	23							
48203015	HOT-MIX ASPHALT SHOULDERS, 4 1/2"	SQ YD	119	119							
48203023	HOT-MIX ASPHALT SHOULDERS, 6 1/2"	SQ YD	1,221	1,221							
50105220	PIPE CULVERT REMOVAL	FOOT	21	21							
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	1	1							
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	1	1							
54213666	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 21"	EACH	1	1							
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	612	612							
550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FOOT	10	10							
550A0110	STORM SEWERS, CLASS A, TYPE 1 21"	FOOT	52	52							
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	76	76							
550A0360	STORM SEWERS, CLASS A, TYPE 2 15"	FOOT	199	199							
55100500	STORM SEWER REMOVAL 12"	FOOT	13	13							
56106400	ADJUSTING WATER MAIN 8"	FOOT	20	20							
56106600	ADJUSTING WATER MAIN 12"	FOOT	20	20							

* STP (70% FED, 30% LA)
 CMAQ (80% FED, 20% LA)
 PER LOCAL AGENCY
 AGREEMENT

* SPECIALTY ITEM

** CONSTRUCTION TYPE CODE = 0042

FILE PATH: G:\CIBB\0808\Road\PHASE 2\Sheet\1712008-SHT-SumQty.dgn



USER NAME = katorenz	DESIGNED - TKS	REVISED - 12/12/12
FILE NAME = D:\X2008-SHT-SumQty.dgn	DRAWN - TKS	REVISED -
PLOT SCALE = 50.000 / in.	CHECKED - JMG	REVISED -
PLOT DATE = 12/17/2012	DATE = 10/22/2012	REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

BUTTERFIELD ROAD AT COMMONWEALTH LANE
 SUMMARY OF QUANTITIES

SCALE: NOT TO SCALE SHEET NO. 4 OF 108 SHEETS

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
3545	09-00170-00-CH	DUPAGE	108	4
FED. ROAD DIST. NO. 7 ILLINOIS FED. AID PROJECT			CONTRACT NO. 63742	