

PLAN SURVEYED BY DATE  
 NOTE BOOK NO. CHECKED BY  
 NO. 15407 FILE NAME

SUMMARY OF QUANTITIES				ROADWAY#	LIGHTING#	TRAFFIC SIGNALS			NON-PARTICIPATING
CODE NO.	PAY ITEM	UNIT	QUANTITY			BUTTERFIELD RD & COMMONWEALTH LN	INTERCONNECT#	EMERGENCY VEHICLE PREEMPTION	
				70% FED 30% LA	70% FED 30% LA	70% FED 30% LA	70% FED 30% LA	100% ELMHURST	100% ELMHURST
				0004	0021	0021	0021	0043	
56400500	FIRE HYDRANTS TO BE REMOVED	EACH	2					2	
56400825	FIRE HYDRANT WITH AUXILIARY VALVE, VALVE BOX AND TEE	EACH	2					2	
60107600	PIPE UNDERDRAINS 4"	FOOT	770	770					
60200105	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE I FRAME, OPEN LID	EACH	1	1					
60201330	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 23 FRAME AND GRATE	EACH	2	2					
60208230	CATCH BASINS, TYPE C, TYPE 23 FRAME AND GRATE	EACH	9	9					
60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE I FRAME, CLOSED LID	EACH	5	5					
60219000	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 8 GRATE	EACH	1	1					
60219530	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 23 FRAME AND GRATE	EACH	2	2					
60234200	INLETS, TYPE A, TYPE I FRAME, OPEN LID	EACH	1	1					
60236200	INLETS, TYPE A, TYPE 8 GRATE	EACH	3	3					
60261530	INLETS TO BE ADJUSTED WITH NEW TYPE 23 FRAME AND GRATE	EACH	2	2					
60265700	VALVE VAULTS TO BE ADJUSTED	EACH	3	3					
60500205	FILLING CATCH BASINS	EACH	2	2					
60600605	CONCRETE CURB, TYPE B	FOOT	27	27					
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	1,628	1,628					
60608600	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.06	FOOT	83	83					
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SO FT	652	652					
60619600	CONCRETE MEDIAN, TYPE SB-6.12	SO FT	2,995	2,995					
60624600	CORRUGATED MEDIAN	SO FT	144	144					
63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	188	188					
63000009	STEEL PLATE BEAM GUARDRAIL, TYPE B, 9 FOOT POSTS	FOOT	50	50					
63100167	TRAFFIC BARRIER TERMINAL, TYPE I (SPECIAL) TANGENT	EACH	1	1					
63200310	GUARDRAIL REMOVAL	FOOT	400	400					
66400105	CHAIN LINK FENCE, 4'	FOOT	304	304					
66400305	CHAIN LINK FENCE, 6'	FOOT	330	330					
66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	860	860					
66900450	SPECIAL WASTE PLANS AND REPORTS	L SUM	1	1					
66900530	SOIL DISPOSAL ANALYSIS	EACH	3	3					
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	9	9					
67100100	MOBILIZATION	L SUM	1	1					
70300100	SHORT TERM PAVEMENT MARKING	FOOT	2,552	2,552					
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SO FT	218	218					
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	29,727	29,727					
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1,089	1,089					
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	3,336	3,336					

\* STP (70% FED, 30% LA)  
 CMAQ (80% FED, 20% LA)  
 PER LOCAL AGENCY AGREEMENT

\* SPECIALTY ITEM

\*\* CONSTRUCTION TYPE CODE = 0042

FILE PATH = G:\C080\0808\Road\Phase 2\Sheets\020088-SHT-SumQty.dgn



USER NAME = kolorenz	DESIGNED - TKS	REVISED - 10/12/12
FILE NAME = 01X0088-SHT-SumQty.dgn	DRAWN - TKS	REVISED -
PLOT SCALE = 98/000 / 1 in.	CHECKED - JMG	REVISED -
PLOT DATE = 12/17/2012	DATE - 10/22/2012	REVISED -

STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION

BUTTERFIELD ROAD AT COMMONWEALTH LANE  
 SUMMARY OF QUANTITIES

SCALE: NOT TO SCALE SHEET NO. 5 OF 108 SHEETS

F.A.U. RTE. 3545	SECTION 09-0010-00-CH	COUNTY DUPAGE	TOTAL SHEETS 108	SHEET NO. 5
CONTRACT NO. 63742				
FED. ROAD DIST. NO. 7 ILLINOIS FED. AID PROJECT				