

PLAN SURVEYED BY DATE
 PLOTTED BY
 CHECKED BY
 DATE OF CHECK
 NO. OF WAX CHECKED
 CADD FILE NAME

SUMMARY OF QUANTITIES				ROADWAY#	LIGHTING#	TRAFFIC SIGNALS			NON-PARTICIPATING
CODE NO.	PAY ITEM	UNIT	QUANTITY			BUTTERFIELD RD & COMMONWEALTH LN	INTERCONNECT#	EMERGENCY VEHICLE PREEMPTION	
				70% FED 30% LA 0004	70% FED 30% LA 0021	70% FED 30% LA 0021	70% FED 30% LA 0021	100% ELMHURST 0021	100% ELMHURST 0043
87800420	CONCRETE FOUNDATION, TYPE E 42-INCH DIAMETER	FOOT	21			21			
88030020	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST-ARM MOUNTED	EACH	10			10			
88030110	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, MAST-ARM MOUNTED	EACH	2			2			
88030210	SIGNAL HEAD, LED, 2-FACE, 3-SECTION, BRACKET MOUNTED	EACH	2			2			
88030240	SIGNAL HEAD, LED, 2-FACE, 1-3 SECTION, 1-5 SECTION, BRACKET MOUNTED	EACH	2			2			
88102717	PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	2			2			
88102747	PEDESTRIAN SIGNAL HEAD, LED, 2-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	1			1			
88200210	TRAFFIC SIGNAL BACKPLATE, LOUVERED, ALUMINUM	EACH	12			12			
88500100	INDUCTIVE LOOP DETECTOR	EACH	12			12			
88600100	DETECTOR LOOP, TYPE I	FOOT	851			851			
88700200	LIGHT DETECTOR	EACH	3					3	
88700300	LIGHT DETECTOR AMPLIFIER	EACH	1					1	
88800100	PEDESTRIAN PUSH-BUTTON	EACH	4			4			
89000100	TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	1			1			
89502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	1,495		200		1,295		
89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	1			1			
89502380	REMOVE EXISTING HANDHOLE	EACH	11			11			
89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	10			10			
A2007120	TREE, QUERCUS RUBRA (RED OAK), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	2	2					
D2001772	EVERGREEN, PICEA ABIES (NORWAY SPRUCE), 6' HEIGHT, BALLED AND BURLAPPED	EACH	3	3					
K0029634	WEED CONTROL, PRE-EMERGENT GRANULAR HERBICIDE	POUND	1	1					
X0324085	EMERGENCY VEHICLE PRIORITY SYSTEM LINE SENSOR CABLE, NO. 20 3/C	FOOT	807					807	
X2090210	POROUS GRANULAR BACKFILL, SPECIAL	CU YD	170	170					
X2110100	TOPSOIL FURNISH AND PLACE, SPECIAL	CU YD	515	515					
X4403800	MEDIAN SURFACE REMOVAL	SO FT	7,823	7,823					
X5420612	PIPE CULVERTS TO BE CLEANED 12"	FOOT	89	89					
X5420624	PIPE CULVERTS TO BE CLEANED 24"	FOOT	104	104					
X5537800	STORM SEWERS TO BE CLEANED 12"	FOOT	72	72					
X5537900	STORM SEWERS TO BE CLEANED 15"	FOOT	218	218					
X6020096	MANHOLES, TYPE A, 6'-DIAMETER, WITH 2 TYPE 1 FRAME, CLOSED LID, RESTRICTOR PLATE	EACH	1	1					
X6026050	SANITARY MANHOLES TO BE ADJUSTED	EACH	3	3					
X6030310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	8	8					
X6330725	STEEL PLATE BEAM GUARDRAIL (SHORT RADIUS)	FOOT	89	89					
X6640300	CHAIN LINK FENCE REMOVAL	FOOT	700	700					
X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1					
X7030030	WET REFLECTIVE TEMPORARY TAPE TYPE III, 4 INCH	FOOT	10,851	10,851					

STP (70% FED, 30% LA)
 CMAQ (80% FED, 20% LA)
 PER LOCAL AGENCY
 AGREEMENT

- SPECIALTY ITEM
- CONSTRUCTION TYPE CODE = 0042

FILE PATH = G:\7\88\8888\Road\PHASE 2\Sheet\01A0008-SHT-SumQty.dgn



USER NAME = katoranz	DESIGNED - TKS	REVISED - 10/12/12
FILE NAME = 01A0008-SHT-SumQty.dgn	DRAWN - TKS	REVISED -
PLOT SCALE = 500.000 / 1 in.	CHECKED - JMG	REVISED -
PLOT DATE = 12/17/2012	DATE - 10/22/2012	REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

BUTTERFIELD ROAD AT COMMONWEALTH LANE
 SUMMARY OF QUANTITIES

SCALE: NOT TO SCALE SHEET NO. 8 OF 108 SHEETS

F.A.U. RTE. 3545	SECTION 09-00170-00-CH	COUNTY DJPAGE	TOTAL SHEETS 108	SHEET NO. 8
FED. ROAD DIST. NO. 7 ILLINOIS FED. AID PROJECT			CONTRACT NO. 63742	