

# SUMMARY OF QUANTITIES

50% IL  
50% IOWA

Qty Item Number	Description	Units	Total Quantity
			0014
Z0007101	CONTAINMENT AND DISPOSAL OF LEAD PAINT CLEANING RESIDUES NO.1	L SUM	1
Z0010501	CLEANING AND PAINTING STEEL BRIDGE NO. 1	L SUM	1
67100100	MOBILIZATION	L SUM	1
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MD	5
78300100	PAVEMENT MARKING REMOVAL	SO FT	2,334
70300220	TEMPORARY PAVEMENT MARKING-LINE4"	FOOT	7,000
70600250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	1
70400100	TEMPORARY CONCRETE BARRIER	FOOT	4,200
70100207	TRAFFIC CONTROL AND PROTECTION STANDARD 701402	EACH	1
70100420	TRAFFIC CONTROL AND PROTECTION STANDARD 701411	EACH	2

# GENERAL NOTES

The Contractor shall be responsible for protecting utility property during construction operations as outlined in Article 107.31 of the Standard Specifications. A minimum of 48 hours advance notice is required for non-emergency work. The JULIE number is 800-892-0123.

The SSPC OP1 & OP2 Contractor Certifications will be required for this contract.

Work on this project may be in progress at the same time as work on a structure rehabilitation, contract 64H33. Work on these projects shall be scheduled in a manner to eliminate or minimize any interference between the contractors.

10

FILE NAME : \\CENTRAL\Shared\2\BR\CONSTANTIN\64H1	USER NAME : bartesc 180 Painting\Cover Sheet.dgn PLOT SCALE : 5000.010 / in. PLOT DATE : Mon Oct 15 08:24:26 2012	DESIGNED - DRAWN - CHECKED - DATE -	REVISED - REVISED - REVISED - REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	Summary of Quantities	F.A.I. RTE. 1-80	SECTION 02 BRIDGE PAINTING 2012-2	COUNTY Rock Island	TOTAL SHEETS 46	SHEET NO. 2	CONTRACT NO. 64H81	FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT
SCALE:					SHEET NO. OF SHEETS STA. TO STA.							