

ROUTE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	11-00033-00-SW	MOULTRIE	44	4
FED. ROAD DIST. NO. 7		ILLINOIS	FED. AID PROJECT	
CONTRACT #95696				

SUMMARY OF QUANTITIES					
ITEM NO.	DESCRIPTION	UNIT	TOTAL QUANTITY	50% FEDERAL 50% LOCAL	80% FEDERAL 20% LOCAL
20800150	TRENCH BACKFILL	CU YD	8		8
35101400	AGGREGATE BASE COURSE, TYPE B	TON	100		100
42001300	PROTECTIVE COAT	SQ YD	2,590		2,590
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	16		16
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT.	17,366		17,366
42400300	PORTLAND CEMENT CONCRETE SIDEWALK 6 INCH	SQ FT	3,576		3,576
42400800	DETECTABLE WARNINGS	SQ FT	408		408
44000100	PAVEMENT REMOVAL	SQ YD	120		120
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	588		588
44000600	SIDEWALK REMOVAL	SQ FT.	25,204		25,204
50901780	PIPE HANDRAIL	FOOT	70		70
60234200	INLETS, TYPE A, TYPE 1 FRAME, OPEN LID	EACH	1		1
60236200	INLETS, TYPE A, TYPE 8 GRATE	EACH	1		1
60255500	MANHOLES TO BE ADJUSTED	EACH	4		4
60260500	INLETS TO BE ADJUSTED WITH NEW TYPE 3 FRAME AND GRATE	EACH	1		1
60261300	INLETS TO BE ADJUSTED WITH NEW TYPE 11 FRAME AND GRATE	EACH	1		1
60266800	VALVE BOXES TO BE ADJUSTED	EACH	12		12
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-5.12	FOOT	498		498
Δ 68900200	NON-SPECIAL WASTE DISPOSAL	CU YD	62		62
Δ 68900450	SPECIAL WASTE PLANS AND REPORTS	L SUM	1		1
Δ 68900530	SOIL DISPOSAL ANALYSIS	EACH	5		5
67100100	MOBILIZATION	L SUM	1		1
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1		1
70102622	TRAFFIC CONTROL AND PROTECTION, STANDARD 701502	L SUM	1		1

SUMMARY OF QUANTITIES					
ITEM NO.	DESCRIPTION	UNIT	TOTAL QUANTITY	50% FEDERAL 50% LOCAL	80% FEDERAL 20% LOCAL
Δ 81028350	UNDERGROUND CONDUIT, PVC, 2" DIA.	FOOT	747	747	
Δ 81028370	UNDERGROUND CONDUIT, PVC, 3" DIA.	FOOT	127	127	
Δ 81400100	HANDHOLE	EACH	9	9	
Δ 81603035	UNIT DUCT, 800V, 2-1/2" NO.5, 1/2" NO.6 GROUND, (XLP-TYPE USE), 1" DIA. POLYETHYLENE	FOOT	3,816	3,816	
Δ 81702415	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 3-1/2" NO. 6	FOOT	635	635	
Δ 82800300	LIGHTING CONTROLLER, POLE MOUNTED, 240VOLT, 30AMP	EACH	3	3	
Δ 83600200	LIGHT POLE FOUNDATION, 24" DIAMETER	FOOT	190	190	
* X0327018	DECORATIVE SIGN POST	EACH	17		17
* X2501000	SEEDING, CLASS 2 (SPECIAL)	ACRE	0.1		0.1
* X4240420	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH, SPECIAL	SQ FT	11,013		11,013
* X4240440	PORTLAND CEMENT CONCRETE SIDEWALK 6 INCH, SPECIAL	SQ FT	2,083		2,083
* X6024802	INLETS, TYPE B, WITH SPECIAL FRAME AND GRATE	EACH	1		1
* X6026200	INLETS TO BE ADJUSTED (SPECIAL)	EACH	3		3
* X7010218	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1		1
*	RELOCATE GUTTER DRAIN	EACH	12		12
*	WATER METER LIDS TO BE ADJUSTED	EACH	10		10
* Δ	LIGHT POLE, STREET & SIDEWALK, SPECIAL	EACH	31	31	
* Δ	LIGHT POLE, STREET, SPECIAL	EACH	7	7	
*	CLEAN AND SEAL EXISTING COLORED CONCRETE	SQ FT	7,834		7,834
*	PORTLAND CEMENT CONCRETE SIDEWALK RAMP	EACH	1		1
*	CONCRETE STEPS	EACH	3		3
*	CONCRETE STEPS	SQ FT	2,437		2,437

* SPECIAL PROVISION
Δ SPECIALTY ITEMS

M
engineering
G

MEANO & GRUNLOH ENGINEERS, LLC
114 WEST WASHINGTON
P.O. BOX 587
SPRINGFIELD, ILLINOIS 62401
PHONE: (217) 347-7282
(800) 577-2714
FAX: (217) 342-9438

File name: S:\DW\11-00033-00-SW\Quantities.dwg
Plot date: 11/27/12 at 07:35

SUMMARY OF QUANTITIES
SIDEWALK ENHANCEMENT
CITY OF SULLIVAN
SECTION 11-00033-00-SW
MOULTRIE COUNTY, ILLINOIS