


TRANSPORTATION BULLETIN



Illinois Department of Transportation

ADDENDUM NO. 1

Dated: January 9, 2013

For: Transportation Bulletin
Letting Date: January 18, 2013
Volume 15, No. 49r
Dated: December 1, 2012
REVISED: January 8, 2013

Item No. 2A – Separate Runway Circuits & Construct Vault

Illinois Valley Regional Airport
Peru, Illinois
LaSalle County
IL Project No.: **VYS-4177**
SBG Project No.: 3-17-0060-**B21**
Contract No.: **IL029**

REASON FOR ADDENDUM: Corrections to Regulator Type

The project documents are revised to reflect equipment revisions to the existing and specified Constant Current Regulators as described below.

TO ALL PLAN HOLDERS:

- 1) The existing 30KW regulator is an L-828W (Phasecut) SCR CCR, **not** Type L-829 (Synchro-Tap) as indicated in Section 109-2.19, C.5a on Page 19 of the Special Provisions. Convert to a 10KW, L-828S Synchro-Tap Style SCR CCR in accordance with the specifications.
- 2) The two new 20KW constant current regulators shall be Type L-828 Ferro, and **not** the monitored L-829, as specified in Section 109-2.19, C.5b on Page 19 of the Special Provisions and as shown on Plan Sheet 10 of 10. Also, these regulators will **not** require individual circuit breakers in the CCR cell.