

<b>ROUTE</b>	<b>SECTION</b>	<b>COUNTY</b>	<b>TOTAL SHEETS</b>	<b>SHEET NUMBER</b>
FAP 342	530CRC-PP	COOK	15	7

CONTRACT 62962

**SOUTHBOUND IL RTE. 53 EXTENSION**

PATCH LOCATION NUMBER	LANE	STATION	Southbound			TYPE
			SIZE (L X W)	AREA (SQ. YD.)		
1	2	489+25	15 x 12	20.0	III	
2	2	487+30	6 x 12	8.0	II	
3	2	484+96	20 x 12	26.67	III	
3A	2	483+25	8 x 12	10.67	II	
4	2	482+53	45 x 12	60.0	IV	
5	2	481+62	40 x 12	53.3	IV	
5A	1	481+40	30 x 12	40.0	IV	
6	2	480+98	12 x 12	16.0	III	
7	2	480+31	62 x 12	82.7	IV	
8	2	479+64	33 x 12	44.0	IV	
10	2	478+40	104 x 12	138.67	IV	
12	2	475+95	32 x 12	42.7	IV	
13	2	474+95	10 x 12	13.3	II	
14	2	473+67	120 x 12	160.0	IV	
14A	1	472+00	12 x 12	16.0	III	
14B	1	473+67	14 x 12	18.7	III	
17	2	471+31	14 x 12	18.7	III	
18	2	469+80	10 x 12	13.3	II	
19	2	468+53	110 x 12	146.67	IV	
22	2	464+79	9 x 12	12.0	II	
23	2	462+93	12 x 12	16.0	III	

**SCHEDULE TOTALS**

CLASS D PATCHES, TYPE II	265 SQ YD
CLASS D PATCHES, TYPE III	300 SQ YD
CLASS D PATCHES, TYPE IV	1860 SQ YD
SAW CUTS	2270 FT

ILLINOIS DEPARTMENT OF TRANSPORTATION  
  
**IL ROUTE 53 EXTENSION  
PAVEMENT PATCHING SCHEDULE  
2 OF 2**