

SUMMARY OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
645	(105BR) 1-1	MARSHALL	9	3
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

100% STATE SAFETY-2A
MARSHALL COUNTY

CODE NO.	ITEM	UNIT	TOTAL
40603335	Hot - Mix Asphalt Surface Course, Mix " D ", N50	TON	25.2
44001005	Hot - Mix Asphalt Surface Removal	SQ YD	45
50400305	Precast Prestressed Concrete Deck Beams (17" Depth)	SQ FT	1091
50900905	Removing and Re-erecting Existing Railing	FOOT	79
58100200	Waterproofing Membrane System	SQ YD	168
58300100	PORTLAND CEMENT MORTAR FAIRING COURSE	FOOT	406
67000400	Engineer's Field Office, Type A	CAL MO	5
67100100	Mobilization	L SUM	1
70100405	Traffic Control and Protection Standard 701321	EACH	1
70100450	Traffic Control and Protection, Standard 701201	L SUM	1
70300220	Temporary Pavement Marking - Line 4"	FOOT	196
70301000	Work Zone Pavement Marking Removal	SQ FT	536
70400100	Temporary Concrete Barrier	FOOT	348
* 78001110	Paint Pavement Marking - Line 4"	FOOT	1,396
78300100	Pavement Marking Removal	SQ FT	67
89502500	Remove Temporary Traffic Signal Installation	EACH	1
X0301424	Silicone Joint Sealer	FOOT	40
X0320047	Removal of Existing Precast Prestressed Concrete Deck Beams	SQ FT	1095
X0320887	Polymer Concrete	CU FT	5
* X7200200	Wide Load Signing	L SUM	1
Z0001900	Asbestos Bearing Pad Removal	EACH	9
⊙ Z0030250	Impact Attenuators Temporary (Non-Redirection) Test Level 3	EACH	2

⊙ SFTY-3N
 ▲ * SPECIALTY ITEM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
 DATE 10-11-2006
 DRAWN BY BTS
 CHECKED BY

▲ REVISED 11/3/07

PLOT DATE * MONITOR
 PLOT SCALE * 1/8" = 1'-0"
 PLOT SCALE * 1/4" = 1'-0"
 REFERENCE * SHEET