

SCHEDULE OF QUANTITIES

CLASS A PATCHES

LOCATION #1 - I-57

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
:	::	***	18	11
STA. _____		TO STA. _____		
FED. ROAD DIST. NO. _____		ILLINOIS FED. AID PROJECT		

- 57 & 74
- D5 ANNUAL PATCHING 2007-3
- CHAMPAIGN, DOUGLAS, & VERMILION

STATION	DIRECTION	LANE	LENGTH (ft)	WIDTH (ft)	PATCH AREA				SAW CUTS 44213200 (ft)	TIE BARS Z0075300 (Each)	PATCHING REINFORCEMENT 44213000 (sq. yd)	HMA REM OVER PATCH 3.25 44002213 (sq. yd)	HMA REPLACEMENT OVER PATCHES 40601005 (Tons)
					TYPE I 7" (sq. yd)	TYPE II 7" (sq. yd)	TYPE III 7" (sq. yd)	TYPE IV 7" (sq. yd)					
150+16.61	NORTHBOUND	PL	30	6	0.0	0.0	20.0	0.0	84.0	15	20.0	21.3	3.9
152+96.45	NORTHBOUND	PL	25	6	0.0	0.0	16.7	0.0	74.0	13	16.7	18.0	3.3
154+54.85	NORTHBOUND	DL,LWL	80	6	0.0	0.0	0.0	53.3	184.0	40	53.3	54.7	9.9
155+76.29	NORTHBOUND	DL,LWL	8	6	0.0	5.3	0.0	0.0	40.0	0	5.3	6.7	1.2
156+39.65	NORTHBOUND	DL	8	12	0.0	10.7	0.0	0.0	64.0	0	10.7	13.3	2.4
157+66.37	NORTHBOUND	DL	6	6	4.0	0.0	0.0	0.0	36.0	0	4.0	5.3	1.0
162+15.17	NORTHBOUND	DL,LWL	16	6	0.0	10.7	0.0	0.0	56.0	0	10.7	12.0	2.2
170+96.93	NORTHBOUND	DL	6	6	4.0	0.0	0.0	0.0	36.0	0	4.0	5.3	1.0
201+11.81	NORTHBOUND	DL	18	12	0.0	0.0	24.0	0.0	84.0	0	24.0	26.7	4.9
211+51.97	NORTHBOUND	DL	10	6	0.0	6.7	0.0	0.0	44.0	0	6.7	8.0	1.5
227+72.93	NORTHBOUND	DL	10	12	0.0	13.3	0.0	0.0	68.0	0	13.3	16.0	2.9
257+56.13	NORTHBOUND	DL	12	6	0.0	8.0	0.0	0.0	48.0	0	8.0	9.3	1.7
262+41.89	NORTHBOUND	DL	10	6	0.0	6.7	0.0	0.0	44.0	0	6.7	8.0	1.5
263+52.77	NORTHBOUND	DL	6	12	0.0	8.0	0.0	0.0	60.0	0	8.0	10.7	1.9
264+31.97	NORTHBOUND	DL,LWL	26	6	0.0	0.0	17.3	0.0	76.0	13	17.3	18.7	3.4
269+59.97	NORTHBOUND	DL	8	6	0.0	5.3	0.0	0.0	40.0	0	5.3	6.7	1.2
281+37.41	NORTHBOUND	DL	12	12	0.0	0.0	16.0	0.0	72.0	0	16.0	18.7	3.4
281+69.09	NORTHBOUND	DL	6	12	0.0	8.0	0.0	0.0	60.0	0	8.0	10.7	1.9
296+42.21	NORTHBOUND	DL,LWL	6	6	4.0	0.0	0.0	0.0	36.0	0	4.0	5.3	1.0
325+99.01	NORTHBOUND	DL,LWL	12	6	0.0	8.0	0.0	0.0	48.0	0	8.0	9.3	1.7
328+20.77	NORTHBOUND	DL	8	12	0.0	10.7	0.0	0.0	64.0	0	10.7	13.3	2.4
335+54.69	NORTHBOUND	DL	8	6	0.0	5.3	0.0	0.0	40.0	0	5.3	6.7	1.2
366+01.25	NORTHBOUND	DL	6	6	4.0	0.0	0.0	0.0	36.0	0	4.0	5.3	1.0
412+58.21	NORTHBOUND	DL	6	6	4.0	0.0	0.0	0.0	36.0	0	4.0	5.3	1.0
430+48.13	NORTHBOUND	DL	6	12	0.0	8.0	0.0	0.0	60.0	0	8.0	10.7	1.9
433+17.41	NORTHBOUND	DL	8	6	0.0	5.3	0.0	0.0	40.0	0	5.3	6.7	1.2
450+07.01	NORTHBOUND	PL	6	12	0.0	8.0	0.0	0.0	60.0	0	8.0	10.7	1.9
455+50.85	NORTHBOUND	DL	6	12	0.0	8.0	0.0	0.0	60.0	0	8.0	10.7	1.9
540+72.77	NORTHBOUND	DL,LWL	6	6	4.0	0.0	0.0	0.0	36.0	0	4.0	5.3	1.0
SHEET TOTALS					24.0 (sq. yd)	136.0 (sq. yd)	94.0 (sq. yd)	53.3 (sq. yd)	1686.0 (ft)	81.0 (Each)	307.3 (sq. yd)	359.3 (sq. yd)	65.4 (Tons)

PLOT DATE = 10/25/2006
 FILE NAME = c:\projects\458206 (v.8)\70567 text.dgn
 PLOT SCALE = 42.3525' / IN.
 USER NAME = stults,j

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		SCHEDULE OF QUANTITIES SCALE: VERT. _____ HORIZ. _____ DATE _____
DRAWN BY _____		CHECKED BY _____