

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
:	::	:::	18	17
STA. _____		TO STA. _____		
FED. ROAD DIST. NO. _____		ILLINOIS FED. AID PROJECT		

# SCHEDULE OF QUANTITIES

## CLASS B PATCHES

### LOCATION #3 - I-74

- 57 & 74
- D5 ANNUAL PATCHING 2007-3
- CHAMPAIGN, DOUGLAS, & VERMILION

STATION	DIRECTION	LANE	LENGTH (ft)	WIDTH (ft)	PATCH AREA				DOWEL BARS Z0017100 (Each)	SAW CUTS 44213200 (ft)	TIE BARS Z0075300 (Each)	PAVEMENT FABRIC 44213100 (sq. yd)	HMA REM OVER PATCH 5 44002220 (sq. yd)	HMA REPLACEMENT OVER PATCHES 40601005 (Tons)
					TYPE I 10" (sq. yd)	TYPE II 10" (sq. yd)	TYPE III 10" (sq. yd)	TYPE IV 10" (sq. yd)						
1240+12.00	EASTBOUND	DL	6	12	0.0	8.0	0.0	0.0	20	48.0	0	0.0	10.7	3.0
1240+12.00	EASTBOUND	PL	6	12	0.0	8.0	0.0	0.0	20	48.0	0	0.0	10.7	3.0
1240+82.00	EASTBOUND	PL	15	12	0.0	0.0	20.0	0.0	20	66.0	8	20.0	22.7	6.3
1241+46.00	EASTBOUND	DL	8	12	0.0	10.7	0.0	0.0	20	52.0	0	0.0	13.3	3.7
1241+68.00	EASTBOUND	DL	10	12	0.0	13.3	0.0	0.0	20	56.0	0	0.0	16.0	4.5
1319+51.00	EASTBOUND	DL	6	12	0.0	8.0	0.0	0.0	20	48.0	0	0.0	10.7	3.0
1319+70.00	EASTBOUND	DL	6	12	0.0	8.0	0.0	0.0	20	48.0	0	0.0	10.7	3.0
1321+81.00	EASTBOUND	DL	20	12	0.0	0.0	0.0	26.7	20	76.0	10	26.7	29.3	8.2
1414+33.00	EASTBOUND	DL	12	12	0.0	0.0	16.0	0.0	20	60.0	0	16.0	18.7	5.2
1698+94.00	EASTBOUND	DL	8	12	0.0	10.7	0.0	0.0	20	52.0	0	0.0	13.3	3.7
1698+94.00	EASTBOUND	PL	8	12	0.0	10.7	0.0	0.0	20	52.0	0	0.0	13.3	3.7
1698+94.00	EASTBOUND	RAMP 210	8	12	0.0	10.7	0.0	0.0	20	52.0	0	0.0	13.3	3.7
1632+87.00	WESTBOUND	DL	8	12	0.0	10.7	0.0	0.0	20	52.0	0	0.0	13.3	3.7
1632+87.00	WESTBOUND	PL	8	12	0.0	10.7	0.0	0.0	20	52.0	0	0.0	13.3	3.7
1627+79.00	WESTBOUND	DL	6	12	0.0	8.0	0.0	0.0	20	48.0	0	0.0	10.7	3.0
1627+79.00	WESTBOUND	PL	6	12	0.0	8.0	0.0	0.0	20	48.0	0	0.0	10.7	3.0
1627+37.00	WESTBOUND	WB	6	12	0.0	8.0	0.0	0.0	20	48.0	0	0.0	10.7	3.0
1626+37.00	WESTBOUND	WB	6	12	0.0	8.0	0.0	0.0	20	48.0	0	0.0	10.7	3.0
1625+35.00	WESTBOUND	DL	6	12	0.0	8.0	0.0	0.0	20	48.0	0	0.0	10.7	3.0
1412+44.00	WESTBOUND	WB	15	12	0.0	0.0	20.0	0.0	20	66.0	8	20.0	22.7	6.3
SHEET TOTALS					0.0 (sq. yd)	149.3 (sq. yd)	56.0 (sq. yd)	26.7 (sq. yd)	400 (Each)	1068.0 (ft)	26.0 (Each)	82.7 (sq. yd)	285.3 (sq. yd)	79.9 (Tons)

### CLASS B PATCHING TOTALS

#### LOCATION #3 - I-74

PATCH AREA				DOWEL BARS Z0017100 (Each)	SAW CUTS 44213200 (ft)	TIE BARS Z0075300 (Each)	PAVEMENT FABRIC 44213100 (sq. yd)	HMA REM OVER PATCH 5 44002220 (sq. yd)	HMA REPLACEMENT OVER PATCHES 40601005 (Tons)
TYPE I 10" (sq. yd)	TYPE II 10" (sq. yd)	TYPE III 10" (sq. yd)	TYPE IV 10" (sq. yd)						
0.0 (sq. yd)	150.0 (sq. yd)	56.0 (sq. yd)	27.0 (sq. yd)	400 (Each)	1068.0 (ft)	26.0 (Each)	83.0 (sq. yd)	286.0 (sq. yd)	80.0 (Tons)

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

#### SCHEDULE OF QUANTITIES

SCALE: VERT.  
HORIZ.  
DATE

DRAWN BY  
CHECKED BY