

SUMMARY OF QUANTITIES

CODE NO.	DESCRIPTION	UNIT	TOTAL	0014 BRIDGE REPAIR 90% FED. 10% STATE	0021 UNDERPASS LIGHTING 90% FED. 10% STATE
52100520	ANCHOR BOLTS, 1"	EACH	64	64	
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	118	118	
55100500	STORM SEWER REMOVAL 12"	FOOT	100	100	
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	88	88	
60100945	PIPE DRAINS 12"	FOOT	38	38	
60200205	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	4	4	
60500050	REMOVING CATCH BASINS	EACH	4	4	
61000115	TYPE E INLET BOX, STANDARD 610001	EACH	4	4	
* 63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	FOOT	450	450	
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4	4	
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	4	4	
63200310	GUARDRAIL REMOVAL	FOOT	1,580	1,580	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4	4	
67100100	MOBILIZATION	L SUM	1	1	
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	4	4	
70200100	NIGHTTIME WORK ZONE LIGHTING	L SUM	1	1	
70400100	TEMPORARY CONCRETE BARRIER	FOOT	600	600	
72400720	RELOCATE SIGN PANEL - TYPE 2	SQ FT	24	24	
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	1,000	1,000	
* 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	1,300	1,300	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	14	14	
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	16	16	
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	16	16	
* 78200530	BARRIER WALL MARKERS, TYPE C	EACH	32	32	
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	4	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	30	30	
81100320	CONDUIT ATTACHED TO STRUCTURE 1" DIA. PVC COATED GALVANIZED STEEL	FOOT	449		449
81300220	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 6" X 6" X 4"	EACH	8		8
81300530	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 12" X 10" X 6"	EACH	4		4
81702110	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 10	FOOT	2,176		2,176
82107100	UNDERPASS LUMINAIRE, 70 WATT, HIGH PRESSURE SODIUM VAPOR	EACH	4		4
82107200	UNDERPASS LUMINAIRE, 100 WATT, HIGH PRESSURE SODIUM VAPOR	EACH	4		4
X0315541	REMOVE EXISTING LIGHTING SYSTEM	L SUM	1		1
Z0033028	MAINTENANCE OF LIGHTING SYSTEM	CAL MO	9		9
X2070304	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	225	225	
X5537800	STORM SEWERS TO BE CLEANED 12"	FOOT	210	210	
X7010216	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	L SUM	1	1	
X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1	1	
X7013820	TRAFFIC CONTROL SURVEILLANCE, EXPRESSWAYS	CAL DA	30	30	
* X7030030	WET REFLECTIVE TEMPORARY TAPE TYPE III, 4 INCH	FOOT	600	600	

* SPECIALTY ITEM
 Δ **NON-PARTICIPATING (100% STATE)**

DATE	
BY	
FINAL SURVEY	
NOTE BOOK	
NO.	
SUPERVISED	
TEMPLATE	
AREAS	
CHECKED	

DATE	
BY	
ORIGINAL SURVEY	
NOTE BOOK	
NO.	
SUPERVISED	
TEMPLATE	
AREAS	
CHECKED	

FILE NAME = D:\62P17-0002.dgn
 PLOT DATE = 11/17/2011
 PLOT SCALE = 50.0000' / IN.

CHRISTIAN-ROGE & ASSOCIATES, INC.
 ENGINEERS-PLANNERS-SURVEYORS
 211 WEST WACKER DRIVE
 CHICAGO, ILLINOIS 60606
 PHONE: (312)372-2023 FAX: (312)372-5274

DESIGNED - S.J.P./K.R.K.
 DRAWN - B.K.
 CHECKED -
 DATE - OCTOBER, 2011

REVISED -
 REVISED -
 REVISED -
 REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCALE: NONE		SHEET NO. 2 OF 3 SHEETS		STA.	TO STA.
F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
80	1415-803HB-R	COOK	51	4	
CONTRACT NO. 60P17					
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT					

SUMMARY OF QUANTITIES
CENTRAL AVENUE OVER I-80