



**NOTES:**

1. Existing reinforcement in the abutment to be cleaned and incorporated into proposed construction. Any reinforcement bars that are damaged during partial removal operations at the abutments shall be repaired or replaced using an approved bar splicer or anchorage system. Cost included with Concrete Removal.
2. The existing deck slab shall be removed a maximum of 3'-0" from the back of abutment in the direction of traffic in all locations.

**LEGEND**

- Concrete Removal
- Superstructure Removal

**BILL OF MATERIAL**

ITEM	UNIT	TOTAL
Concrete Removal	Cu. Yd.	3.0

N:\PROJECTS\0003377.00\0003377.06\Design\Structural\CAD\016-2818 14 Abutment Removal.dgn



USER NAME = rdanley	DESIGNED BWS	REVISED -
PLOT SCALE = 4.000000' / in.	CHECKED LVH	REVISED -
PLOT DATE = 10/25/2011	DRAWN RD	REVISED -
	CHECKED DL	REVISED -

**STATE OF ILLINOIS**  
**DEPARTMENT OF TRANSPORTATION**

**ABUTMENT REMOVAL**  
**STRUCTURE NO. 016-2818**

SHEET NO. S-14 OF S-17 SHEETS

F.A.I.L. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2742	3222-W-BR	COOK	51	39
CONTRACT NO. 62116				
ILLINOIS FED. AID PROJECT				