

SUMMARY OF QUANTITIES

SP	SPECIALTY TEM	CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	ROADWAY 0003	TRAFFIC SIGNALS 0021	TRAINEES 0042
		54213447	END SECTION 12"	EACH	1	1		
		54213459	END SECTIONS 24"	EACH	1	1		
		542A1069	PIPE CULVERT, CLASS A, TYPE 2 24"	FOOT	10	10		
		54214299	END SECTIONS, EQUIVALENT ROUND-SIZE 24"	EACH	2	2		
		550A0050	STORM SEWER CLASS A, TYPE 1 12"	FOOT	13	13		
		542A8209	PIPE CULVERTS, CLASS A, TYPE 2 EQUIVALENT ROUND-SIZE 24"	FOOT	90	90		
		60100060	CONCRETE HEADWALLS FOR PIPE DRAINS	EACH	15	15		
*		60109510	PIPE UNDERDRAINS, FABRIC LINED TRENCH 4"	FOOT	5,401	5,401		
		60260300	INLETS TO BE ADJUSTED WITH NEW TYPE 1 FRAME, OPEN LID	EACH	1	1		
		60603500	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.06	FOOT	79	79		
		60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	534	534		
		60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	1,184	1,184		
		60619600	CONCRETE MEDIAN, TYPE SB-6.12	SQ FT	1,326	1,326		
		60624600	CORRUGATED MEDIAN	SQ FT	139	139		
+		63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	212.5	212.5		
+		63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	1	1		
+		63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	1	1		
		63200310	GUARDRAIL REMOVAL	FOOT	310	310		
+		63500105	DELINEATORS	EACH	39	39		
		64200116	SHOULDER RUMBLE STRIPS, 16 INCH	FOOT	855	855		
		67100100	MOBILIZATION	L SUM	1	1		
		70106800	CHANGEABLE MESSAGE SIGN	CAL MO	16	16		
		70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SQ FT	274	274		
		70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	41,795	41,795		
		70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	396	396		
		70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	14,971	14,971		
		70400100	TEMPORARY CONCRETE BARRIER	FOOT	1,300	1,300		
		70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	1,000	1,000		
+		78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	546	546		
+		78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	7,909	7,909		
+		78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1,828	1,828		
+		78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	497	497		
+		78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	145	145		
+		78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	97	97		
+		78003110	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 4"	FOOT	1,945	1,945		
+		78003120	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 5"	FOOT	214	214		
+		78003130	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 6"	FOOT	98	98		
+		78003140	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 8"	FOOT	280	280		
+		78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	182	182		
+		78200410	GUARDRAIL MARKERS, TYPE A	EACH	4	4		
+		78200530	BARRIER WALL MARKERS, TYPE C	EACH	176	176		
+		78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	1	1		

PLAN	SURVEYED	DATE
	PLOTTED	
	CHECKED	
	BY	
	NOTE BOOK	
	NO. OF WAY CHECKED	
	CADD FILE NAME	

PROFILE	SURVEYED	DATE
	PLOTTED	
	CHECKED	
	BY	
	NOTE BOOK	
	NO. OF WAY CHECKED	
	STRUCTURE NOTATIONS CHECKED	

FILE NAME = D:\1157207-SHT-S00-02.DGN

USER NAME = malopez

DESIGNED - ML
DRAWN - BH

REVISED -
REVISED -

PLOT SCALE = #SCALE#
PLOT DATE = 11/29/2011

CHECKED - DW
DATE - 04-04-11

REVISED -
REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**RANDALL ROAD AT US ROUTE 20 (FOOTHILL ROAD)
SUMMARY OF QUANTITIES**

SCALE: NTS SHEET NO. 2 OF 4 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
336	06-00345-00-CH	KANE	92	6
CONTRACT NO. 63623				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				