

PAVEMENT SCHEDULE

LOCATION	HOT-MIX ASPHALT BASE COURSE 9 1/4" (SQ YD)	HOT-MIX ASPHALT BASE COURSE WIDENING 9 1/4" (SQ YD)	BITUMINOUS MATERIALS (PRIME COAT) (GAL)	LEVELING BINDER (MACHINE METHOD), N70 (TON)	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70 (TON)	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90 (TON)	STRIP REFLECTIVE CRACK CONTROL TREATMENT (FOOT)	AGGREGATE SHOULDERS, TYPE B 6" (SQ YD)	HOT-MIX ASPHALT SHOULDERS, 8" (SQ YD)	COMBINATION CONCRETE CURB AND GUTTER TYPE B-6.06 (FOOT)	COMBINATION CONCRETE CURB AND GUTTER TYPE B-6.24 (FOOT)	CONCRETE MEDIAN SURFACE, 4 INCH (SQ FT)	CONCRETE MEDIAN, TYPE SB-6.12 (SQ FT)	CORRUGATED MEDIAN, (SQ FT)	STEEL PLATE BEAM GUARDRAIL TYPE A, 6 FOOT POSTS (FOOT)	TRAFFIC BARRIER TERMINAL, TYPE 6 (EACH)
RANDALL ROAD (SOUTH)																
STA. 149+97.6 TO 157+38.0 (NORTH)	1025	68	1687	77	709.9	741.8	1000	188	762				56		212.5	1
STA. 157+38.0 TO 161+66.0	378	43	630	30	271.2	292.2	455	94	251				224			
FOOTHILL ROAD																
STA. 70+31.6 TO STA. 78+93.0	1428	150	1731	41	190.8	516.9	825	381	745		390					
US ROUTE 20																
STA. 2097+09.5 TO STA. 2110+29.2	3596	112	3412	15	591.6	523.5	1079	415	1744	79	144	1184	1046	139		
ADDITIONAL	193	12		5	52.9	62.2										
TOTAL	6620	385	7460	169	1817	2137	3359	1078	3502	79	534	1184	1326	139	212.5	1

PAVEMENT SCHEDULE

LOCATION	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT (EACH)	DELINEATORS (EACH)	SHOULDER RUMBLE STRIPS, 16 INCH (FOOT)	GUARDRAIL MARKERS, TYPE A (EACH)	TERMINAL MARKER DIRECT APPLIED (EACH)	AGGREGATE SUBGRADE 12" (SQ YD)	TEMPORARY PAVEMENT (SQ YD)
RANDALL ROAD (SOUTH)							
STA. 149+97.6 TO 157+38.0 (NORTH)	1			4	1	1904	16
STA. 157+38.0 TO 161+66.0						710	28
FOOTHILL ROAD							
STA. 70+31.6 TO STA. 78+93.0						2475	1101
US ROUTE 20							
STA. 2097+09.5 TO STA. 2110+29.2		39	855			5520	290
ADDITIONAL							0
TOTAL	1	39	855	4	1	10609	1435

DATE: _____
BY: _____
PLAN: _____
NO. _____
SHEET: _____
DATE: _____
BY: _____
PLAN: _____
NO. _____
SHEET: _____
DATE: _____
BY: _____
PLAN: _____
NO. _____
SHEET: _____

DATE: _____
BY: _____
PROFILE: _____
NO. _____
SHEET: _____
DATE: _____
BY: _____
PROFILE: _____
NO. _____
SHEET: _____

FILE NAME = D:\157207-SHT-SCH-02.dgn

USER NAME = melopez	DESIGNED - BH	REVISED -
PLOT SCALE = #SCALE#	DRAWN - ML	REVISED -
PLOT DATE = 11/29/2011	CHECKED - DWW	REVISED -
	DATE - 05-09-2011	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**RANDALL ROAD AT US ROUTE 20 (FOOTHILL ROAD)
PAVEMENT AND PAVEMENT MARKING SCHEDULES**

SCALE: SHEET NO. 3 OF 4 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
336	06-00345-00-CH	KANE	92	13
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT			CONTRACT NO. 63623	