

SUMMARY OF QUANTITIES

Specialty_Item	PAY ITEM #	DESCRIPTION	UNIT	TOTAL QUANTITIES	0011 BRIDGE HENDERSON 80% FED. 20% STATE	0004 ROADWAY HENDERSON 80% FED 20% STATE	0004 ROADWAY HENDERSON 100% STATE
	20100500	TREE REMOVAL, ACRES	ACRE	1.5		1.5	
	20200100	EARTH EXCAVATION	CU YD	1527		1527	
	20400800	FURNISHED EXCAVATION	CU YD	6090		6090	
	21101615	TOPSOIL FURNISH & PLACE, 4"	SQ YD	22462		22462	
X	25000300	SEEDING, CLASS 3	ACRE	4.64		4.64	
X	25000400	NITROGEN FERTILIZER NUTRIENT	POUND	420		420	
X	25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	420		420	
X	25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	420		420	
X	25100105	MULCH, METHOD 1	ACRE	4.64		4.64	
	25100630	EROSION CONTROL BLANKET	SQ YD	100		100	
	28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	465		465	
	28000305	TEMPORARY DITCH CHECKS	FOOT	1460		1460	
	28000400	PERIMETER EROSION BARRIER	FOOT	3000		3000	
	28000500	INLET AND PIPE PROTECTION	EACH	3		3	
	28100705	STONE DUMPED RIPRAP, CLASS A3	SQ YD	570		570	
	28100109	STONE RIPRAP, CLASS A5	SQ YD	1080	1080		
	28200200	FILTER FABRIC	SQ YD	1080	1080		

\*SPECIALTY ITEM

FILE NAME = Summary of Quantities.dgn	USER NAME = lobbisdism	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>	F.A.S RTE. 1190	SECTION (125BY)BR	COUNTY KNOX	TOTAL SHEETS 94	SHEET NO. 4	
PLOT SCALE = 100,000' / in.	CHECKED -	REVISED -	SCALE:			SHEET NO.	OF	SHEETS	STA.	TO STA.	CONTRACT NO. 68087
PLOT DATE = 10/21/2011	DATE -	REVISED -	ILLINOIS FED. AID PROJECT								