

TABULATION OF PAVEMENT MARKING QUANTITIES									
LOCATION				EPOXY PAVEMENT MARKING - LINE 4"		SHORT TERM PAVEMENT MARKING	WORK ZONE PAVEMENT MARKING REMOVAL	TEMPORARY PAVEMENT MARKING - LINE 4"	
				FT YELLOW	FT WHITE			FT	SQ FT
EDGE LINE RT/LT	STA. 142+00	TO	STA. 156+50		2900				2900
LT CENTER LINE	STA. 142+00	TO	STA. 146+50	450		580	48	450	
RT CENTER LINE	STA. 151+00	TO	STA. 156+50	550				550	
SKIP CNTR LINE	STA. 142+00	TO	STA. 156+50	365				365	
SUB-TOTAL				1365	2900	580	48	1365	2900
TOTAL				4265		580	48	4265	

FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS			
LOCATION	OFFSET	LT/RT	EACH
STA. 142+00	40.09	LT	1
STA. 143+10	100.00		1
STA. 143+50	110.00		1
STA. 146+00	85.00		1
STA. 149+40	85.00		1
STA. 150+74	130.57		1
STA. 151+39	130.60		1
STA. 152+00	45.00		1
STA. 154+00	45.00		1
STA. 145+42	40.77	1	
TOTAL			17

PERMANENT SURVEY MARKERS, TYPE I	
LOCATION	EACH
ON STRUCTURE AS DIRECTED BY THE ENGINEER	1
TOTAL	1

LAY OUT INFORMATION FOR THE PRIVATE ENTRANCE AT STA. 153+00									
SEGMENT	ELEMENT								
	RADIUS					LINE			
	R	PC		PT		BEGINNING		END	
	FT	STA.	OFFSET	STA.	OFFSET	STA.	OFFSET	STA.	OFFSET
A	20	STA. 125+25	11.0	STA. 152+32	49.6				
B						STA. 152+32	49.58	STA. 151+97	63.8
C	70	STA. 151+97	63.8	STA. 151+65	88.7				
D	55	STA. 151+75	95.6	STA. 152+20	73.6				
E	50	STA. 152+20	73.6	STA. 152+61	54.2				
F	75	STA. 152+61	54.2	STA. 153+20	25.0				
G	40	STA. 153+20	25.0	STA. 153+50	11.0				

THIS TABLE IS USED ON THE PLAN 01 SHEET ONLY NOT AS A PART OF THE SCHEDULE