

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**SUMMARY OF QUANTITIES**

CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0005 ALTON 3P	0005 MADISON COUNTY 3P	0004 MADISON COUNTY 3R	0021 SIGNALS				
				1746							
20800150	TRENCH BACKFILL	CU YD	184			184					
35101600	AGGREGATE BASE COURSE, TYPE B 4"	SQ YD	10799	3710	845	6244					
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	8.7			8.7					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	46.9	34.5	4.8	7.6					
40600300	AGGREGATE (PRIME COAT)	TON	224.8	165.5	23.1	36.2					
40600821	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	8742.4	6179.7	862.7	1700					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	16363.6	12543.5	2750.9	1069.2					
40600990	TEMPORARY RAMP	SQ YD	1334.6	890.8	207.3	236.5					
40603545	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	12592.1	9269.5	1294	2028.6					
40800020	BITUMINOUS MATERIALS (PRIME COAT)	TON	63.85	56.67	7.18						
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	1966.5	1415.9	273	277.6					
42000500	PORTLAND CEMENT CONCRETE PAVEMENT 10"	SQ YD	1355	510	845						
42000501	PORTLAND CEMENT CONCRETE PAVEMENT 10" (JOINTED)	SQ YD	9444	3200		6244					
42001200	PAVEMENT FABRIC	SQ YD	1488.4	510	845	133.4					
42001300	PROTECTIVE COAT	SQ YD	7950	7395.6	554.4						
44000100	PAVEMENT REMOVAL	SQ YD	7580	4555		3025					
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	4431	4431							
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	9981	4120	550	5311					
44003100	MEDIAN REMOVAL	SQ FT	51950	16850	3800	31300					
44022025	PARTIAL DEPTH REMOVAL 2"	SQ YD	7446.1	5385.6	673.3	1387.2					
44200553	CLASS A PATCHES, TYPE II, 10 INCH	SQ YD	13.3	13.3							
44200557	CLASS A PATCHES, TYPE III, 10 INCH	SQ YD	72	72							
44200559	CLASS A PATCHES, TYPE IV, 10 INCH	SQ YD	653.3	653.3							
44200970	CLASS B PATCHES, TYPE II, 10 INCH	SQ YD	522.7	32	240	250.7					
44200974	CLASS B PATCHES, TYPE III, 10 INCH	SQ YD	80		48	32					
44200976	CLASS B PATCHES, TYPE IV, 10 INCH	SQ YD	53.4			53.4					
44201299	DOWEL BARS 1 1/2"	EACH	1360	80	660	620					
44213000	PATCHING REINFORCEMENT	SQ YD	738.6	738.6							
44213200	SAW CUTS	FOOT	5416	2164	1632	1620					
44213202	TIE BARS 1"	EACH	3393	178		3215					
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	1033	906	127						

REVISOR 1-5-2012

FILE NAME =	USER NAME = karlosal	DESIGNED -	REVISED -
c:\pwork\pwork\karlosal\0260664\d076080_2-shr-plan.dgn		DRAWN -	REVISED -
PLOT SCALE = 50.0000' / 1"		CHECKED -	REVISED -
PLOT DATE = 9/12/2011		DATE -	REVISED -

STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
785	(132-2,3,4 133-1)RS	MADISON	122	4
CONTRACT NO. 76B80				
ILLINOIS FED. AID PROJECT				