



# Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

January 5, 2023

SUBJECT: Route FAU 4309 (Crete Road)  
Section 15-00049-00-PV (Crete)  
Will County  
Contract No. 61H99  
Item 106  
January 20, 2023 Letting  
Addendum B

## NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

- 1. Revised sheets 3, 6, 10 & 18 – 23 of the Plans.**
- 2. Revised the Schedule of Prices.**
- 3. Revised page 1 of the Table of Contents to the Special Provisions.**
- 4. Added page 14A to the Special Provisions.**

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read 'Jack A. Elston'.

Jack A. Elston, P.E.  
Bureau Chief, Design and Environment

**SPECIAL PROVISIONS**

**TABLE OF CONTENTS**

LOCATION OF PROJECT..... 1

DESCRIPTION OF PROJECT..... 1

MAINTENANCE OF ROADWAYS (D1)..... 1

WORK HOURS ..... 1

COORDINATION/SCHEDULING OF WORK ..... 2

CONTRACTOR COOPERATION ..... 2

WATER USE ..... 3

STATUS OF UTILITIES (DISTRICT 1)..... 4

DUST CONTROL ..... 7

TRAFFIC CONTROL PLAN (D1)..... 7

DEWATERING ..... 8

EXISTING DRAINAGE FACILITIES ..... 8

SAW CUT JOINTS ..... 8

TOPSOIL STRIPPING..... 8

HOT-MIX ASPHALT DRIVEWAY PAVEMENT, 4” ..... 9

PROPOSED STORM SEWER CONNECTION TO EXISTING MANHOLE ..... 9

ADJUSTING WATER MAIN ..... 9

FIRE HYDRANTS TO BE ADJUSTED ..... 11

TREE AND BRUSH REMOVAL..... 12

REMOVE SIGN PANEL ASSEMBLY – TYPE A..... 12

PROCESSING LIME STABILIZED SOIL MIXTURE 12”..... 12

EXPLORATORY EXCAVATION..... 12

DRAINAGE & UTILITY STRUCTURES TO BE ADJUSTED ..... 13

STUMP REMOVAL..... 13

PUBLIC CONVENIENCE AND SAFETY (D1)..... 13

AVAILABLE REPORTS ..... 14

WATER MAIN QUALITY STORM SEWER..... 14A

TEMPORARY TRAFFIC SIGNAL TIMING ..... 15

**WATER MAIN QUALITY STORM SEWER**

This work shall be completed in accordance with Section 550 of the Standard Specifications.

This work shall be required for storm sewer installation along the eastern curb line where proposed storm sewer is called for installation within 10 feet of the existing water main. For these locations, storm sewers shall be installed with rubber gasketed joints in accordance with ASTM C443.

For locations beyond 10 feet from existing water mains, mastic joints shall be allowed and will be paid for via other pay items.

This item shall be measured for payment in accordance with Section 550.09.

This work will be paid for at the contract unit price per FOOT for STORM SEWERS, of the type specified, WATER MAIN QUALITY PIPE, of the size specified and shall include all materials, equipment, and labor required to complete the work as specified above.

1