

60468

60468

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1300	5BRS-3	COOK	23	3
FED. ROAD DIST. NO. 1		ILLINOIS	HIGHWAY PROJECT	
D-91-358-97				

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	100% STATE CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		URBAN I 000-2A				
35500300	BITUMINOUS BASE COURSE 6"	SQ YD	40	40				
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	20	20				
40600300	AGGREGATE (PRIME COAT)	TON	45	45				
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS	TON	3	3				
X4067100	POLYMERIZED LEVELING BINDER (MACHINE METHOD) SUPERPAVE, IL-4.75, NSO	TON	1100	1100				
X4066548	POLYMERIZED BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX 'F', N90	TON	1880	1880				
40600895	CONSTRUCTING TEST STRIP	EACH	3	3				
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	258	258				
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	150	150				
40601000	BITUMINOUS REPLACEMENT OVER PATCHES	TON	210	210				
X4421000	PARTIAL DEPTH PACHING	TON	135	135				
42001300	PROTECTIVE COAT	SQ YD	200	200				
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	40	40				
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SO FT	750	750				
44000007	BITUMINOUS SURFACE REMOVAL 2"	SQ YD	6500	6500				
44000112	BITUMINOUS REMOVAL OVER PATCHES 3"	SQ YD	1160	1160				
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	40	40				
44000600	SIDEWALK REMOVAL	SQ FT	750	750				
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	200	200				
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SQ YD	750	750				
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SQ YD	160	160				
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SQ YD	250	250				
X0321020	PORTLAND CEMENT CONCRETE SURFACE REMOVAL (COLD MILLING) VARIABLE DEPTH	SQ YD	2350	2350				
55039700	STORM SEWERS TO BE CLEANED	FOOT	500	500				
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	20	20				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6				
67100100	MOBILIZATION	L SUM	1	1				

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	100% STATE CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		URBAN I 000-2A				
70102620	TRAFFIC CONTROL AND PROTECTION STANDARD 701501	L SUM	1	1				
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1				
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1				
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1				
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1				
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	15	15				
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	2000	2000				
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	182	182				
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	9000	9000				
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1460	1460				
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	100	100				
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	350	350				
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	700	700				
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	182	182				
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	9000	9000				
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1460	1460				
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	100	100				
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	350	350				
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	320	320				
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	300	300				
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	1200	1200				
X0322256	TEMPORARY INFORMATION SIGNING	SO FT	85	85				
X4422025	PARTIAL DEPTH REMOVAL 2"	SQ YD	1170	1170				
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	20	20				
G0251740	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE 24 FRAME AND GRATE	EACH	10	10				
G0252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	7	7				

\* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
SUMMARY OF QUANTITIES  
CENTRAL ROAD

PLOT DATE: 09/14/99

09/14/99 09:46:33 AM D:\1108\60468\60468.dwg