

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90/94	2003-0311	COOK	976	10
STA.	TO STA.			
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		

62583

SUMMARY OF QUANTITIES						
CODE NO.	ITEM	UNIT	90% FED	QUANTITIES		
			10% STATE	CIVIL	LIGHTING	SURVEILLANCE
			URBAN	J000	Y030-1E	Y032-1F
X0324012	NEW DMS - CHICAGO RIVER	L SUM	1	0	0	1
X0324013	TEMPORARY DETECTION STATION	EACH	18	0	0	18
X0324014	TEMPORARY DETECTION SYSTEM, REMOVE AND SALVAGE	L SUM	1	0	0	1
X0324015	TEMPORARY DETECTION SYSTEM MONTHLY MAINTENANCE	CAL MO	33	0	0	33
X0324016	TEMPORARY DETECTION HUB	EACH	4	0	0	4
X0324017	TEMPORARY DETECTION HUB, RELOCATE	EACH	1	0	0	1
X0324018	CCTV DISTRIBUTION SUBSYSTEM, COMCENTER	L SUM	1	0	0	1
X0324019	CCTV DISTRIBUTION SUBSYSTEM, TRAFFIC SYSTEMS CENTER	L SUM	1	0	0	1
X0324020	CCTV DISTRIBUTION SUBSYSTEM, I-80 AT STATE LINE	L SUM	1	0	0	1
X0324021	CCTV DISTRIBUTION SUBSYSTEM, I-57 AT I-294	L SUM	1	0	0	1
X0324022	CCTV DISTRIBUTION SUBSYSTEM, I-57 AT I-94	L SUM	1	0	0	1
X0324023	CCTV DISTRIBUTION SUBSYSTEM, I-55 AT I-94	L SUM	1	0	0	1
X0324024	CCTV DISTRIBUTION SUBSYSTEM, HILLSIDE	L SUM	1	0	0	1
X0324025	CCTV DISTRIBUTION SUBSYSTEM, EMERGENCY TRANSPORTATION PATROL	L SUM	1	0	0	1
X0324026	TRAFFIC SURVEILLANCE SYSTEM, TRAFFIC SYSTEMS CENTER	L SUM	1	0	0	1
X0324027	TRAFFIC SURVEILLANCE SYSTEM, I-57 AT I-94	L SUM	1	0	0	1
X0324028	TRAFFIC SURVEILLANCE SYSTEM, I-55 AT I-94	L SUM	1	0	0	1
X0324029	HIGHWAY ADVISORY RADIO CENTRAL SYSTEM UPGRADE	L SUM	1	0	0	1
X0324030	HIGHWAY ADVISORY RADIO COMMUNICATIONS EQUIPMENT	L SUM	1	0	0	1
X0324031	UNINTERRUPTIBLE POWER SUPPLY UPGRADE	L SUM	1	0	0	1
X0324032	GENERATOR PACKAGED STANDBY ENGINE GENERATOR SYSTEM, INSTALLATION ONLY	EACH	3	0	0	3
X0324033	PACKAGED STANDBY ENGINE GENERATOR SYSTEM, REIMBURSEMENT ONLY	L SUM	1			1
X0324033	TRANSFER SWITCH	EACH	3	0	0	3
X0324034	TEMPORARY DYNAMIC MESSAGE SIGN SYSTEM	L SUM	1	0	0	1
X0324035	LED DYNAMIC MESSAGE SIGN FULL-MATRIX CONFIGURATION	EACH	7	0	0	7
X0700200	ELECTRIC CABLE ASSEMBLY IN CONDUIT, 600V (EPR-TYPE TC) 3/C NO. 2/0 AND NO. 6 GROUND	FOOT	5,577	0	0	5,577
X0700210	ELECTRIC CABLE ASSEMBLY IN CONDUIT, 600V (EPR-TYPE TC) 3/C NO. 4/0 AND NO. 4 GROUND	FOOT	1,864	0	0	1,864
X0700220	ELECTRIC CABLE ASSEMBLY IN CONDUIT, 600V (EPR-TYPE TC) 3/C NO. 4/0 AND NO. 2 GROUND	FOOT	782	0	0	782
X0730240	ELECTRIC CABLE IN CONDUIT NO. 18 4PR, TWISTED, SHIELDED	FOOT	2,177	0	0	2,177
X0324036	AUTOMATED TRAFFIC RECORDER CABINET	EACH	2	0	0	2
X0324097	SOIL STABILIZERS	LBS	112,152	112,152	0	0
X0324098	APPLYING DUST SUPPRESSION AGENT	UNIT	41	41	0	0
X0324057	CIRCUIT BREAKER, 2-POLE, 50-AMPERE, 240 VOLT IN EXISTING METER PEDESTAL CABINET	EACH	1	0	0	1



Rev. 12-29-04

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 F.A.I. 90/94 (DAN RYAN EXPRESSWAY)
 31st STREET TO I-57

SUMMARY OF QUANTITIES

SCALE: NONE
 DATE: October 29, 2004

DRAWN BY: CJM
 CHECKED BY: JPC

12/01/2004 09:31:58 AM