

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90/94	2003-0311	COOK	976	6
STA.	TO STA.			
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		

62583

SUMMARY OF QUANTITIES						
CODE NO.	ITEM	UNIT	90-FED. 101-STATE	QUANTITIES		
			URBAN	CIVIL	LIGHTING	SURVEILLANCE
			QUANTITY	J000	Y030-1E	Y032-1F
83600200	LIGHT POLE FOUNDATION, 24" DIA.	FOOT	243	0	243	0
83700250	LIGHT TOWER FOUNDATION, 44" DIAMETER	FOOT	1,872	0	1,872	0
84100110	REMOVAL OF TEMPORARY LIGHTING UNITS	EACH	24	0	24	0
84200500	REMOVAL OF EXISTING LIGHTING UNIT, SALVAGE	EACH	668	0	668	0
84200705	LIGHTING FOUNDATION REMOVAL, PARTIAL	EACH	24	0	24	0
84500110	REMOVAL OF LIGHTING CONTROLLER	EACH	8	0	8	0
84500120	REMOVAL OF ELECTRIC SERVICE INSTALLATION	EACH	8	0	8	0
84500130	REMOVAL OF LIGHTING CONTROLLER FOUNDATION	EACH	8	0	8	0
86300400	CONTROLLER CABINET TYPE IV	EACH	2	0	0	2
87000212	ELECTRIC CABLE ASSEMBLY IN CONDUIT, 600V (EPR-TYPE TC) 3/C NO. 2 AND NO. 6 GROUND	FOOT	1,005	0	0	1,005
87302405	ELECTRIC CABLE AERIAL SUSPENDED, COMMUNICATIONS, NO. 18 3 PAIR	FOOT	800	0	0	800
87502100	TRAFFIC SIGNAL POST, PAINTED STEEL 2.5 FT	EACH	9	0	0	9
87502207	TRAFFIC SIGNAL POST, PAINTED STEEL 5 FT.	EACH	20	0	0	20
87502210	TRAFFIC SIGNAL POST, PAINTED STEEL 7 FT	EACH	9	0	0	9
87800200	CONCRETE FOUNDATION, TYPE D	FOOT	9	0	0	9
87900200	DRILL EXISTING HANDHOLE	EACH	18	0	0	18
88600300	DETECTOR LOOP, TYPE III	FOOT	780	0	0	780
89502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	1,050	0	0	1,050
89502350	REMOVE AND REINSTALL ELECTRIC CABLE FROM CONDUIT	FOOT	3,605	0	0	3,605
X0321973	MODIFY EXISTING SERVICE INSTALLATION	EACH	2	0	1	1
X0322300	ELECTRIC CABLE IN CONDUIT NO. 18 4/C, TWISTED, SHIELDED	FOOT	147,147	0	0	147,147
X0323360	WOODEN POLE REMOVAL	EACH	307	0	301	6
X0323363	ELECTRIC CABLE IN CONDUIT, NO. 12 3/C	FOOT	5,403	0	0	5,403
X0324790	ELECTRIC CABLE IN CONDUIT, NO. 19 12/C	FOOT	782	0	0	782
X0323426	SEDIMENT CONTROL, DRAINAGE STRUCTURE, INLET FILTER CLEANING	EACH	282	282	0	0
X0323574	MAINTAIN LIGHTING SYSTEM	CAL MO	33	0	33	0
X0323710	REMOVE CONDUIT ATTACHED TO STRUCTURE	FOOT	2,158	0	2,158	0
X0323900	CONCRETE FOUNDATION, TYPE 1	FOOT	191	0	0	191
X0323907	COMMUNICATIONS VAULT	EACH	27	0	0	27
X0323914	FIBER OPTIC CABLE SPLICE - LATERAL	EACH	52	0	0	52
X0323917	CABINET, MODEL 334	EACH	49	0	0	49



REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 F.A.I. 90/94 (DAN RYAN EXPRESSWAY)
 31st STREET TO I-57

SUMMARY OF QUANTITIES

SCALE: NONE
 DATE: October 29, 2004

DRAWN BY: CJM
 CHECKED BY: JPC

M:\V-40488-E\rev\6-Contr\2003\Contract 2500020042-4.rvt 12/07/2004 05:20:05 PM