

CONTRACT NO.: 62680				
FAP FAU	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2714	2003-095 RS	COOK	23	3
FED. ROAD DIST. NO. 1		ILLINOIS	HIGHWAY PROJECT	

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		100% STATE 25th AVE. I000				
20201006	GRADING AND SHAPING SHOULDERS	UNIT	40	40				
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	16	16				
40600300	AGGREGATE (PRIME COAT)	TON	79	79				
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	10	10				
40600895	CONSTRUCTING TEST STRIP	EACH	1	1				
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	152	152				
40601000	BITUMINOUS REPLACEMENT OVER PATCHES	TON	584	584				
42001300	PROTECTIVE COAT	SQ YD	133	133				
44000124	BITUMINOUS REMOVAL OVER PATCHES 6"	SQ YD	1737	1737				
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	825	825				
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SQ YD	800	800				
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SQ YD	750	750				
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SQ YD	550	550				
48101200	AGGREGATE SHOULDERS, TYPE B	TON	1075	1075				
50300130	PREFORMED JOINT SEAL 4"	FOOT	143	143				
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	22	22				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3				
67100100	MOBILIZATION	L SUM	1	1				
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701204	L SUM	1	1				
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701300	L SUM	1	1				
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1				
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1				
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	5	5				
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	7446	7446				
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	73	73				
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1				

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		100% STATE 25th AVE. I000				
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	20712	20712				
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	434	434				
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	66	66				
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1655	1655				
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	73	73				
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	20712	20712				
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	434	434				
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	66	66				
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	513	513				
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	513	513				
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	360	360				
X0321020	PORTLAND CEMENT CONCRETE SURFACE REMOVAL (COLD MILLING) VARIABLE DEPTH	SQ YD	9290	9290				
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	154.2	154.2				
X4066426	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N70	TON	3302	3302				
X4067100	POLYMERIZED LEVELING BINDER (MACHINE METHOD), SUPERPAVE, IL-4.75, N50	TON	1681	1681				
X4409410	BITUMINOUS SURFACE REMOVAL 2 1/4"	SQ YD	13662	13662				
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	41	41				
55039700	STORM SEWERS TO BE CLEANED	FOOT	1500	1500				
60404800	FRAMES AND GRATES TYPE 11	EACH	35	35				
60404805	FRAMES AND GRATES TYPE 11V	EACH	4	4				
60404400	FRAMES AND GRATES TYPE 4	EACH	2	2				
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	2	2				

* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
FAU 2714 - 25th AVE.
(I-290 TO 26th ST.)

Rev.

PLOT DATE: 10/27/2004